Project: PER Ridderkerk

Deerns

Ventilation	PoR
Public areas	35
Club areas	35
gym/spa	50

LBK/LAK

61.010 Basement and groundfloor
61.020 Hotel kamers
61.030 4e verdieping
61.040 5e verdieping

61.110 LAV toiletten
61.120 LAV afzuigkappen

Project: SOHO house Amsterdam
projectnr.: 150-01941-00-0002
Datum: 30-9-2015

Roomnr.	Room name	Opp.	height	occupancy		CAPACITY				Supply air						Return air						Exhaust air		
				m³/pp	calc.	persons	vv	-	result.	syst.	61.010	61.020	61.030	61.040		syst.	61.010	61.020	61.030	61.040		syst.	61.110	61.120
		[m²]	[m³]	[-]	[-]	[m³/h]	[1/h]	[m³/h]	[m³/h]	[-]	[m³/h]	[m³/h]	[m³/h]	[m³/h]		[-]	[m³/h]	[m³/h]	[m³/h]	[m³/h]		[-]	[m³/h]	[m³/h]
Souterrain																								
1K01	CV-ruimte	96,00	4,0				1		385	61.010	385	0	0	0		61.010	385	0	0	0			0	0
1K02	wasgoed	35,00	3,0			0	4		420	61.010	315	0	0	0			0	0	0	0		61.110	420	0
1K03	wasgoed	80,00	3,0			0			0	61.010	0	0	0	0			0	0	0	0		61.120	0	0
1K04	werkplaats	17,00	3,0	5	3	119			120	61.010	120	0	0	0		61.010	120	0	0	0			0	0
1K05	heren kleedkamer	45,00	3,0			0		300	300	61.010	300	0	0	0			0	0	0	0		61.110	300	0
1K06	vrouwen kleedkamer	47,00	3,0			0		300	300	61.010	300	0	0	0			0	0	0	0		61.110	300	0
1K07	toilet heren	11,00	3,0			0	6		200	61.010	135	0	0	0			0	0	0	0		61.110	200	0
1K08	toilet dames	10,00	3,0			0	6		180	61.010	120	0	0	0			0	0	0	0		61.110	180	0
1K09	filmkamer	94,00	3,0	5	19	658			660	61.010	660	0	0	0		61.010	660	0	0	0			0	0
1K10/18	behandelzone	69,00	3,0	5	14	483			485	61.010	485	0	0	0		61.010	485	0	0	0			0	0
1K19	fietsen	101,00	3,0						0		0	0	0	0			0	0	0	0			0	0
1K20	gasmeter	10,00	3,0						0		0	0	0	0			0	0	0	0			0	0
1K21	expeditie	41,00	3,0						0		0	0	0	0			0	0	0	0			0	0
1K22/23/24/48	inkoopzone E	35,00	3,0						0		0	0	0	0			0	0	0	0			0	0
1K26	noodtrappenhuis	8,00	3,0						0		0	0	0	0			0	0	0	0			0	0
1K30	vuilnis	12,00	3,0				20		720	61.010	720	0	0	0			0	0	0	0		61.110	720	0
1K31	voorruimte	20,00	3,0						0		0	0	0	0			0	0	0	0			0	0
1K32	gang	19,00	3,0				0,5	90	90	61.010	90	0	0	0			0	0	0	0			0	0
1K33	lobby	42,00	3,0				0,5		65	61.010	65	0	0	0			0	0	0	0			0	0
1K35	trap	7,00	3,0						0		0	0	0	0			0	0	0	0			0	0
1K36	filmbar	75,00	3,0	2	38	1313			1.315	61.010	1.315	0	0	0		61.010	1.315	0	0	0			0	0
1K37	voorruimte	12,00	3,0						0	61.010	0	0	0	0		61.010	0	0	0	0			0	0
1K38	kantoor	7,00	3,0	5	1	49			50	61.010	50	0	0	0		61.010	50	0	0	0			0	0
1K39	diensttrap	6,00	3,0						0		0	0	0	0			0	0	0	0			0	0
1K40	gang	107,00	3,0				1,0		325	61.010	325	0	0	0			0	0	0	0			0	0
1K41	bierkelder	16,00	3,0					100	100	61.010	100	0	0	0			0	0	0	0		61.110	100	0
1K42/43/44/45	koud opslag	14,00	3,0					200	200		0	0	0	0			0	0	0	0		61.110	200	0
1K46	opslag	5,00	3,0					50	50		0	0	0	0			0	0	0	0		61.110	50	0
											5.485	0	0	0			3.015	0	0	0			2.470	0
Groundfloor																								
0.01	Cecconis	344,00	4,5	2	172	6020			6.020	61.010	6.585	0	0	0			0	0	0	0			0	6.020
0.02/0.03/miva	toiletten	22,00	4,5				6		595	61.010	396	0	0	0			0	0	0	0		61.110	595	0
0.04	opslag	5,00	4,5				1,0		25		0	0	0	0		61.010	25	0	0	0			0	0
0.05	prive	32,00	4,5	5	6	224			225	61.010	225	0	0	0		61.010	225	0	0	0			0	0
0.06	kantoor	7,00	4,5	5	1	49	2,0		65	61.010	65	0	0	0		61.010	65	0	0	0			0	0
0.07	gang	4,00	4,5								0	0	0	0			0	0	0	0			0	0
0.08	koffers	4,00	4,5				0,5	25	25		0	0	0	0		61.010	25	0	0	0			0	0
0.09	prive	4,00	4,5	5	1	28	0,5		30	61.010	30	0	0	0		61.010	30	0	0	0			0	0
0.10	Alli's bar	185,00	4,5	5	37	1295			1.295	61.010	1.295	0	0	0		61.010	1.039	0	0	0			0	0
0.12/0.13/0.14	toiletten	28,00	4,5				6		760	61.010	504	0	0	0			0	0	0	0		61.110	760	0
0.15	glazenwas	7,00	4,5				6,0		190		0	0	0	0		61.010	190	0	0	0			0	0
0.16	entree	29,00	4,5								0	0	0	0			0	0	0	0			0	0
0.17	sluis	30,00	4,5				0,5		70	61.010	70	0	0	0			0	0	0	0			0	0
0.18	centrale hal	38,00	4,5				0,5		90	61.010	90	0	0	0			0	0	0	0			0	0
0.19	lobby	15,00	4,5				0,5		35	61.010	35	0	0	0			0	0	0	0			0	0
0.23	gang	23,00	4,5						0		0	0	0	0			0	0	0	0			0	0
0.24	receptie	11,00	4,5	5	2	77			80	61.010	80	0	0	0		61.010	80	0	0	0			0	0
0.25	prep kitchen	13,00	4,5						0	61.010	0	0	0	0			0	0	0	0		61.120	0	0
0.26	prep kitchen	16,00	4,5						0	61.010	0	0	0	0			0	0	0	0		61.120	0	0
0.27	Cowshed	144,00	4,5	5	29	1008			1.010	61.010	1.010	0	0	0		61.010	882	0	0	0			0	0
0.29	toilet	14,00	4,5				6		380	61.010	252	0	0	0			0	0	0	0		61.110	380	0
0.28/0.30/0.31	koude opslag	13,00	4,5						0		0	0	0	0			0	0	0	0			0	0
0.32	voorruimte	7,00	4,5	5	1	49			50	61.010	50	0	0	0			0	0	0	0			0	0
0.35	gang	27,00	4,5			0	0,5		65	61.010	65	0	0	0			0	0	0	0			0	0
0.36	glazenwas	14,00	4,5				6,0		380		0	0	0	0			0	0	0	0		61.120	0	380
0.38	berging	12,00	4,5				1,0		55		0	0	0	0		61.010	55	0	0	0			0	0
											10.752	0	0	0			2.616	0	0	0			1.735	6.400

131

Behoort bij ontwerpbesluit
BWT 1903953
Gemerkt 123

Gemeente Amsterdam
Centrum

Project: PER Ridderkerk

Deerns

Ventilation	PoR
Public areas	35
Club areas	35
gym/spa	50

LBK/LAK

61.010 Basement and groundfloor
61.020 Hotel kamers
61.030 4e verdieping
61.040 5e verdieping

61.110 LAV toiletten
61.120 LAV afzuigkappen

Project: SOHO house Amsterdam
projectnr.: 150-01941-00-0002
Datum: 30-9-2015

Roomnr.	Room name	Opp.	height	occupancy		CAPACITY				Supply air						Return air						Exhaust air		
				m²/pp	calc.	persons	vv	-	result.	syst.	61.010	61.020	61.030	61.040		syst.	61.010	61.020	61.030	61.040		syst.	61.110	61.120
		[m²]	[m³]	[-]	[-]	[m³/h]	[1/h]	[m³/h]	[m³/h]	[-]	[m³/h]	[m³/h]	[m³/h]	[m³/h]		[-]	[m³/h]	[m³/h]	[m³/h]	[m³/h]		[-]	[m³/h]	[m³/h]
first floor																								
1.01	kamer 1	23,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
1.02	kamer 2	21,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
1.03	kamer 3	20,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
1.04	kamer 4	20,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
1.05	kamer 5	19,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
1.06	kamer 6	19,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
1.07	kamer 7	18,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
1.08	kamer 8	36,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
1.09	kamer 9	36,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
1.10	kamer 10	36,00	3,8					125	125	61.020	0	110	0	0		61.020	0	125	0	0			0	0
1.11	kamer 11	38,00	3,8					125	125	61.020	0	110	0	0		61.020	0	125	0	0			0	0
1.12	kamer 12	42,00	3,8					125	125	61.020	0	110	0	0		61.020	0	125	0	0			0	0
1.13	kamer 13	82,00	3,8					125	125	61.020	0	110	0	0		61.020	0	125	0	0			0	0
1.14	kamer 14	24,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
1.15	kamer 15	20,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
1.16	kamer 16	26,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
1.17	kamer 17	26,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
1.18	kamer 18	26,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
1.19	kamer 19	26,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
1.20	kamer 20	25,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
1.21	kamer 21	35,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
1.22	kamer 22	24,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
1.23	kamer 23	25,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
1.24	noodtrap	15,00	3,8						0		0	0	0	0			0	0	0	0			0	0
1.25	gang	108,00	3,8					225	225	61.020	0	225	0	0			0	0	0	0			0	0
1.26	BOH/MEP	7,00	3,8	5	1	49	2,0		55	61.020	0	55	0	0		61.020	0	55	0	0			0	0
1.27	gang	79,00	3,8					75	75	61.020	0	75	0	0			0	0	0	0			0	0
1.29	centrale hal	15,00	3,8						0		0	0	0	0			0	0	0	0			0	0
1.30	sluis	15,00	3,8					15	15	61.020	0	15	0	0			0	0	0	0			0	0
1.31	sluis	15,00	3,8					30	30	61.020	0	30	0	0			0	0	0	0			0	0
											0	2.455	0	0			0	2.455	0	0			0	0
second floor																								
2.01	kamer 1	24,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.02	kamer 2	21,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.03	kamer 3	20,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.04	kamer 4	26,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.05	kamer 5	25,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.06	kamer 6	25,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.07	kamer 7	25,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.08	kamer 8	24,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.09	kamer 9	24,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.10	kamer 10	18,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.11	kamer 11	21,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.12	kamer 12	20,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.13	kamer 13	23,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.14	kamer 14	19,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.15	kamer 15	27,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.16	kamer 16	45,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.17	kamer 17	25,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.18	kamer 18	26,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.19	kamer 19	26,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.20	kamer 20	26,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.21	kamer 21	26,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.22	kamer 22	26,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.23	kamer 23	26,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.24	kamer 24	26,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.25	kamer 25	25,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.26	kamer 26	24,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.27	kamer 27	35,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.28	kamer 28	31,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.29	kamer 29	25,00	3,8					100	100	61.020	0	85	0	0		61.020	0	100	0	0			0	0
2.30	noodtrap	13,00	3,8						0		0	0	0	0			0	0	0	0			0	0
2.31	gang	146,00	3,8					405	405	61.020	0	405	0	0			0	0	0	0			0	0
2.32	sluis	16,00	3,8					30	30	61.020	0	30	0	0			0	0	0	0			0	0
2.33	BOH	12,00	3,8	5	2	84	2		95	61.020	0	95	0	0		61.020	0	95	0	0			0	0
2.40	trap	17,00	3,8						0		0	0	0	0			0	0	0	0			0	0
2.41	centrale hal	36,00	3,8						0		0	0	0	0			0	0	0	0			0	0
											0	2.995	0	0			0	2.995	0	0			0	0

Project: PER Ridderkerk

Deerns

Ventilation	PoR
Public areas	35
Club areas	35
gym/spa	50

LBK/LAK

61.010 Basement and groundfloor
61.020 Hotel kamers
61.030 4e verdieping
61.040 5e verdieping
61.110 LAV toiletten
61.120 LAV afzuigkappen

Project: SOHO house Amsterdam
projectnr.: 150-01941-00-0002
Datum: 30-9-2015

Roomnr.	Room name	Opp.	height	occupancy		CAPACITY				Supply air					Return air					Exhaust air		
				m²/pp	calc.	persons	vv	-	result.	syst.	61.010	61.020	61.030	61.040	syst.	61.010	61.020	61.030	61.040	syst.	61.110	61.120
		[m²]	[m³]	[-]	[-]	[m³/h]	[1/h]	[m³/h]	[m³/h]	[-]	[m³/h]	[m³/h]	[m³/h]	[m³/h]	[-]	[m³/h]	[m³/h]	[m³/h]	[m³/h]	[-]	[m³/h]	[m³/h]
Mezzanine																						
2A.01	kantoor	60,00	3,8	5	12	420	2		460	61.020	0	460	0	0	61.020	0	460	0	0		0	0
2A.02	MER	20,00	3,8					50	50	61.020	0	50	0	0	61.020	0	50	0	0		0	0
2A.03	sluis	5,00	3,8						0		0	0	0	0		0	0	0	0		0	0
2A.05	noodtrap	17,00	3,8						0		0	0	0	0		0	0	0	0		0	0
											0	510	0	0		0	510	0	0		0	0
third floor																						
3.01	kamer 1	22,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.02	kamer 2	21,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.03	kamer 3	20,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.04	kamer 4	26,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.05	kamer 5	25,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.06	kamer 6	25,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.07	kamer 7	25,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.08	kamer 8	24,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.09	kamer 9	24,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.10	kamer 10	18,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.11	kamer 11	21,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.12	kamer 12	20,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.13	kamer 13	23,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.14	kamer 14	19,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.15	kamer 15	27,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.16	kamer 16	45,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.17	kamer 17	25,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.18	kamer 18	26,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.19	kamer 19	26,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.20	kamer 20	26,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.21	kamer 21	26,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.22	kamer 22	26,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.23	kamer 23	26,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.24	kamer 24	26,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.25	kamer 25	25,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.26	kamer 26	24,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.27	kamer 27	35,00	3,8					100	100	61.020	0	85	0	0	61.020	0	100	0	0		0	0
3.28	gang	147,00	3,8					405	405	61.020	0	405	0	0		0	0	0	0		0	0
3.29	gang	20,00	3,8					50	50	61.020	0	50	0	0		0	0	0	0		0	0
3.30	noodtrap	12,00	3,8						0		0	0	0	0		0	0	0	0		0	0
3.31	patch	8,00	3,8					50	50		0	0	0	0	61.020	0	50	0	0		0	0
3.32	BOH	5,00	3,8	5	1	35	1		35	61.020	0	35	0	0	61.020	0	35	0	0		0	0
3.33	sluis	16,00	3,8						0		0	0	0	0		0	0	0	0		0	0
3.34	noodtrap	17,00	3,8						0		0	0	0	0		0	0	0	0		0	0
3.40	trap	17,00	3,8						0		0	0	0	0		0	0	0	0		0	0
3.41	centrale hal	36,00	3,8						0		0	0	0	0		0	0	0	0		0	0
											0	3.805	0	0		0	3.805	0	0		0	0
forth floor																						
4.01	kleedkamer dames	122,00	3,8	5	24	1220	6		2.785	61.030	0	0	1.854	0	61.030	0	0	2.785	0		0	0
4.02	SPA	78,00	3,8	5	16	780			780	61.030	0	0	780	0	61.030	0	0	780	0		0	0
4.03	kleedkamer heren	102,00	3,8	5	20	1020	6		2.330	61.030	0	0	1.550	0	61.030	0	0	2.330	0		0	0
4.04	noodtrap	17,00	3,8						0		0	0	0	0		0	0	0	0		0	0
4.05	sluis	15,00	3,8						0	61.030	0	0	0	0	61.030	0	0	0	0		0	0
4.07	wasserette	12,00	3,8	5	2	120			120		0	0	0	0	61.030	0	0	120	0		0	0
4.08	gang	92,00	3,8						0	61.030	0	0	0	0	61.030	0	0	0	0		0	0
4.09	noodtrap	12,00	3,8						0	61.030	0	0	0	0	61.030	0	0	0	0		0	0
4.10	Sportschool	354,00	3,8	5	71	3540			3.540	61.030	0	0	3.540	0	61.030	0	0	1.710	0		0	0
4.11	trap	17,00	3,8						0	61.030	0	0	0	0		0	0	0	0		0	0
4.12	receptie	39,00	3,8						0	61.030	0	0	0	0	61.030	0	0	0	0		0	0
4.13	studio 1	50,00	3,8	5	10	500			500	61.030	0	0	500	0	61.030	0	0	500	0		0	0
4.14	studio 2	54,00	3,8	5	11	540			540	61.030	0	0	540	0	61.030	0	0	540	0		0	0
4.15	winkel	10,00	3,8	2	5	250	0,5		250	61.030	0	0	250	0	61.030	0	0	250	0		0	0
											0	0	9.015	0		0	0	9.015	0		0	0

Project: PER Ridderkerk

Deerns

Ventilation	PoR
Public areas	35
Club areas	35
gym/spa	50

LBK/LAK

61.010 Basement and groundfloor
61.020 Hotel kamers
61.030 4e verdieping
61.040 5e verdieping

61.110 LAV toiletten
61.120 LAV afzuigkappen

Project: SOHO house Amsterdam
projectnr.: 150-01941-00-0002
Datum: 30-9-2015

Roomnr.	Room name	Opp.	height	occupancy		CAPACITY				Supply air					Return air					Exhaust air		
				m²/pp	calc.	persons	vv	-	result.	syst.	61.010	61.020	61.030	61.040	syst.	61.010	61.020	61.030	61.040	syst.	61.110	61.120
		[m²]	[m³]	[-]	[-]	[m³/h]	[1/h]	[m³/h]	[m³/h]	[-]	[m³/h]	[m³/h]	[m³/h]	[m³/h]	[-]	[m³/h]	[m³/h]	[m³/h]	[m³/h]	[-]	[m³/h]	[m³/h]
Fifth floor																						
5.01	spelruimte	166,00	3,8	2	83	2905			2.905	61.040	0	0	0	2.905		0	0	0	0		0	0
5.02	Club/restaurant	134,00	3,8	2	67	2345			2.345	61.040	0	0	0	2.345		0	0	0	0	61.120	0	5.250
5.03	Prep kitchen	38,00	3,8			0			0		0	0	0	0		0	0	0	0		0	0
5.04	noodtrap	19,00	3,8			0			0		0	0	0	0		0	0	0	0		0	0
5.05	sluis	6,00	3,8			0			0		0	0	0	0		0	0	0	0		0	0
5.06	spoelketuken	6,00	3,8			0	6		140	61.040	0	0	0	140	61.040	0	0	0	140		0	0
5.08	bibliotheek	49,00	3,8	5	10	343			345	61.040	0	0	0	345	61.040	0	0	0	345		0	0
5.10	trap	17,00	3,8			0			0	61.040	0	0	0	0	61.040	0	0	0	0		0	0
5.11	receptie/lobby	38,00	3,8			0		65	65		0	0	0	0	61.040	0	0	0	65		0	0
5.13/5.14/5.16	toiletten	44,00	3,8				6		1.005	61.040	0	0	0	669		0	0	0	0	61.110	1.005	0
5.15	Salon	44,00	3,8	5	9	308		336	340	61.040	0	0	0	340		0	0	0	0		0	0
											0	0	0	6.744		0	0	0	550		1.005	5.250
								0	0		0	0	0	0		0	0	0	0		0	0
TOTAL		6.877			770						16.237	9.255	9.015	6.744		5.631	9.255	9.015	550		5.210	11.650
TOTAL, INCL 10% roundup on 25											17.875	10.200	9.925	7.425		6.200	10.200	9.925	625		5.750	12.825