3659925 2018

NOTITIE

C1

- 8 MEI 2018

Behoort bij besluit d.d.:

27 JULI 2018

☒ Gemeente
☒ Amsterdam
☒

CRUX

CRUX Engineering BV
Pedro de Medinalaan 3c
NL-1086 XK Amsterdam
Tel: +31 (0)20 - 494 30 70
Fax: +31 (0)20 - 494 30 71
info@cruxbv.nl
www.cruxbv.nl

AAN

CONTACTPERSOON

DATUM	PROJECTNUMMER	DOCUMENTNUMMER	VERSIE	PAGINA'S
5 maart 2018	17499	NT17499a1	1	8

ONDERWERP **Funderingsadvies Generaal Vetterstraat 78-B te Amsterdam**

OPGESTELD

GECONTROLEERD


VRIJGAVE

BIJLAGEN
Bijlage 1 Grondonderzoek, ref[1]
Bijlage 2 Berekening zwel
Bijlage 3 Uitvoer D-Foundation druk
Bijlage 4 Uitvoer D-Foundation trek, rekenwaarde
Bijlage 5 Uitvoer D-Foundation trek representatief

VERSIE	DATUM	OPMERKING
1	05-03-2018	-


1 INLEIDING

Ten behoeve van realisatie van een nieuw kantoorgebouw met ondergrondse parkeerkelder aan de Generaal Vetterstraat 78-B in Amsterdam heeft CRUX Engineering BV een funderingsadvies opgesteld, zoals aangeboden in offerte OF17499a1 van 3 november 2017. In Figuur 1 is de locatie van het te realiseren gebouw weergegeven.



Figuur 1 Projectlocatie (www.google.nl/maps)

Ten behoeve van de bouw wordt het huidige kantoorpand gesloopt. Het nieuw te bouwen kantoorgebouw gaat uit 6 verdiepingen bestaan met daaronder een parkeerkelder, zie Figuur 2. De onderzijde van de kelder bevindt zich op NAP-2,6m. In Figuur 1 is een bovenaanzicht van de situatie weergegeven. In dit figuur is te zien dat een gedeelte van het nieuw te realiseren pand zich gedeeltelijk ter plaatse van het huidige kantoorpand bevindt en het overige deel op een parkeerplaats.



Figuur 2 Doorsnede gevel kantoren, ref[3]

2 UITGANGSPUNTEN

2.1 Documenten

De volgende documenten zijn gebruikt voor de berekeningen:

[1] Inpijn-Blokpoel ingenieursbureau; grondonderzoek *Geotechnisch onderzoek aan de Generaal vetterstraat 76-78 te Amsterdam*; documentnummer 06P003913-RG-01; d.d. 29 januari 2018;

[2] Duyts bouwconstructies BV; rapport *constructieve uitgangspunten bedrijfsgebouw*; 217416_RAPPORT_01A; d.d. 8 februari 2018;

[3] Gietermans & Van Dijk Architecten; tekeningen *Generaal Vetterstraat 78*; gevels en plattegronden; werknummer P7035; d.d. 21 december 2017

[4] Duyts bouwconstructies BV; e-mail *Generaal Vetterstraat 78-B te Amsterdam*; Bijlage tekening ifc Generaal_Vetterstraat_78_constructie.ifc; d.d. 7 februari 2018;

[5] SBR CUR net; Handboek funderingen - Deel B; ISBN 978-90-5367-462-8; d.d. 3 december 2015.

CRUX staat niet in voor de juistheid en/of volledigheid van de door derden verstrekte informatie en gegevens.

2.2 Programmatuur

De paalberekeningen zijn uitgevoerd met D-Foundation – model Bearing Piles, programma voor berekening van druk- en trekpalen volgens Eurocode en CUR 2001-4, versie 8.2, Deltares Systems.

De met DFoundation behaalde resultaten zijn verwerkt in een bij CRUX intern opgezet en gevalideerd spreadsheet.

2.3 Uitgevoerd grondonderzoek, grondopbouw en grondwaterstand

Op 20 januari 2018 is door Inpijn-Blokpoel [1] op locatie grondonderzoek uitgevoerd, zie Bijlage 1. Dit grondonderzoek bestaat uit 5 sonderingen en één grondboring. Het grondonderzoek is op de parkeerplaatsen uitgevoerd. Na de sloop van het huidige kantoorpand worden aanvullende sonderingen uitgevoerd op de locatie van het nieuw te bouwen kantoorgebouw. In Tabel 1 is de globale bodemopbouw gegeven.

Tabel 1 Globale bodemopbouw

Grondsoort [-]	Bovenzijde grondlaag [NAP...m]
Topzandlaag	+0,85 à 0,79 (MV)
Hollandveen	-2,6 à -3,0
Oude Zeeklei	-5,0 à -5,4
Wadzand	-7,5 à -7,7
Hydrobiaklei	-10,0 à -10,5
Basisveen	-11,0 à -11,5
Eerste Zandlaag	-11,0 à -12,0
Tweede Zandlaag	-17,0 à -18,5
* De maximaal verkende diepte is NAP-24,0m à NAP-26,0m	

De freatische grondwaterstand is aangehouden op NAP-0,5m conform ref[2].

3 FUNDERINGSADVIES

3.1 Paalsystemen

Aangezien het te realiseren kantoorgebouw zich op korte afstand van bestaande bebouwing bevindt, is voor trillingsarme paalsystemen gekozen. Hierbij is gekozen voor een Fundex Groutinjectiepaal en een Drilling Push Aside schroefpaal (DPA-paal). Beide systemen zijn in de grond gevormde palen. Voor de uitvoerbaarheid van deze paalsystemen dient contact opgenomen te worden met een deskundig aannemer.

Tabel 2 Beschouwd paalsysteem drukbelasting

Paalsysteem en afmetingen	Inbrengmethode	Typering	LZ-gedrag	Paalfactoren
Fundex GI-palen Schacht casing / punt : Ø380 mm / 450 mm Ø460 mm / 560 mm	Schroevend, inclusief groutinjectie	In de grond gevormd, grondverdringend	type I	αp = 0,63 αs = 0,009 αt = 0,009 s = 1,0 β = 1,0
DPA-palen Schacht paal: Ø410 mm Ø460 mm	Schroevend	In de grond gevormd, grondverdringend	type I**	αp = 0,56* αs = 0,010* αt = 0,009* s = 1,0 β = 1,0

* De DPA paal dient minimaal 2,5 m in de funderingszandlaag te worden aangebracht. Indien de paal minder dan 2,5m de funderingszandlaag penetreert, moeten lagere ontwerpfactoren in rekening worden gebracht conform het type avegaarpaal, ref[5]

** Het last-vervormingsgedrag van DPA-palen is conform ref [5] op basis van proefbelastingen aanzienlijk gunstiger ten opzichte van de traditionele avegaarpalen ('type 2' van EC7). Het paaltype vertoont echter een minder stijf gedrag dan de grondverdringende palen dient onder 'type 1' van de EC7 zijn ondergebracht. Doormiddel van het bepalen van de rekenwaarde lage veerstijfheid wordt het minder stijve gedrag meegenomen.

3.2 Zwelbelasting

3.2.1 Algemeen

Het ontgraven van de bouwkuip leidt tot een afname van de effectieve verticale korrelspanning in de onderliggende grondlagen. Deze afname van de korrelspanning gaat in de onderliggende lagen gepaard met een toename van het volume onder toetreding van water. Met zwel wordt over het algemeen volumevergroting van cohesieve lagen bedoeld.

Zwel kan leiden tot een heffing van de bouwkuipbodem na het ontgraven. De rijzende lagen kunnen een belasting uitoefenen op de constructievloer en de trekpalen waarmee deze in de diepe zandlagen wordt verankerd. Ook kunnen de lagen via schuifkrachten de belasting direct op de funderingspalen overdragen indien het rijzingsproces nog niet ten einde is bij het installeren van de funderingspalen. In deze paragraaf wordt ingegaan op de effecten van de zwel op de constructieonderdelen.

3.2.2 Zwel op funderingspalen

Als conservatief uitgangspunt is door CRUX aangenomen dat de funderingspalen worden geïnstalleerd voordat de bouwkuip volledig wordt ontgraven en worden derhalve door de opwaarts bewegende grondlagen belast. De krachten zijn afkomstig van de schuifweerstand tussen de palen en de grond.

In Tabel 3 de representatieve zwelbelasting gepresenteerd. Hierbij zijn alleen de lagen boven de Eerste Zandlaag in rekening gebracht. De zwelbelasting op de palen is bepaald op basis van CUR ontwerprichtlijn zwelbelastingen op funderingen. De zwelbelastingen dienen meegenomen te worden in de toetsing van de trekcapaciteit van de palen. Ook dienen de palen gewapend te worden op de totale trekbelasting.

Tabel 3 Representatieve zwelbelasting


Paalafmeting (schacht- / puntdiameter) [mm / mm]	$F_{zwel;rep}$ [kN]
Fundex Groutinjectiepaal Ø380/450	63
Fundex Groutinjectiepaal Ø460/560	76
DPA-paal Ø410	61
DPA-paal Ø460	69

3.2.3 Zwel op constructievloer

In CUR202 wordt voor de constructievloer welke door zwel belast worden aangenomen dat de vloer de zwelbelasting volledig tegengaat. De vloer wordt in dit geval dus als plaatsvast beschouwd. Zwel van de grondlagen is een tijdsafhankelijk proces waarbij voor de eindwaarde vaak een periode van 30 jaar wordt gehanteerd. Door consolidatie (toe- of afstromen van water) treedt het grootste deel van de zwel echter binnen enkele maanden op.
Aangezien de vloer als plaatsvast wordt beschouwd, is op het moment van storten van de betonvloer de reeds opgetreden zwel als eindzwel te beschouwen. Dit betekent dat de zwelbelasting even groot is als de belasting die nodig is om de (verdere) rijzing van de lagen tegen te gaan.
In de CUR richtlijn wordt de situatie verder beschouwd als 1-dimensionaal en wordt het effect van de palen verwaarloosd, waardoor de volledige belasting direct op de vloer werkt. In de CUR-richtlijn wordt voor het versneld toestromen van water bij zwel een minimum factor 5 à 15 ten opzichte van een "normale" consolidatie gehanteerd. Voor de verhouding is in dit geval en factor 8 gehanteerd.

Tijdens het ontgraven van de bouwkuip treedt al een groot deel van de zwel op. Analoog aan de ophogingen, waar 50% van de ophoogtijd kan worden gezien als zettingstijd, kan dit bij zwel ook minimaal worden gehanteerd. Omdat zwel veel sneller optreedt, is dit een conservatief uitgangspunt.

In verband met de consolidatietijd van de zwelperiode is voor verschillende momenten in de tijd de zwelkracht op de vloer berekend. De berekende zwelkrachten zijn weergegeven in Figuur 3. De berekening is opgenomen in Bijlage 2.



Figuur 3 Verloop zweldruk op constructievloer in de tijd

Opmerkingen bij de figuur:
Een inschatting zal gemaakt moeten worden na hoeveel dagen de constructievloer gestort zal worden vanaf start ontgraven. start ontgraving dient halverwege de ontgravingsperiode gekozen te worden (bv. Bij 4 weken ontgravingsduur wordt 2 weken aangehouden voor het aantal in rekening te brengen dagen).

Opgemerkt wordt dat de waarden uit Figuur 3 een bovengrens van de optredende zweldruk betreffen waarbij het effect van het verplaatsen van de paalkop ten gevolge van de belasting vanuit de betonvloer door waterdruk na uitschakelen bemaling niet is verdisconteerd.

3.3 Berekening drukpalen

3.3.1 Uitgangspunten

Voor de berekening van het verticaal draagvermogen van de palen zijn de volgende uitgangspunten gehanteerd:

- Berekening volgens NEN-9997-1 op basis van sonderingen;
- De grondlaag indeling in DFoundation is gebeurd op basis van de CUR-rule methode;
- Bij het bepalen van de schachtwrijving is voor de diameter van de fundexpaal met groutinjectie gezien het toepassen van groutinjectie uitgegaan van $\varnothing_{schacht} = (\varnothing_{punt} + \varnothing_{schacht;casing})/2$;
- Paalpuntniveau in de Tweede Zandlaag, vanaf ca. NAP -17,0 à 18,5 m;
- De positieve schachtwrijving wordt ontleend aan het zandpakket vanaf circa NAP -11,0 à -12,0 m;
- Negatieve kleef wordt gezien de ontgraving niet meegenomen;
- In de berekeningen wordt rekening gehouden met reductie van de gemeten conusweerstanden ten gevolge van een ontgraving tot maximaal NAP -2,6m;
- De stijfheid van de constructie van de bovenbouw bepaalt mede de waarde van de factoren ξ (ksi) die onzekerheid in het grondonderzoek en de mogelijkheid van herverdeling van belasting over meerdere palen in rekening brengt. In het ontwerp van een slappe fundering uitgegaan;
- Aangehouden factoren ξ (ksi) en veiligheidsfactoren:
    - De draagkracht is op twee manieren berekend: het gemiddelde van de sonderingen waarbij de factor ξ3 van toepassing is, en de slechtste van de groep sonderingen waarbij ξ4 van toepassing is. De laagste draagkracht is maatgevend. Hierbij moet wel gelden dat de variatiecoëfficiënt <= 12% is. De factor ξ is mede afhankelijk van het aantal sonderingen dat als groep bij elkaar genomen wordt. Sonderingen welke op een afstand < 25m van een gebouwdeel zijn gesitueerd mogen meegenomen worden in de bepaling van de ξ. In deze fase van het ontwerp wordt uitgegaan van een maximale groep van 4 sonderingen in verband met het nog uit te voeren grondonderzoek;
    - $\gamma_b, \gamma_s = 1,2$

3.3.2 Paaldrukdraagvermogen en veerstijfheid

De veerstijfheid bij statische belasting heeft betrekking op het eigen gewicht en het permanent aanwezige deel van de veranderlijke belasting. De paalkopzakking bestaat uit een gedeelte paalzakking ten gevolge van mobiliseren grondweerstand (s_b) en een gedeelte elastische verkorting (s_{el}) van de paal. De paalpuntzakking is berekend volgens de standaard last-zakkingsdiagrammen uit de Eurocode. De aangehouden elasticiteitsmodulus van de paal voor de berekening van de elastische verkorting is E = 15.000 N/mm^2 voor in de grond gevormde palen. Bij het bepalen van de elastische verkorting is voor de schachtdiameter van de Fundex Groutinjectiepalen uitgegaan van $\varnothing_{schacht} = (\varnothing_{punt} + \varnothing_{schacht;casing})/2$. Opgemerkt wordt dat de puntzakking t.g.v. mobilisatie van de grondweerstand niet lineair verloopt. Bij toenemende belasting neemt de zakking meer dan evenredig toe en de veerstijfheid neemt dus af. In deze fase van het ontwerp is voor de paalbelasting uitgegaan van 70% van het representatieve paaldraagvermogen.

In Tabel 4 is het paaldraagvermogen op druk voor de paalsystemen met een paalpuntniveau van NAP-18,0m tot NAP-21,5m weergegeven. Daarnaast zijn de aan te houden veerconstanten voor een statische belasting op de drukpalen samengevat. In de weergegeven stijfheid is de elastische verkorting van de paal meegenomen. Als Bijlage 3 is de uitvoer van de berekening toegevoegd.

Bij de bepaling van de rekenwaarde van de lage en hoge veerstijfheid dient bepaald te worden door respectievelijk deling en vermenigvuldiging met $\sqrt{2}$.

Tabel 4 Paaldraagvermogen op druk en paalveerconstante inclusief elastische verkorting

PPN	Fundex Groutinjectiepaal				DPA-paal			
	Ø380/450		Ø460/560		Ø410		Ø460	
[NAP...m]	$R_{c;net;d}$ [kN]	$K_{v;1}$ [MN/m]	$R_{c;net;d}$ [kN]	$K_{v;1}$ [MN/m]	$R_{c;net;d}$ [kN]	$K_{v;1}$ [MN/m]	$R_{c;net;d}$ [kN]	$K_{v;1}$ [MN/m]
-18,0	1045	91	1462	118	925	93	1095	102
-18,5	1323	97	1863	126	1151	97	1366	106
-19,0	1393	102	1942	134	1222	100	1447	113
-19,5	2101	100	2722	128	1375	99	2170	111
-20,0 ND*	2071	100	2077	132	1573	95	2136	112
-20,5	1504	103	2078	138	1363	101	1594	115
-21,0	1473	106	2052	141	1345	102	1586	117
-21,5	1433	108	1972	145	1334	102	1564	120
* Niet dieper funderen in verband met een afnemend draagvermogen								

De in Tabel 4 gepresenteerde waarden betreft de rekenwaarde van het uitwendige geotechnische paaldrukdraagvermogen. Door de constructeur dient te worden gecontroleerd of de bijbehorende paalschachtspanningen, met andere woorden het inwendige constructieve draagvermogen, toelaatbaar zijn.

Geadviseerd wordt om voor alle paalsystemen en afmetingen op NAP-19,5m of NAP-20,0m te funderen.

3.4 Berekening trekpalen

3.4.1 Uitgangspunten

Voor de berekeningen van de trekpalen zijn de volgende aanvullende uitgangspunten gehanteerd:

- Door CRUX is aangenomen dat de funderingspalen in de eindsituatie niet op trek belast worden. Hiermee is de belastingvariatiefactor $\gamma_{m;var;qc}$ gelijk aan 1,0;
- Positieve schachtwrijving voor de palen wordt ontleend aan de zandlagen vanaf ca. NAP-11,0m à -12,0 m;
- In de berekening zijn alleen middenpalen beschouwd met een maatgevend paalstramien van 2x2m;
- Veiligheidsfactor γ_s is gelijk aan 1,35.

3.4.2 Paaldraagvermogen op trek en veerstijfheid

In Tabel 5 is een samenvatting gegeven van het trekdraagvermogen exclusief zwelbelasting op de palen en de zwelbelasting uit de vloer en de veerstijfheden inclusief elastische verlening. Als Bijlage 4 en Bijlage 5 is de uitvoer van de berekening toegevoegd.

Indien de palen voorafgaand aan het ontgraven worden geïnstalleerd treedt zwel langs de palen op. Hier is geen rekening mee gehouden in het trekdraagvermogen in Tabel 5. Daarnaast is ook geen rekening gehouden met de reductie van het trekdraagvermogen ten gevolge van de zwelbelasting op de vloer. De zwelbelasting op de vloer en de palen dient door de constructeur verdisconteerd te worden in het paaldraagvermogen. Zie voorgaande paragraaf 3.2 voor de zwelbelasting.

Bij de bepaling van de rekenwaarde van de lage en hoge veerstijfheid dient bepaald te worden door respectievelijk deling en vermenigvuldiging met $\sqrt{2}$.

Tabel 5 Paaldraagvermogen op trek excl. zwelbelasting - paalveerconstante inclusief elastische verlenging

PPN	Fundex Groutinjectiepaal				DPA-paal			
	Ø380/450		Ø460/560		Ø410		Ø460	
[NAP...m]	$R_{t;d}$ [kN]	$K_{v;1}$ [MN/m]	$R_{t;d}$ [kN]	$K_{v;1}$ [MN/m]	$R_{t;d}$ [kN]	$K_{v;1}$ [MN/m]	$R_{t;d}$ [kN]	$K_{v;1}$ [MN/m]
-18,0	315	52	358	58	313	52	337	55
-18,5	340	53	376	59	338	53	363	57
-19,0	365	54	392	61	363	54	388	58
-19,5	389	55	408	62	386	55	411	59
-20,0 ND*	412	56	424	63	409	55	427	60
-20,5	433	57	439	64	431	56	443	61
-21,0	454	57	455	65	451	57	459	61
-21,5	474	58	471	66	471	57	475	62
* Niet dieper funderen in verband met een afnemend drukdraagvermogen								

De in gepresenteerde waarden betreft de rekenwaarde van het uitwendige geotechnische paaldrukdraagvermogen. Door de constructeur dient te worden gecontroleerd of de bijbehorende paalschachtspanningen, met andere woorden het inwendige constructieve draagvermogen, toelaatbaar zijn.

Geadviseerd wordt om voor alle paalsystemen en afmetingen op NAP-19,5m of NAP-20,0m te funderen.

4 CONCLUSIES EN AANBEVELINGEN

Ten behoeve van realisatie van een nieuw kantoorgebouw met ondergrondse parkeerkelder aan de Generaal Vetterstraat 78-B in Amsterdam is in deze notitie een funderingsadvies opgesteld voor twee trillingsarme paalsystemen in verband met de belendende panden.

Het advies is opgesteld aan de hand van sonderingen op een gedeelte van het terrein zonder bebouwing. Na de sloop van het huidige kantoor worden aanvullende sonderingen ter plaatse van het toekomstige kantoorgebouw gemaakt. De in deze notitie berekende paaldraagvermogens en veerstijfheden dienen gecontroleerd te worden aan de hand van deze sonderingen.

Uitgaande van een Fundex groutinjectie kan een drukdraagvermogen van 2071kN en 2077kN worden bereikt met een diameter van respectievelijk Ø219/310mm en Ø355/450mm en een paalpuntniveau NAP-20,0m.
Het bijbehorende trekdraagvermogen is 412kN en 424kN exclusief de zwelbelasting bij een hart op hart afstand van 2m. De bijbehorende zwelbelasting is 63kN voor de afmeting Ø219/310mm en 76kN per paal voor Ø355/450mm. Daarnaast dient rekening gehouden te worden met een zwelbelasting op de vloer, conform Tabel 3. Indien een kleinere hart op hart afstand wordt toegepast neemt het trekdraagvermogen af.

Uitgaande van een DPA-paal kan een drukdraagvermogen van 1573kN en 2136kN worden bereikt met een diameter van respectievelijk Ø410mm en Ø460mm en een paalpuntniveau NAP-20,0m.
Het bijbehorende trekdraagvermogen is 409kN en 427kN exclusief zwelbelasting bij een hart op hart afstand van 2m. De bijbehorende zwelbelasting is 61kN per paal voor de afmeting Ø410mm en 69kN per paal voor Ø460mm. Daarnaast dient rekening gehouden te worden met een zwelbelasting op de vloer conform Tabel 3. Indien een kleinere hart op hart afstand wordt toegepast neemt het trekdraagvermogen af.

Voor de uitvoering wordt aanbevolen om de uitvoerbaarheid van de paalsystemen door een deskundig aannemer te laten controleren.

Mocht u naar aanleiding van deze notitie nog vragen hebben dan kunt u contact opnemen met ing. H.J. Honing.

Bijlage 1 Grondonderzoek, ref[1]


B
INPIJN-BLOKPOEL
ingenieursbureau
Geotechniek - Milieutechniek

Geotechnisch onderzoek aan de Generaal Vetterstraat 76-78 te Amsterdam

Betreft	Resultaten geotechnisch onderzoek
Opdrachtnummer	06P003913
Documentnummer	06P003913-RG-01
Opdrachtgever	Crux Engineering B.V. Pedro de Medinalaan 3c 1086 XK Amsterdam

Opgesteld door	:	Paraaf :	
Gezien	:		Paraaf :
Status	:		
Codering	:		
Datum rapport	:		

INPIJN-BLOKPOEL Ingenieursbureau
Mercuriusweg 18
2741 TA WADDINXVEEN

T 0182-610013
F 0182-626016
E west@inpijn-blokpoel.com

INHOUDSOPGAVE

1. INLEIDING **1**

2. ONDERZOEK **1**

2.1 SONDERINGEN 1
2.2 BORING 1
2.3 INMETING EN WATERPASSING 1
2.4 FOTO'S 2

BIJLAGEN:

A) Situatietekening en foto's
B) Waterpasstaat
C) Sondeergrafieken
D) Boorstaat
E) Verklaring codering

VERZENDLIJST

1 x Crux Engineering B.V. te Amsterdam t.a.v.

INPIJN-BLOKPOEL Ingenieursbureau
Mercuriusweg 18
2741 TA WADDINXVEEN

T 0182-610013
F 0182-626016
E west@inpijn-blokpoel.com

1. INLEIDING

Ten behoeve van het project "Geotechnisch onderzoek aan de Generaal Vetterstraat 76-78 te Amsterdam" is door ons bureau op verzoek van Crux Engineering B.V. uit Amsterdam een geotechnisch onderzoek verricht. Voorliggend rapport bevat een beschrijving en de resultaten van het onderzoek.

2. ONDERZOEK

2.1 Sonderingen

Er zijn 5 sonderingen gemaakt met een elektrische conus conform NEN-EN-ISO 22476-1. Bij de sonderingen is naast de conusweerstand tevens de plaatselijke wrijving gemeten en geregistreerd. De relatie tussen conusweerstand en plaatselijke wrijving, het wrijvingsgetal, geeft een indicatie van de verschillende grondsoorten onder het grondwaterniveau. De sonderingen zijn uitgevoerd door een sondeertruck.

Sonderingen DKM-01 en DKM-02 konden niet uitgevoerd worden omdat er op de geplande sondeerlocatie een hek staat.

De ondergrond is ter plaatse van DKM-03, DKM-05, DKM-08 en DKM-09 voorgeboord in verband met de mogelijke aanwezigheid van kabels en/of leidingen; de aangetroffen grondslag is geclassificeerd en weergegeven in een voorboorstaat. Hiervoor wordt verwezen naar bijlage D.

De ondergrond is ter plaatse van DKM-06 80cm voorgedrukt in verband met verhardingen op de sondeerlocatie.

Voor de grafieken van de sonderingen wordt verwezen naar bijlage C; de locatie van de sondeerpunten is aangegeven op de situatietekening SIT-01, toegevoegd onder bijlage A. Voor een verklaring van de op de tekening gebruikte tekens wordt verwezen naar de "Verklaring Codering" die onder bijlage E aan dit rapport is toegevoegd.

2.2 Boring

Er is een boring uitgevoerd. In het boorgat is naar de grondwaterstand gepeild. Voor het profiel van de boring wordt verwezen naar bijlage D; de locatie van het boorpunt is aangegeven op de situatietekening SIT-01, toegevoegd onder bijlage A. Voor een verklaring van de op de tekening en de boorprofielen gebruikte tekens wordt verwezen naar de "Verklaring Codering" die onder bijlage E aan dit rapport is toegevoegd.

2.3 Inmeting en waterpassing

Met behulp van een GNSS meetsysteem zijn de locaties van de onderzoekspunten uitgezet in RD-coördinaten en is de hoogte van het maaiveld ter plaatse van ieder onderzoekspunt bepaald ten opzichte van NAP.
De gemeten hoogte is gecontroleerd aan de hand van een NAP-referentieniveau in de omgeving van het werk. Voor de omschrijving van het referentiepunt en voor de resultaten van de inmeting en waterpassing wordt verwezen naar de inmeet- en waterpasstaat bijlage B.

2.4 Foto's

Tijdens de uitvoering van het veldwerk zijn enkele foto's gemaakt. Voor de foto's en een tekening waarop met pijlen is aangegeven vanuit welke positie en in welke richting de foto's zijn gemaakt wordt verwezen naar bijlage A.


INPIJN-BLOKPOEL Ingenieursbureau
Mercuriusweg 18
2741 TA WADDINXVEEN

T 0182-610013
F 0182-626016
E west@inpijn-blokpoel.com

Bijlage A

INPIJN-BLOKPOEL Ingenieursbureau
Mercuriusweg 18
2741 TA WADDINXVEEN

T 0182-610013
F 0182-626016
E west@inpijn-blokpoel.com



Bestaande bebouwing

0 5 10 15 20 25m

N

Bron: E-mail digitale tekening	
Bureau + vestigingsplaats: KLIC	
Tekening- / bladnummer: --	
Datum laatste bewerking: --	

INPIJN-BLOKPOEL Ingenieursbureau

Opdrachtomschrijving / locatie: Geotechnisch onderzoek aan de Generaal Vetterstraat 76-78 te Amsterdam	Opdrachtnummer: 06P0039133	Bijlage: SIT-01	
	Bewerkt: tfn	Datum: 29-01-2018	
Omschrijving tekening: Situatietekening	X, Y: RD/dGPS	Schaal: 1 : 500	Formaat: A4

Deze situatietekening dient om inzicht te geven in de locatie van de meet- en onderzoekspunten.
De tekening dient niet voor andere doeleinden te worden gebruikt.

N:\Opdrachten\06\00\Veldwerk\Tekeningen\06P003913-SIT-01-tfn

Opdracht : 06P003913
Project : Geotechnisch onderzoek aan de Generaal Vetterstraat 76-78 te Amsterdam



1. Locatie DKM-06



2. Locatie DKM-08



3. B-01



4. Locatie B-01



5. Locatie DKM-05



6. Dorpel 1

INPIJN-BLOKPOEL ingenieursbureau
Mercuriusweg 18
2741 TA WADDINXVEEN

Telefoon: 0182-610013

Fax: 0182-626016

Bijlage B

INPIJN-BLOKPOEL Ingenieursbureau
Mercuriusweg 18
2741 TA WADDINXVEEN

T 0182-610013
F 0182-626016
E west@inpijn-blokpoel.com

Opdracht : 06P003913
Project : Geotechnisch onderzoek aan de Generaal Vetterstraat 76-78 te Amsterdam

WATERPASSTAAT

Meetmethode : Uitgezet en gewaterpast middels dGPS
Datum meting : 20 januari 2018
Hoogte (Z) t.o.v. : NAP

Meetpunten	*x-coördinaat [m]*	*y-coördinaat [m]*	*z-coördinaat (hoogte) [m t.o.v. NAP]*
DKM-01 (niet uitgevoerd)	--	--	--
DKM-02 (niet uitgevoerd)	--	--	--
DKM-03	118.155,8	484.051,6	0,84
DKM-05	--	--	0,84
DKM-06	118.140,0	484.052,1	0,85
DKM-08	--	--	0,85
DKM-09	118.121,9	484.052,0	0,79
B-01	--	--	0,83
Grondwaterstand B-01 (20-01-2018)	--	--	-0,51
Put 1	118.171,1	484.054,1	0,69
Weg 1	118.170,9	484.069,2	0,66
Dorpel 1	--	--	0,77
Water 1 (20-01-2018)	118.113,7	484.048,6	-0,48

Opmerking:
--Indien geen -x- en -y-coördinaten zijn gepresenteerd dan is de NAP-hoogte terrestrisch ingemeten.

Let op:
Deze waterpasstaat dient om inzicht te geven in de hoogteligging en locaties van de meet- en onderzoekspunten ten opzichte van een referentiepunt. De resultaten dienen niet voor andere doeleinden te worden gebruikt.

INPIJN-BLOKPOEL ingenieursbureau
Mercuriusweg 18
2741 TA WADDINXVEEN


T 0182-610013
F 0182-626016
E west@inpijn-blokpoel.com

Bijlage C

INPIJN-BLOKPOEL Ingenieursbureau
Mercuriusweg 18
2741 TA WADDINXVEEN

T 0182-610013
F 0182-626016
E west@inpijn-blokpoel.com

Opdracht: 06P003913
Project: Geotechnisch onderzoek aan de Generaal Vetterstraat 76-78 te Amsterdam



Sondering volgens NEN-EN-ISO 22476-1
Sondeerklasse
Conusnummer: I-CFXY-10


Uitvoerder: S9
Datum: 20-1-2018

X: 118155,775
Y: 484051,619

Sondering 3

INPIJN-BLOKPOEL Ingenieursbureau

Opdracht: 06P003913
Project: Geotechnisch onderzoek aan de Generaal Vetterstraat 76-78 te Amsterdam



Sondering volgens NEN-EN-ISO 22476-1
Sondeerklasse
Conusnummer: I-CFXY-10


Uitvoerder: S9
Datum: 20-1-2018

X: 0.000
Y: 0.000

Sondering

INPIJN-BLOKPOEL Ingenieursbureau

Opdracht: 06P003913
Project: Geotechnisch onderzoek aan de Generaal Vetterstraat 76-78 te Amsterdam



Sondering volgens NEN-EN-ISO 22476-1
Sondeerklasse
Conusnummer: I-CFXY-10


Uitvoerder: S9
Datum: 20-1-2018

X: 118139.992
Y: 484052.092

Sondering

INPIJN-BLOKPOEL Ingenieursbureau

Opdracht: 06P003913
Project: Geotechnisch onderzoek aan de Generaal Vetterstraat 76-78 te Amsterdam



Sondering volgens NEN-EN-ISO 22476-1
Sondeerklasse
Conusnummer: I-CFXY-10


Uitvoerder: S9
Datum: 20-1-2018

X: 0.000
Y: 0.000

Sondering

INPIJN-BLOKPOEL Ingenieursbureau

Opdracht: 06P003913
Project: Geotechnisch onderzoek aan de Generaal Vetterstraat 76-78 te Amsterdam



Sondering volgens NEN-EN-ISO 22476-1
Sondeerklasse
Conusnummer: I-CFXY-10

Uitvoerder: S9
Datum: 20-1-2018

X: 118121.897
Y: 484051.978

Sondering

INPIJN-BLOKPOEL Ingenieursbureau

Bijlage D

INPIJN-BLOKPOEL Ingenieursbureau
Mercuriusweg 18
2741 TA WADDINXVEEN

T 0182-610013
F 0182-626016
E west@inpijn-blokpoel.com

Opdracht: 06P003913
Project: Geotechnisch onderzoek aan de Generaal Vetterstraat 76-78 te Amsterdam

Boring B001

Uitvoering op: 20-01-2018
Uitvoering door: MEK
Uitgevoerd nabij: DKM-03

Boringgegevens

Maaiveldhoogte [m]: 0,83 N.A.P.
Grondwaterstand [cm-mv]: 134

Classificatiegegevens



Bijlage E

INPIJN-BLOKPOEL Ingenieursbureau
Mercuriusweg 18
2741 TA WADDINXVEEN

T 0182-610013
F 0182-626016
E west@inpijn-blokpoel.com

VERKLARING CODERING BORINGEN
(conform NEN 5104)

GRIND
- grind, siltig
- grind, zwak zandig
- grind, matig zandig
- grind, sterk zandig
- grind, uiterst zandig

ZAND
- zand, kleiig
- zand, zwak siltig
- zand, matig siltig
- zand, sterk siltig
- zand, uiterst siltig


VEEN
- veen, mineraalarm
- veen, zwak kleiig
- veen, sterk kleiig
- veen, zwak zandig
- veen, sterk zandig

LEEM
- leem, zwak zandig
- leem, sterk zandig

SLIB
- slib

KLEI
- klei, zwak siltig
- klei, matig siltig
- klei, sterk siltig
- klei, uiterst siltig
- klei, zwak zandig
- klei, matig zandig
- klei, sterk zandig

TOEVOEGINGEN
- zwak humeus
- matig humeus
- sterk humeus
- zwak grindig
- matig grindig
- sterk grindig

PEILBUIS


GRONDMONSTERS
- geroerd monster
- ongeroerd monster

OVERIG
- bijzonder bestanddeel
- indicatie hoge grondwaterstand
- actuele grondwaterstand
- indicatie lage grondwaterstand

LEGENDA TEKENINGEN

SONDERINGEN
- D — Sondering met meting conusweerstand
- DKM — Diepsondering met plaatselijke kleef
- DKP — Sondering met waterspanning
- DKM — Seismische sondering
- DKM — Sondering met bolconus
- hM — Handsondering
- SD — Slagsondering
- Niet uitgevoerde sonderingen

BORINGEN en PEILBUIZEN
- B — Boring
- B — Boring met peilbuis
- Niet uitgevoerde boring
- B — Boring eerdere fase

MONITORING
- SCM-01 — Scheurmeter
- Deformatiebout
- Trillingsmeter
- PDP- — Plaatdrukproef
- ZB- — Zakbaak
- WSM- — Waterspanningsmeter
- HLM- — Hellingmeter

ANDERE SYMBOLEN
- foto 1 — Positie en richting foto
- Meetpunt
- 0-punt lokaal assenstelsel

KLEUR CODERING ONDERZOEKSFASE
- D- — Sondering Fase 02
- D- — Sondering Fase 03
- D- — Sondering Fase 04

ADVISERING GEOTECHNIEK

Paalfundering
Fundering op staal

Bouwputontwerp
Bemaling
Grondkerende constructie
Taludstabiliteit

Bouwrijp maken terrein
Grondbalans
Drainage
Afkoppelen en infiltreren
Geo-hydrologische studie

Toezicht heiwerk

Funderingsrenovatie
Schade expertise

Pijpleidingen
Gestuurde boringen

Trillingsanalyse
Geluidsanalyse

VELDWERK

Sonderen
Boren
Pompproeven
Peilbuizen

Landmeetkundig werk
Nauwkeurigheidswaterpassing
DGPS-metingen
Inmeten palenplan

Trillingsmeting
Geluidsmeting
Akoestische paalcontrole
Geo-monitoring

Heibegeleiding
Toezicht bouwputten

LABORATORIUM

Classificatie proeven
Mechanische eigenschappen
Chemische analyse

MILIEU-ONDERZOEK

Verkennend-, nader- en
saneringsonderzoek
Advisering
Projectbegeleiding
Akoestisch onderzoek
Partijkeuringen besluit bodemkwaliteit (Bbk)

INPIJN-BLOKPOEL
ingenieursbureau

Ingenieursbureau Inpijn-Blokpoel West B.V.
Mercuriusweg 18
2741 TA Waddinxveen
telefoon (0182) 61 00 13

e-mail west@inpijn-blokpoel.com

Tevens vestigingen:
Son, Hoofddorp en Groningen

www.inpijn-blokpoel.com

MGMT. SYS. RvA C 174

SGS

VCA CHECKLIST AANNEMERS

Op de opdrachten voor het uitvoeren en rapporteren van technische werkzaamheden, zijn van toepassing de "A.L.U.W.-2015". Deze zijn gedeponeerd ter Griffie van de Arrondissementsrechtbank te 's-Hertogenbosch. Voor adviesopdrachten geldt de "D.N.R.-2005". Inschrijving Handelsregister K.v.K.nummer 17076128.

Bijlage 2 Berekening zwel

Sheet	**Zwelbelasting - analytische berekening V001**
Project	Generaal Vetterstraat 78-B te Amsterdam
Projectnummer	17499
Fase	Fundex Groutinjectie 380/450
Onderdeel	keldervloer
Datum	1-3-2018
Opsteller	hon

Berekening zwel agv ontgraving
Berekend wordt: de primaire zwel in de loop der tijd (consolidatie) en de secundaire zwel in de loop der tijd. Aan de hand hiervan wordt de zweldruk bepaald die op zal bouwen na aanleg van een vloer op een bepaald moment.

De resterende zweldruk wordt berekend volgens analytische methoden uit CUR202; zwel op palen volgens slipmethode; zwel op vloer volgens Koppejan.

Uitgangspunten: Horizontaal oneindige ontgraving / Zwellende grondlagen worden gecombineerd tot één laag met gemiddelde cv;zwel.

CRUX


P:\17xx\17499 Duyts Advies Generaal Vetterstraat A' dam\04 REKEN\zet\[SH17499a1 Zwelbelasting - analytische berekening v001tj.xlsm]Fundex 380450

1. Invoer

1.1 Algemeen

Veiligheidsklasse	RC 2		
γ_{water}	10	[kN/m³]	
t_{eind}	10000	[dagen]	periode voor bepaling eindzwel
t_{zwel}	30	[dagen]	periode van vrije zwel; $t_{zwel} = \frac{1}{2} \times t_{ontgraven} + t_{aat} + t_{start}$
η	1	[-]	modelfactor afh. van geometrie, zie figuur

$\gamma_{zwel;vloer}$ = 1,35 [-] partiële factor zweldruk op vloer
$\gamma_{zwel;paal}$ = 1,00 [-] partiële factor zweldruk enkele paal (alleenstaande paal, volledige slip)



1D als h << b; η = 1
2D als l >> b; η = 2
3D als b ≈ l; η = 3

1.2 Initiële gegevens

maaiveld	+0,85	[NAP .. m]	
freatische GWS	-0,50	[NAP .. m]	check PDF blz 60
onderkant zwellende lagen	-12,00	[NAP .. m]	

1.3 Fasering

Fase	ontgraven	aanbrengen palen	start bemalen	aanbrengen vloer	leegpompen kuip
Tijdstip [dagen]	0	0	15	15	0

1.4 Ontgraving

ontgravingsniveau	-2,60	[NAP .. m]	
waterstand in ontgraving	-3,10	[NAP .. m]	
extra belasting	0,0	[kPa]	
Rekenen met spreiding?	Nee		spreiding conform Boussinesq
Breedte bouwkuip	50,0	[m]	
Onderzijde damwand	-12,00	[NAP .. m]	voor grondlagen boven ok wand wordt geen spreiding meegenomen!

Δu = 26,0 [kPa] verandering waterspanning

1.5 Paalgegevens

paaltype	in de grond gevormd		
paalvorm	rond		
diameter schacht	0,42	[m]	
hoh X-richting	2,00	[m]	
hoh Y-richting	2,00	[m]	

factor δ / φ = 1,00 [-]
O = 1,319 [m] schachtomtrek
$A_{stramien}$ = 4,00 [m²] stramienoppervlak

1.6 Grondprofiel

laag	type	head [NAP .. m]	bk [NAP .. m]	γ_d [kN/m³]	γ_{sat} [kN/m³]	ϕ [°]	OCR [-]	A_p [-]	A_s [-]	cv [m²/s]	cv;zwel / cv [-]	cv;zwel [m²/s]
Aanvullaag (zand)	Zand, n.c.	-0,50	+0,85	18,10	18,10	28,0	1,0	823	3854	0,100	8,0	0,800
Hollandveen	Veen, n.c.	-0,50	-2,60	10,50	10,50	17,0	1,0	183	559	8,00E-07	8,0	6,40E-06
Oude Zeeklei	Klei, n.c.	-0,50	-5,40	16,20	16,20	26,0	1,0	565	2379	6,00E-07	8,0	4,80E-06
Oude Zeeklei	Klei, n.c.	-0,50	-7,20	16,20	16,20	26,0	1,0	565	2379	6,00E-07	8,0	4,80E-06
Wadzand	Zand, n.c.	-0,50	-9,00	17,90	17,90	27,0	1,0	396	1832	1,00E-04	4,0	4,00E-04
Hydrobiaklei	Klei, n.c.	99	-10,00	15,20	15,20	26,0	1,0	464	1845	1,00E-06	8,0	8,00E-06
Basisveen	Veen, n.c.	99	-11,00	11,70	11,70	18,0	1,0	232	758	2,00E-08	8,0	1,60E-07
1ste zandlaag	Zand, n.c.	-3,10	-12,00	17,70	19,70	32,0	1,0	1130	5786	1,00E-04	8,0	8,00E-04
2e zandlaag	Zand, n.c.	-3,10	-17,00	16,90	18,90	33,0	1,0	965	4722	1,00E-04	8,0	8,00E-04


bij head 99 invullen voor interpolatie over de betreffende grondlaag

legen cellen grondlagen [weergeven] [+] legen cellen grondlagen weergeven

2. Numerieke uitvoer

ALGEMEEN

$\sigma'_{v;ontgniv}$ =	41,4	[kPa]	initiële korrelspanning op ontgravingsniveau
$\Delta p'$ =	-41,4	[kPa]	delta P waarmee gerekend wordt om zwel te bepalen
afstromen =	2	-zijdig	
d_{zwel} =	9,40	[m]	dikte zwellende grondlagen
h =	4,70	[m]	afstroomlengte (2-zijdige afstromen)
$c_{v;zwel;eq}$ =	2,765E-06	[m²/s]	
U(0) =	20	[%]	directe aanpassing



VRIJE ZWEL OP PAAL EN WAND (slipmethode)
- bovengrens slipmethode, alleenstaande paal met volledige slip
- aanpassing U = 0%

ONTGRAVEN GRONDPROFIEL

laag	bk [NAP .. m]	ok [NAP .. m]	dikte [m]	ϕ [°]	OCR [-]	K_0 [-]	$\sigma'_{v;mid;init.}$ [kPa]	$\sigma'_{v;mid;ontgr.}$ [kPa]	δ [°]	$K_0 \times \tan(\delta)$ [-]	$F_{zwel;repd}$ [kN]	$\Sigma F_{zwel;rep}$ [kN]	$\Sigma F_{zwel;rep;red}$ [%]
Hollandveen	-2,60	-5,40	2,80	17,0	1,0	0,71	42,1	0,7	17,0	2,72	7,0	7	7
Oude Zeeklei	-5,40	-7,20	1,80	26,0	1,0	0,56	48,4	7,0	26,0	0,92	15,3	22	22
Oude Zeeklei	-7,20	-9,00	1,80	26,0	1,0	0,56	59,6	18,1	26,0	0,63	27,3	50	42
Wadzand	-9,00	-10,00	1,00	27,0	1,0	0,55	69,1	27,7	27,0	0,55	20,2	70	51
Hydrobiaklei	-10,00	-11,00	1,00	26,0	1,0	0,56	82,2	40,7	26,0	0,50	26,7	97	58
Basisveen	-11,00	-12,00	1,00	18,0	1,0	0,69	98,6	57,2	18,0	0,46	34,7	131	63

$F_{zwel;rep}$ =	131	[kN]	representatieve zwelbelasting ...	$F_{zwel;rep}$ =	63	[kN]	representatieve zwelbelasting incl. reductie
$F_{zwel;d}$ =	131	[kN]	rekenwaarde zwelbelasting	$F_{zwel;d}$ =	63	[kN]	rekenwaarde zwelbelasting incl. reductie

Sheet	**Zwelbelasting - analytische berekening V001**
Project	Generaal Vetterstraat 78-B te Amsterdam
Projectnummer	17499
Fase	Fundex Groutinjectie 460/560
Onderdeel	keldervloer
Datum	1-3-2018
Opsteller	hon

Berekening zwel agv ontgraving
Berekend wordt: de primaire zwel in de loop der tijd (consolidatie) en de secundaire zwel in de loop der tijd. Aan de hand hiervan wordt de zweldruk bepaald die op zal bouwen na aanleg van een vloer op een bepaald moment.

De resterende zweldruk wordt berekend volgens analytische methoden uit CUR202; zwel op palen volgens slipmethode; zwel op vloer volgens Koppejan.

Uitgangspunten: Horizontaal oneindige ontgraving / Zwellende grondlagen worden gecombineerd tot één laag met gemiddelde cv;zwel.

CRUX

P:\V\to\V499 Duyts Advies Generaal Vetterstraat A'dam\04 REK\Excel\[SH V499a1Zwelbelasting - analytische berekening v001tjs.xlsm]Fu Ok 460560


1. Invoer

1.1 Algemeen

Veiligheidsklasse	RC 2		
γ_{water}	10	[kN/m³]	
t_{eind}	10000	[dagen]	periode voor bepaling eindzwel
t_{zwel}	30	[dagen]	periode van vrije zwel; $t_{zwel} = \frac{1}{2} \times t_{ontgraven} + t_{aan} + t_{stort}$
η	1	[-]	modelfactor afh. van geometrie, zie figuur

$\gamma_{zwel;vloer}$ = 1,35 [-] partiële factor zweldruk op vloer

$\gamma_{zwel;paal}$ = 1,00 [-] partiële factor zweldruk enkele paal (alleenstaande paal, volledige slip)



1D als h << b; η = 1
2D als l >> b; η = 2
3D als b ≈ l; η = 3

1.2 Initiële gegevens

maaiveld	+0,85	[NAP .. m]
freatische GWS	-0,50	[NAP .. m] check PDF blz 60
onderkant zwellende lagen	-12,00	[NAP .. m]

1.3 Fasering

Fase	ontgraven	aanbrengen palen	start bemalen	aanbrengen vloer	leegpompen kuip
Tijdstip [dagen]	0	0	15	15	0

1.4 Ontgraving

ontgravingsniveau	-2,60	[NAP .. m]
waterstand in ontgraving	-3,10	[NAP .. m]
extra belasting	0,0	[kPa]

Δu = 26,0 [kPa] verandering waterspanning

Rekenen met spreiding?	Nee	spreiding conform Boussinesq
Breedte bouwkuip	50,0	[m]
Onderzijde damwand	-12,00	[NAP .. m] voor grondlagen boven ok wand wordt geen spreiding meegenomen!

1.5 Paalgegevens

paaltype	in de grond gevormd	
paalvorm	rond	
diameter schacht	0,51	[m]
hoh X-richting	2,00	[m]
hoh Y-richting	2,00	[m]

factor δ / φ = 1,00 [-]

O = 1,602 [m] schachtomtrek

$A_{stramien}$ = 4,00 [m²] stramienoppervlak

1.6 Grondprofiel

laag	type	head [NAP .. m]	bk [NAP .. m]	γ_d [kN/m³]	γ_{sat} [kN/m³]	ϕ [°]	OCR [-]	A_p [-]	A_s [-]	Cv [m²/s]	Cv;zwel / Cv [-]	Cv;zwel [m²/s]
Aanvullaag (zand)	Zand, n.c.	-0,50	+0,85	18,10	18,10	28,0	1,0	823	3854	0,100	8,0	0,800
Hollandveen	Veen, n.c.	-0,50	-2,60	10,50	10,50	17,0	1,0	183	559	8,00E-07	8,0	6,40E-06
Oude Zeeklei	Klei, n.c.	-0,50	-5,40	16,20	16,20	26,0	1,0	565	2379	6,00E-07	8,0	4,80E-06
Oude Zeeklei	Klei, n.c.	-0,50	-7,20	16,20	16,20	26,0	1,0	565	2379	6,00E-07	8,0	4,80E-06
Wadzand	Zand, n.c.	-0,50	-9,00	17,90	17,90	27,0	1,0	396	1832	1,00E-04	4,0	4,00E-04
Hydrobiaklei	Klei, n.c.	99	-10,00	15,20	15,20	26,0	1,0	464	1845	1,00E-06	8,0	8,00E-06
Basisveen	Veen, n.c.	99	-11,00	11,70	11,70	18,0	1,0	232	758	2,00E-08	8,0	1,60E-07
1ste zandlaag	Zand, n.c.	-3,10	-12,00	17,70	19,70	32,0	1,0	1130	5786	1,00E-04	8,0	8,00E-04
2e zandlaag	Zand, n.c.	-3,10	-17,00	16,90	18,90	33,0	1,0	965	4722	1,00E-04	8,0	8,00E-04


bij head 99 invullen voor interpolatie over de betreffende grondlaag

legen cellen grondlagen weergeven [+] legen cellen grondlagen weergeven

2. Numerieke uitvoer

ALGEMEEN

$\sigma'_{v;ontgniv}$ =	41,4	[kPa]	initiële korrelspanning op ontgravingsniveau
$\Delta p'$ =	-41,4	[kPa]	delta P waarmee gerekend wordt om zwel te bepalen
afstromen =	2	-zijdig	
d_{zwel} =	9,40	[m]	dikte zwellende grondlagen
h =	4,70	[m]	afstroomlengte (2-zijdige afstromen)
$C_{v;zwel;eq}$ =	2,765E-06	[m²/s]	
U(0) =	20	[%]	directe aanpassing



VRIJE ZWEL OP PAAL EN WAND (slipmethode)

- bovengrens slipmethode, alleenstaande paal met volledige slip
- aanpassing U = 0%

ONTGRAVEN GRONDPROFIEL

laag	bk [NAP .. m]	ok [NAP .. m]	dikte [m]	ϕ [°]	OCR [-]	K_0 [-]	$\sigma'_{v;mid;init.}$ [kPa]	$\sigma'_{v;mid;ontgr.}$ [kPa]	δ [°]	$K_0 \times \tan(\delta)$ [-]	$F_{zwel;rep;i}$ [kN]	$\Sigma F_{zwel;rep}$ [kN]	$\Sigma F_{zwel;rep;red}$ [%]
Hollandveen	-2,60	-5,40	2,80	17,0	1,0	0,71	42,1	0,7	17,0	2,72	8,5	9	9
Oude Zeeklei	-5,40	-7,20	1,80	26,0	1,0	0,56	48,4	7,0	26,0	0,92	18,6	27	27
Oude Zeeklei	-7,20	-9,00	1,80	26,0	1,0	0,56	59,6	18,1	26,0	0,63	33,2	60	51
Wadzand	-9,00	-10,00	1,00	27,0	1,0	0,55	69,1	27,7	27,0	0,55	24,5	85	62
Hydrobiaklei	-10,00	-11,00	1,00	26,0	1,0	0,56	82,2	40,7	26,0	0,50	32,4	117	71
Basisveen	-11,00	-12,00	1,00	18,0	1,0	0,69	98,6	57,2	18,0	0,46	42,1	159	76
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]

$F_{zwel;rep}$ =	159	[kN]	representatieve zwelbelasting ...	$F_{zwel;rep}$ =	76	[kN] representatieve zwelbelasting incl. reductie
$F_{zwel;d}$ =	159	[kN]	rekenwaarde zwelbelasting	$F_{zwel;d}$ =	76	[kN] rekenwaarde zwelbelasting incl. reductie

Sheet	**Zwelbelasting - analytische berekening V001**
Project	Generaal Vetterstraat 78-B te Amsterdam
Projectnummer	17499
Fase	DPA 410
Onderdeel	keldervloer
Datum	1-3-2018
Opsteller	hon

Berekening zwel agv ontgraving
Berekend wordt: de primaire zwel in de loop der tijd (consolidatie) en de secundaire zwel in de loop der tijd. Aan de hand hiervan wordt de zweldruk bepaald die op zal bouwen na aanleg van een vloer op een bepaald moment.

De resterende zweldruk wordt berekend volgens analytische methoden uit CUR202; zwel op palen volgens slipmethode; zwel op vloer volgens Koppejan.

Uitgangspunten: Horizontaal oneindige ontgraving / Zwellende grondlagen worden gecombineerd tot één laag met gemiddelde cv;zwel.

CRUX

P:\Wtx\V400 Duyts Advies Generaal Vetterstraat A'dam\04 REK\Excel\[SH V400ut Zwelbelasting - analytische berekening v001tjt.xlsm]DPA 410


1. Invoer

1.1 Algemeen

Veiligheidsklasse	RC 2		
γ_{water}	10	[kN/m³]	
t_{eind}	10000	[dagen]	periode voor bepaling eindzwel
t_{zwel}	30	[dagen]	periode van vrije zwel; $t_{zwel} = \frac{1}{2} \times t_{ontgraven} + t_{mat} + t_{stort}$
η	1	[-]	modelfactor afh. van geometrie, zie figuur

$\gamma_{zwel;vloer}$ = 1,35 [-] partiële factor zweldruk op vloer

$\gamma_{zwel;paal}$ = 1,00 [-] partiële factor zweldruk enkele paal (alleenstaande paal, volledige slip)



1D als h << b; η = 1
2D als l >> b; η = 2
3D als b ≈ l; η = 3

1.2 Initiële gegevens

maaiveld	+0,85	[NAP .. m]	
freatische GWS	-0,50	[NAP .. m]	check PDF blz 60
onderkant zwellende lagen	-12,00	[NAP .. m]	

1.3 Fasering

Fase	ontgraven	aanbrengen palen	start bemalen	aanbrengen vloer	leegpompen kuip
Tijdstip [dagen]	0	0	15	15	0

1.4 Ontgraving

ontgravingsniveau	-2,60	[NAP .. m]	
waterstand in ontgraving	-3,10	[NAP .. m]	
extra belasting	0,0	[kPa]	
Rekenen met spreiding?	Nee		spreiding conform Boussinesq
Breedte bouwkuip	50,0	[m]	
Onderzijde damwand	-12,00	[NAP .. m]	voor grondlagen boven ok wand wordt geen spreiding meegenomen!

Δu = 26,0 [kPa] verandering waterspanning

1.5 Paalgegevens

paaltype	in de grond gevormd		
paalvorm	rond		
diameter schacht	0,41	[m]	
hoh X-richting	2,00	[m]	
hoh Y-richting	2,00	[m]	

factor δ / φ = 1,00 [-]

O = 1,288 [m] schachtomtrek

$A_{stramien}$ = 4,00 [m²] stramienoppervlak

1.6 Grondprofiel

laag	type	head [NAP .. m]	bk [NAP .. m]	γ_d [kN/m³]	γ_{sat} [kN/m³]	φ [°]	OCR [-]	A_p [-]	A_s [-]	Cv [m²/s]	Cv;zwel / Cv [-]	Cv;zwel [m²/s]
Aanvullaag (zand)	Zand, n.c.	-0,50	+0,85	18,10	18,10	28,0	1,0	823	3854	0,100	8,0	0,800
Hollandveen	Veen, n.c.	-0,50	-2,60	10,50	10,50	17,0	1,0	183	559	8,00E-07	8,0	6,40E-06
Oude Zeeklei	Klei, n.c.	-0,50	-5,40	16,20	16,20	26,0	1,0	565	2379	6,00E-07	8,0	4,80E-06
Oude Zeeklei	Klei, n.c.	-0,50	-7,20	16,20	16,20	26,0	1,0	565	2379	6,00E-07	8,0	4,80E-06
Wadzand	Zand, n.c.	-0,50	-9,00	17,90	17,90	27,0	1,0	396	1832	1,00E-04	4,0	4,00E-04
Hydrobiaklei	Klei, n.c.	99	-10,00	15,20	15,20	26,0	1,0	464	1845	1,00E-06	8,0	8,00E-06
Basisveen	Veen, n.c.	99	-11,00	11,70	11,70	18,0	1,0	232	758	2,00E-08	8,0	1,60E-07
1ste zandlaag	Zand, n.c.	-3,10	-12,00	17,70	19,70	32,0	1,0	1130	5786	1,00E-04	8,0	8,00E-04
2e zandlaag	Zand, n.c.	-3,10	-17,00	16,90	18,90	33,0	1,0	965	4722	1,00E-04	8,0	8,00E-04


bij head 99 invullen voor interpolatie over de betreffende grondlaag

legen cellen grondlagen weergeven [+] legen cellen grondlagen weergeven

2. Numerieke uitvoer

ALGEMEEN

$\sigma'_{v;ontgniv}$ =	41,4	[kPa]	initiële korrelspanning op ontgravingsniveau
Δp' =	-41,4	[kPa]	delta P waarmee gerekend wordt om zwel te bepalen
afstromen =	2	-zijdig	
d_{zwel} =	9,40	[m]	dikte zwellende grondlagen
h =	4,70	[m]	afstroomlengte (2-zijdige afstromen)
$c_{v;zwel;eq}$ =	2,765E-06	[m²/s]	
U(0) =	20	[%]	directe aanpassing



VRIJE ZWEL OP PAAL EN WAND (slipmethode)
- bovengrens slipmethode, alleenstaande paal met volledige slip
- aanpassing U = 0%

ONTGRAVEN GRONDPROFIEL

laag	bk [NAP .. m]	ok [NAP .. m]	dikte [m]	φ [°]	OCR [-]	K_0 [-]	$\sigma'_{v;mid;init.}$ [kPa]	$\sigma'_{v;mid;ontgr.}$ [kPa]	δ [°]	K_0 x tan(δ) [-]	$F_{zwel;rep;i}$ [kN]	$\Sigma F_{zwel;rep}$ [kN]	$\Sigma F_{zwel;rep;red}$ [%]
Hollandveen	-2,60	-5,40	2,80	17,0	1,0	0,71	42,1	0,7	17,0	2,72	6,9	7	7
Oude Zeeklei	-5,40	-7,20	1,80	26,0	1,0	0,56	48,4	7,0	26,0	0,92	14,9	22	22
Oude Zeeklei	-7,20	-9,00	1,80	26,0	1,0	0,56	59,6	18,1	26,0	0,63	26,7	48	41
Wadzand	-9,00	-10,00	1,00	27,0	1,0	0,55	69,1	27,7	27,0	0,55	19,7	68	50
Hydrobiaklei	-10,00	-11,00	1,00	26,0	1,0	0,56	82,2	40,7	26,0	0,50	26,1	94	57
Basisveen	-11,00	-12,00	1,00	18,0	1,0	0,69	98,6	57,2	18,0	0,46	33,8	128	61
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]

$F_{zwel;rep}$ = 128 [kN] representatieve zwelbelasting ...
$F_{zwel;d}$ = 128 [kN] rekenwaarde zwelbelasting

$F_{zwel;rep}$ = 61 [kN] representatieve zwelbelasting incl. reductie
$F_{zwel;d}$ = 61 [kN] rekenwaarde zwelbelasting incl. reductie

Sheet	**Zwelbelasting - analytische berekening V001**
Project	Generaal Vetterstraat 78-B te Amsterdam
Projectnummer	17499
Fase	DPA 460
Onderdeel	keldervloer
Datum	1-3-2018
Opsteller	hon

Berekening zwel agv ontgraving
Berekend wordt: de primaire zwel in de loop der tijd (consolidatie) en de secundaire zwel in de loop der tijd. Aan de hand hiervan wordt de zweldruk bepaald die op zal bouwen na aanleg van een vloer op een bepaald moment.

De resterende zweldruk wordt berekend volgens analytische methoden uit CUR202; zwel op palen volgens slipmethode; zwel op vloer volgens Koppejan.

Uitgangspunten: Horizontaal oneindige ontgraving / Zwellende grondlagen worden gecombineerd tot één laag met gemiddelde cv;zwel.

CRUX

P:\Projecten\17499 Duijts Advies Generaal Vetterstraat A'dam\04 RENOExcel\[SH 17499a1Zwelbelasting - analytische berekening v001tjd.xlsm]DPA 460


1. Invoer

1.1 Algemeen

Veiligheidsklasse	RC 2		
γ_{water}	10	[kN/m³]	
t_{eind}	10000	[dagen]	periode voor bepaling eindzwel
t_{zwel}	30	[dagen]	periode van vrije zwel; $t_{zwel} = \frac{1}{2} \times t_{ontgraven} + t_{wal} + t_{stat}$
η	1	[-]	modelfactor afh. van geometrie, zie figuur

$\gamma_{zwel;vloer}$ = 1,35 [-] partiële factor zweldruk op vloer

$\gamma_{zwel;paal}$ = 1,00 [-] partiële factor zweldruk enkele paal (alleenstaande paal, volledige slip)



1D als h << b; η = 1
2D als l >> b; η = 2
3D als b ≈ l; η = 3

1.2 Initiële gegevens

maaiveld	+0,85	[NAP .. m]	
freatische GWS	-0,50	[NAP .. m]	check PDF blz 60
onderkant zwellende lagen	-12,00	[NAP .. m]	

1.3 Fasering

Fase	ontgraven	aanbrengen palen	start bemalen	aanbrengen vloer	leegpompen kuip
Tijdstip [dagen]	0	0	15	15	0

1.4 Ontgraving

ontgravingsniveau	-2,60	[NAP .. m]	
waterstand in ontgraving	-3,10	[NAP .. m]	
extra belasting	0,0	[kPa]	
Rekenen met spreiding?	Nee		spreiding conform Boussinesq
Breedte bouwkuip	50,0	[m]	
Onderzijde damwand	-12,00	[NAP .. m]	voor grondlagen boven ok wand wordt geen spreiding meegenomen!

Δu = 26,0 [kPa] verandering waterspanning

1.5 Paalgegevens

paaltype	in de grond gevormd		
paalvorm	rond		
diameter schacht	0,46	[m]	
hoh X-richting	2,00	[m]	
hoh Y-richting	2,00	[m]	

factor δ / φ = 1,00 [-]

O = 1,445 [m] schachtomtrek

$A_{stramien}$ = 4,00 [m²] stramienoppervlak

1.6 Grondprofiel

laag	type	head [NAP .. m]	bk [NAP .. m]	γ_d [kN/m³]	γ_{sat} [kN/m³]	ϕ [°]	OCR [-]	A_p [-]	A_s [-]	Cv [m²/s]	Cv;zwel / Cv [-]	Cv;zwel [m²/s]
Aanvullaag (zand)	Zand, n.c.	-0,50	+0,85	18,10	18,10	28,0	1,0	823	3854	0,100	8,0	0,800
Hollandveen	Veen, n.c.	-0,50	-2,60	10,50	10,50	17,0	1,0	183	559	8,00E-07	8,0	6,40E-06
Oude Zeeklei	Klei, n.c.	-0,50	-5,40	16,20	16,20	26,0	1,0	565	2379	6,00E-07	8,0	4,80E-06
Oude Zeeklei	Klei, n.c.	-0,50	-7,20	16,20	16,20	26,0	1,0	565	2379	6,00E-07	8,0	4,80E-06
Wadzand	Zand, n.c.	-0,50	-9,00	17,90	17,90	27,0	1,0	396	1832	1,00E-04	4,0	4,00E-04
Hydrobiaklei	Klei, n.c.	99	-10,00	15,20	15,20	26,0	1,0	464	1845	1,00E-06	8,0	8,00E-06
Basisveen	Veen, n.c.	99	-11,00	11,70	11,70	18,0	1,0	232	758	2,00E-08	8,0	1,60E-07
1ste zandlaag	Zand, n.c.	-3,10	-12,00	17,70	19,70	32,0	1,0	1130	5786	1,00E-04	8,0	8,00E-04
2e zandlaag	Zand, n.c.	-3,10	-17,00	16,90	18,90	33,0	1,0	965	4722	1,00E-04	8,0	8,00E-04


bij head 99 invullen voor interpolatie over de betreffende grondlaag

legen cellen grondlagen [weergeven] [+] legen cellen grondlagen weergeven

2. Numerieke uitvoer

ALGEMEEN

$\sigma'_{v;ontgniv}$ =	41,4	[kPa]	initiële korrelspanning op ontgravingsniveau
$\Delta p'$ =	-41,4	[kPa]	delta P waarmee gerekend wordt om zwel te bepalen
afstromen =	2	-zijdig	
d_{zwel} =	9,40	[m]	dikte zwellende grondlagen
h =	4,70	[m]	afstroomlengte (2-zijdige afstromen)
$C_{v;zwel;eq}$ =	2,765E-06	[m²/s]	
U(0) =	20	[%]	directe aanpassing



VRIJE ZWEL OP PAAL EN WAND (slipmethode)

- bovengrens slipmethode, alleenstaande paal met volledige slip
- aanpassing U = 0%

ONTGRAVEN GRONDPROFIEL

laag	bk [NAP .. m]	ok [NAP .. m]	dikte [m]	ϕ [°]	OCR [-]	K_0 [-]	$\sigma'_{v;mid;init.}$ [kPa]	$\sigma'_{v;mid;ontgr.}$ [kPa]	δ [°]	K_0 x tan(δ) [-]	$F_{zwel;rep;i}$ [kN]	$\Sigma F_{zwel;rep}$ [kN]	$\Sigma F_{zwel;rep;red}$ [%]
Hollandveen	-2,60	-5,40	2,80	17,0	1,0	0,71	42,1	0,7	17,0	2,72	7,7	8	8
Oude Zeeklei	-5,40	-7,20	1,80	26,0	1,0	0,56	48,4	7,0	26,0	0,92	16,7	24	24
Oude Zeeklei	-7,20	-9,00	1,80	26,0	1,0	0,56	59,6	18,1	26,0	0,63	29,9	54	46
Wadzand	-9,00	-10,00	1,00	27,0	1,0	0,55	69,1	27,7	27,0	0,55	22,1	76	56
Hydrobiaklei	-10,00	-11,00	1,00	26,0	1,0	0,56	82,2	40,7	26,0	0,50	29,3	106	64
Basisveen	-11,00	-12,00	1,00	18,0	1,0	0,69	98,6	57,2	18,0	0,46	38,0	144	69
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]

$F_{zwel;rep}$ = 144 [kN] representatieve zwelbelasting

$F_{zwel;d}$ = 144 [kN] rekenwaarde zwelbelasting

$F_{zwel;rep}$ = 69 [kN] representatieve zwelbelasting incl. reductie

$F_{zwel;d}$ = 69 [kN] rekenwaarde zwelbelasting incl. reductie

ZWEL OP VLOER

EINDZWEL (t = 10000d na ontgraven)

laag	bk	ok	dikte	A_p	A_s	$c_{v;zwel}$ / c_v	$c_{v;zwel}$	$\sigma'_{v;mid;init}$	$\Delta\sigma'_{v;mid;ontgr.}$	$w_{zw;prim}$	$w_{zw;sec}$	$w_{z;totaal}$	Reductie
	[NAP .. m]	[NAP .. m]	[m]	[-]	[-]	[-]	[m^2/s]	[kPa]	[kPa]	[m]	[m]	[m]	[%]
Hollandveen	-2,60	-5,40	2,80	183	559	8,0	6,40E-06	42,1	-41,4	-0,063	-0,082	-0,145	
Oude Zeeklei	-5,40	-7,20	1,80	565	2379	8,0	4,80E-06	48,4	-41,4	-0,006	-0,006	-0,012	
Oude Zeeklei	-7,20	-9,00	1,80	565	2379	8,0	4,80E-06	59,6	-41,4	-0,004	-0,004	-0,007	27,6
Wadzand	-9,00	-10,00	1,00	396	1832	4,0	4,00E-04	69,1	-41,4	-0,002	-0,002	-0,004	55,0
Hydrobiaklei	-10,00	-11,00	1,00	464	1845	8,0	8,00E-06	82,2	-41,4	-0,002	-0,002	-0,003	72,8
Basisveen	-11,00	-12,00	1,00	232	758	8,0	1,60E-07	98,6	-41,4	-0,002	-0,003	-0,005	86,9

Ongehinderde eindzwel met U(0) = 20%

t_{hydro}	U_{eind}	Σ $w_{primair}$	Σ $w_{secundair}$	Σ w_{totaal}
[dagen]	[%]	[mm]	[mm]	[mm]
185	100,0	-79	-98	-177

met modelfactor η = 1

$\sigma_{zwel;k}$	γ	$\sigma_{zwel;d}$
[kPa]	[-]	[kPa]
41,4	1,35	56,0

Opgetreden vrije zwel met U(0) = 20%

tot t	$U_{v;corr}$	$w_{primair}(t)$	$w_{secundair}(t)$	w(t)
[dagen]	[%]	[mm]	[mm]	[mm]
30	70,9	-56	-36	-92

met modelfactor η = 1

$\sigma_{zwel;k}$	γ	$\sigma_{zwel;d}$
[kPa]	[-]	[kPa]
29,4	1,35	39,7

Opbouw zweldruk op vloer met U(0) = 20%

vanaf t	$U_{v;corr;rest}$	$w_{primair}(t)$	$w_{secundair}(t)$	w(t)
[dagen]	[%]	[mm]	[mm]	[mm]
30	29,1	-23	-62	-85

met modelfactor η = 1

$\sigma_{zwel;k}$	γ	$\sigma_{zwel;d}$
[kPa]	[-]	[kPa]
12,1	1,35	16,3

Bijlage 3 Uitvoer D-Foundation druk

Deformation

Design and Verification according to Eurocode 7 of Bearing/Tension Piles and Shallow Foundations
Developed by Deltares

Company:	CRUX Engineering B.V.
Date of report:	5-3-2018
Time of report:	13:58:25
Date of calculation:	5-3-2018
Time of calculation:	13:57:44
Filename:	P:\..\04 REK\GEO\Paal\DFoua1 Drukdraagvermogen kelder -2,6
Project identification:	
	D-Foundations DFoua1 Drukdraagvermogen kelder -2,6

Contents

1 Table of Contents 2
2 Input Data 3
2.1 General Input Data 3
2.2 General Report Data 3
2.3 Application Area Model Bearing Piles 3
2.4 Superstructure 3
2.5 General CPT Data 3
2.5.1 View of CPT's in Foundation Plan 3
2.6 Soil Data 4
2.6.1 Soil Profile 3 4
2.6.2 Soil Profile 5 5
2.6.3 Soil Profile 6 6
2.6.4 Soil Profile 8 7
2.6.5 Soil Profile 9 9
2.7 Pile Types 10
2.7.1 Pile type : fundex 460-560 10
2.7.2 Pile type : fundex 380-450 10
2.7.3 Pile type : DPA 360 11
2.7.4 Pile type : DPA 410 11
2.7.5 Pile type : DPA 460 12
2.8 Foundation Plan 12
2.8.1 View of Foundation Plan 13
2.9 Excavation Data 13
2.10 Overruled Parameters 14
2.11 Model Options 14
2.12 Model Options 14
3 Bearing Piles (EC7-NL): Results of the Option Preliminary Design, Indication Bearing Capacity 15
3.1 Errors and Warnings 15
3.2 Remarks 15
3.3 Calculation Parameters 15
3.3.1 Pile Factors 15
3.3.2 Pile type : fundex 460-560 15
3.3.3 Pile type : DPA 410 16
3.3.4 Pile type : fundex 380-450 17
3.3.5 Pile type : DPA 460 17
3.4 Results Bearing Forces for Pile type : fundex 460-560 18
3.5 Results Bearing Forces for Pile type : DPA 410 19
3.6 Results Bearing Forces for Pile type : fundex 380-450 19
3.7 Results Bearing Forces for Pile type : DPA 460 20
3.8 Summary Net Bearing Capacity in kN 21

n

ener n

Model Bearing Piles (EC7-NL)

ener e or

Geotechnical consultant :
Design engineer superstructure :
Principal :
Title 1 :
Title 2 :
Title 3 : D-Foundations DFoua1 Drukdraagvermogen kelder -2,6
Number of project :
Location of project :

3 i ion re ode e ring ie

The verifications performed by the model BEARING PILES of D-FOUNDATIONS concern pile foundations on which axial static or quasi-static loads cause pressures in the piles. The calculations of pile forces and pile displacements are based on Cone Penetration Tests. Possible rise of (tension-)piles and horizontal displacements of piles and/or pile groups are not taken into account.


2.4 Superstructure

Rigidity of the superstructure : Non-Rigid

2.5 General CPT Data

Number of CPT's : 5
Timing of CPT's : CPT - Install - Excavation

2.5.1 View of CPT's in Foundation Plan






Number/Name CPT	Pile tip level [m R.L.]	Top of pos. friction zone [m R.L.]	Bottom of neg. friction zone [m R.L.]	X-coor-dinate [m]	Y-coor-dinate [m]
1: 3	-19,26	-11,60	-11,60	118155,78	484051,62
2: 5	-19,26	-11,40	-11,40	0,00	0,00
3: 6	-19,26	-11,60	-11,60	118139,99	484052,09
4: 8	-19,26	-11,40	-11,40	0,00	0,00
5: 9	-19,26	-11,00	-11,00	118121,90	484051,98

2.6 Soil Data

Number of soil profiles (= number of CPT's) : 5

2.6.1 Soil Profile 3

Belonging to CPT 3
Surface level in [m. reference level] : 0,84
Phreatic level in [m. reference level] : -0,50
Pile tip level in [m. reference level] : -19,26
Top of positive skin friction zone in [m. reference level] : -11,60
Bottom of negative skin friction zone in [m. reference level] : -11,60
OCR-value foundation layer : 1,00
Expected groundlevel settlement in [m] : 0,00
Number of layers in profile : 30




Number layer	Top layer [m R.L.]	Gamma [kN/m3]	Gamma;sat [kN/m3]	Phi [deg]	Soil Type	Median (Sand/Gravel) [mm]
1	0,840	19,00	21,00	30,00	Sand	0,200
2	0,340	19,00	21,00	30,00	Sand	0,200
3	0,240	19,00	21,00	30,00	Sand	0,200
4	0,040	19,00	21,00	32,50	Sand	0,200
5	-1,960	19,00	21,00	30,00	Sand	0,200
6	-2,060	19,00	21,00	32,50	Sand	0,200
7	-2,560	19,00	21,00	30,00	Sand	0,200
8	-2,760	20,00	20,00	22,50	Clay	--

Number layer	Top layer [m R.L.]	Gamma [kN/m3]	Gamma;sat [kN/m3]	Phi [deg]	Soil Type	Median (Sand/Gravel) [mm]
9	-2,860	17,00	17,00	17,50	Clay	--
10	-3,260	13,00	13,00	15,00	Peat	--
11	-5,000	17,00	17,00	17,50	Clay	--
12	-5,220	20,00	20,00	22,50	Clay	--
13	-5,939	20,00	20,00	35,00	Loam	--
14	-6,239	20,00	20,00	22,50	Clay	--
15	-6,539	20,00	20,00	35,00	Loam	--
16	-6,839	20,00	20,00	22,50	Clay	--
17	-7,139	20,00	20,00	35,00	Loam	--
18	-8,559	19,00	21,00	30,00	Sand	0,200
19	-9,178	20,00	20,00	35,00	Loam	--
20	-9,478	20,00	20,00	22,50	Clay	--
21	-9,678	20,00	20,00	35,00	Loam	--
22	-10,378	20,00	20,00	22,50	Clay	--
23	-10,697	20,00	20,00	35,00	Loam	--
24	-11,597	20,00	20,00	22,50	Clay	--
25	-11,697	17,00	17,00	17,50	Clay	--
26	-11,797	20,00	20,00	22,50	Clay	--
27	-11,916	20,00	20,00	35,00	Loam	--
28	-12,016	19,00	21,00	30,00	Sand	0,200
29	-12,116	19,00	21,00	32,50	Sand	0,200
30	-24,024	19,00	21,00	32,50	Sand	0,200

2.6.2 Soil Profile 5


Belonging to CPT	5
Surface level in [m. reference level] :	0,84
Phreatic level in [m. reference level] :	-0,50
Pile tip level in [m. reference level] :	-19,26
Top of positive skin friction zone in [m. reference level] :	-11,40
Bottom of negative skin friction zone in [m. reference level] :	-11,40
OCR-value foundation layer :	1,00
Expected groundlevel settlement in [m] :	0,00
Number of layers in profile :	30



Number layer	Top layer [m R.L.]	Gamma [kN/m3]	Gamma;sat [kN/m3]	Phi [deg]	Soil Type	Median (Sand/Gravel) [mm]
1	0,840	20,00	20,00	35,00	Loam	--
2	0,440	20,00	20,00	35,00	Loam	--
3	0,340	20,00	20,00	35,00	Loam	--
4	0,240	19,00	21,00	32,50	Sand	0,200
5	-1,760	19,00	21,00	30,00	Sand	0,200
6	-1,960	19,00	21,00	32,50	Sand	0,200
7	-2,679	19,00	21,00	30,00	Sand	0,200
8	-2,879	20,00	20,00	35,00	Loam	--
9	-2,979	20,00	20,00	22,50	Clay	--
10	-3,079	17,00	17,00	17,50	Clay	--
11	-3,179	13,00	13,00	15,00	Peat	--
12	-5,118	17,00	17,00	17,50	Clay	--
13	-5,318	20,00	20,00	22,50	Clay	--
14	-6,157	20,00	20,00	35,00	Loam	--
15	-6,457	20,00	20,00	22,50	Clay	--
16	-6,557	20,00	20,00	35,00	Loam	--
17	-6,976	20,00	20,00	22,50	Clay	--
18	-7,595	20,00	20,00	35,00	Loam	--
19	-7,895	19,00	21,00	30,00	Sand	0,200
20	-7,995	20,00	20,00	35,00	Loam	--
21	-8,295	19,00	21,00	30,00	Sand	0,200
22	-8,814	20,00	20,00	35,00	Loam	--
23	-9,233	20,00	20,00	22,50	Clay	--
24	-9,533	20,00	20,00	35,00	Loam	--
25	-9,952	20,00	20,00	22,50	Clay	--
26	-10,671	20,00	20,00	35,00	Loam	--
27	-11,190	20,00	20,00	22,50	Clay	--
28	-11,509	19,00	21,00	30,00	Sand	0,200
29	-11,609	19,00	21,00	32,50	Sand	0,200
30	-25,770	19,00	21,00	32,50	Sand	0,200

2.6.3 Soil Profile 6

Belonging to CPT	6
Surface level in [m. reference level] :	0,85
Phreatic level in [m. reference level] :	-0,50
Pile tip level in [m. reference level] :	-19,26
Top of positive skin friction zone in [m. reference level] :	-11,60
Bottom of negative skin friction zone in [m. reference level] :	-11,60
OCR-value foundation layer :	1,00
Expected groundlevel settlement in [m] :	0,00
Number of layers in profile :	27




Number layer	Top layer [m R.L.]	Gamma [kN/m3]	Gamma;sat [kN/m3]	Phi [deg]	Soil Type	Median (Sand/Gravel) [mm]
1	0,850	19,00	21,00	30,00	Sand	0,200
2	-0,350	19,00	21,00	30,00	Sand	0,200
3	-0,450	19,00	21,00	30,00	Sand	0,200
4	-0,850	19,00	21,00	32,50	Sand	0,200
5	-1,750	19,00	21,00	30,00	Sand	0,200
6	-1,970	19,00	21,00	32,50	Sand	0,200
7	-2,289	19,00	21,00	30,00	Sand	0,200
8	-2,589	20,00	20,00	22,50	Clay	--
9	-2,689	17,00	17,00	17,50	Clay	--
10	-2,789	13,00	13,00	15,00	Peat	--
11	-5,008	17,00	17,00	17,50	Clay	--
12	-5,308	20,00	20,00	22,50	Clay	--
13	-7,646	20,00	20,00	35,00	Loam	--
14	-8,465	19,00	21,00	30,00	Sand	0,200
15	-9,184	20,00	20,00	35,00	Loam	--
16	-9,303	20,00	20,00	22,50	Clay	--
17	-9,603	20,00	20,00	35,00	Loam	--
18	-10,122	20,00	20,00	22,50	Clay	--
19	-10,960	20,00	20,00	35,00	Loam	--
20	-11,379	20,00	20,00	22,50	Clay	--
21	-11,479	17,00	17,00	17,50	Clay	--
22	-11,579	13,00	13,00	15,00	Peat	--
23	-11,679	17,00	17,00	17,50	Clay	--
24	-11,798	20,00	20,00	35,00	Loam	--
25	-11,898	19,00	21,00	30,00	Sand	0,200
26	-11,998	19,00	21,00	32,50	Sand	0,200
27	-23,987	19,00	21,00	32,50	Sand	0,200

2.6.4 Soil Profile 8

Belonging to CPT	8
Surface level in [m. reference level] :	0,85
Phreatic level in [m. reference level] :	-0,50

Pile tip level in [m. reference level] :	-19,26
Top of positive skin friction zone in [m. reference level] :	-11,40
Bottom of negative skin friction zone in [m. reference level] :	-11,40
OCR-value foundation layer :	1,00
Expected groundlevel settlement in [m] :	0,00
Number of layers in profile :	33




Number layer	Top layer [m R.L.]	Gamma [kN/m3]	Gamma;sat [kN/m3]	Phi [deg]	Soil Type	Median (Sand/Gravel) [mm]
1	0,850	19,00	21,00	32,50	Sand	0,200
2	0,450	19,00	21,00	32,50	Sand	0,200
3	0,350	19,00	21,00	32,50	Sand	0,200
4	0,250	19,00	21,00	30,00	Sand	0,200
5	-0,650	19,00	21,00	32,50	Sand	0,200
6	-0,950	19,00	21,00	30,00	Sand	0,200
7	-1,150	19,00	21,00	32,50	Sand	0,200
8	-1,850	19,00	21,00	30,00	Sand	0,200
9	-1,950	19,00	21,00	32,50	Sand	0,200
10	-3,250	19,00	21,00	30,00	Sand	0,200
11	-3,550	20,00	20,00	35,00	Loam	--
12	-3,650	20,00	20,00	22,50	Clay	--
13	-3,750	17,00	17,00	17,50	Clay	--
14	-3,950	13,00	13,00	15,00	Peat	--
15	-5,289	17,00	17,00	17,50	Clay	--
16	-5,489	20,00	20,00	22,50	Clay	--
17	-5,789	17,00	17,00	17,50	Clay	--
18	-5,889	20,00	20,00	22,50	Clay	--
19	-6,389	20,00	20,00	35,00	Loam	--
20	-6,689	20,00	20,00	22,50	Clay	--
21	-7,389	20,00	20,00	35,00	Loam	--
22	-8,428	19,00	21,00	30,00	Sand	0,200
23	-8,628	20,00	20,00	35,00	Loam	--
24	-9,228	20,00	20,00	22,50	Clay	--
25	-9,528	20,00	20,00	35,00	Loam	--
26	-9,947	20,00	20,00	22,50	Clay	--
27	-11,366	20,00	20,00	35,00	Loam	--

Number layer	Top layer [m R.L.]	Gamma [kN/m3]	Gamma;sat [kN/m3]	Phi [deg]	Soil Type	Median (Sand/Gravel) [mm]
28	-11,466	19,00	21,00	30,00	Sand	0,200
29	-11,566	19,00	21,00	32,50	Sand	0,200
30	-15,061	19,00	21,00	30,00	Sand	0,200
31	-15,380	19,00	21,00	32,50	Sand	0,200
32	-17,037	19,00	21,00	30,00	Sand	0,200
33	-17,137	19,00	21,00	32,50	Sand	0,200

2.6.5 Soil Profile

Belonging to CPT	9
Surface level in [m. reference level] :	0,79
Phreatic level in [m. reference level] :	-0,50
Pile tip level in [m. reference level] :	-19,26
Top of positive skin friction zone in [m. reference level] :	-11,00
Bottom of negative skin friction zone in [m. reference level] :	-11,00
OCR-value foundation layer :	1,00
Expected groundlevel settlement in [m] :	0,00
Number of layers in profile :	28



Number layer	Top layer [m R.L.]	Gamma [kN/m3]	Gamma;sat [kN/m3]	Phi [deg]	Soil Type	Median (Sand/Gravel) [mm]
1	0,790	19,00	21,00	30,00	Sand	0,200
2	0,290	19,00	21,00	30,00	Sand	0,200
3	0,190	19,00	21,00	30,00	Sand	0,200
4	-0,210	19,00	21,00	32,50	Sand	0,200
5	-2,510	19,00	21,00	30,00	Sand	0,200
6	-2,710	20,00	20,00	35,00	Loam	--
7	-2,810	17,00	17,00	17,50	Clay	--
8	-3,010	13,00	13,00	15,00	Peat	--
9	-3,810	13,00	13,00	15,00	Peat	--
10	-4,010	13,00	13,00	15,00	Peat	--
11	-5,010	17,00	17,00	17,50	Clay	--
12	-5,510	20,00	20,00	22,50	Clay	--

Number layer	Top layer [m R.L.]	Gamma [kN/m3]	Gamma;sat [kN/m3]	Phi [deg]	Soil Type	Median (Sand/Gravel) [mm]
13	-6,790	20,00	20,00	35,00	Loam	--
14	-7,009	20,00	20,00	22,50	Clay	--
15	-7,409	20,00	20,00	35,00	Loam	--
16	-8,509	19,00	21,00	30,00	Sand	0,200
17	-8,709	20,00	20,00	35,00	Loam	--
18	-8,809	19,00	21,00	30,00	Sand	0,200
19	-8,909	20,00	20,00	35,00	Loam	--
20	-9,109	20,00	20,00	22,50	Clay	--
21	-9,509	20,00	20,00	35,00	Loam	--
22	-10,028	20,00	20,00	22,50	Clay	--
23	-10,828	20,00	20,00	35,00	Loam	--
24	-10,928	20,00	20,00	22,50	Clay	--
25	-11,028	20,00	20,00	35,00	Loam	--
26	-11,128	19,00	21,00	30,00	Sand	0,200
27	-11,228	19,00	21,00	32,50	Sand	0,200
28	-24,059	19,00	21,00	32,50	Sand	0,200

2.7 Pile Types

2.7.1 Pile type : funde 460-560

Pile type :	User defined (vibrating)

Note: This user defined pile type is considered not to be of a in place formed type.
Hence the characteristic value of the friction angle at the pile shaft (delta) will be taken as 0.75 * phi.

Pile type for determination of execution factor alpha_s in sand/gravel:
Screw pile, cast in place, lost tip

Pile type for determination of exectution factor alpha_s in clay/loam/peat:
User defined

alpha_s clay/loam/peat :	0,0000

Evidence to support chosen alpha_s should be provided.

Pile type for determination of pile class factor alpha_p :
Screw pile, cast in place, lost tip

Pile type for use in load/settlement curve :	1
Materialtype for pile :	Concrete
Slip layer :	None
Pile shape :	Round pile with lost tip
beta (user defined : Pile tip, shape factor) :	1,00
s (user defined : factor for the influence of the shape of the crosssection of the pile base) :	1,00

Pile dimensions :

Diameter at tip [m] :	0,560
Diameter shaft [m] :	0,510
Effective heigth enlarged base [m] :	0,000

2.7.2 Pile type : funde 380-450

Pile type :	User defined (vibrating)

Note: This user defined pile type is considered not to be of a in place formed type.
Hence the characteristic value of the friction angle at the pile shaft (delta) will be taken as 0.75 * phi.

Pile type for determination of execution factor alpha_s in sand/gravel:
Screw pile, cast in place, with grout

Pile type for determination of exectution factor alpha_s in clay/loam/peat:
User defined

alpha_s clay/loam/peat :	0,0000

Evidence to support chosen alpha_s should be provided.

Pile type for determination of pile class factor alpha_p :
Screw pile, cast in place, with grout

Pile type for use in load/settlement curve :	1
Materialtype for pile :	Concrete
Slip layer :	None
Pile shape :	Round pile with lost tip
beta (user defined : Pile tip, shape factor) :	1,00
s (user defined : factor for the influence of the shape of the crosssection of the pile base) :	1,00

Pile dimensions :

Diameter at tip [m] :	0,450
Diameter shaft [m] :	0,415
Effective heigth enlarged base [m] :	0,000

2.7.3 Pile type : DP 360

Pile type : User defined (vibrating)
Note: This user defined pile type is considered to be of a in place formed type.
Hence the characteristic value of the friction angle at the pile shaft (delta) will be taken as 1.0 * phi.

Pile type for determination of execution factor alpha_s in sand/gravel:
User defined
alpha_s Sand : 0,0100
Evidence to support chosen alpha_s should be provided.

Pile type for determination of exectution factor alpha_s in clay/loam/peat:
User defined
alpha_s clay/loam/peat : 0,0000
Evidence to support chosen alpha_s should be provided.

Pile type for determination of pile class factor alpha_p :
User defined
alpha_p : 0,5600
Evidence to support chosen alpha_p should be provided.

Pile type for use in load/settlement curve :	1
Materialtype for pile :	Concrete
Slip layer :	None
Pile shape :	Round pile
beta (user defined : Pile tip, shape factor) :	1,00
s (user defined : factor for the influence of the shape of the crosssection of the pile base) :	1,00

Pile dimensions :
Diameter [m] : 0,360

2.7.4 Pile type : DP 410

Pile type : User defined (vibrating)
Note: This user defined pile type is considered to be of a in place formed type.
Hence the characteristic value of the friction angle at the pile shaft (delta) will be taken as 1.0 * phi.

Pile type for determination of execution factor alpha_s in sand/gravel:
User defined
alpha_s Sand : 0,0100
Evidence to support chosen alpha_s should be provided.

Pile type for determination of exectution factor alpha_s in clay/loam/peat:
User defined
alpha_s clay/loam/peat : 0,0000

Evidence to support chosen alpha_s should be provided.

Pile type for determination of pile class factor alpha_p :
User defined
alpha_p : 0,5600
Evidence to support chosen alpha_p should be provided.

Pile type for use in load/settlement curve :	1
Materialtype for pile :	Concrete
Slip layer :	None
Pile shape :	Round pile
beta (user defined : Pile tip, shape factor) :	1,00
s (user defined : factor for the influence of the shape of the crosssection of the pile base) :	1,00

Pile dimensions :
Diameter [m] : 0,410

2.7.5 Pile type : DP 460

Pile type : User defined (vibrating)
Note: This user defined pile type is considered to be of a in place formed type.
Hence the characteristic value of the friction angle at the pile shaft (delta) will be taken as 1.0 * phi.

Pile type for determination of execution factor alpha_s in sand/gravel:
User defined
alpha_s Sand : 0,0100
Evidence to support chosen alpha_s should be provided.

Pile type for determination of exectution factor alpha_s in clay/loam/peat:
User defined
alpha_s clay/loam/peat : 0,0000
Evidence to support chosen alpha_s should be provided.

Pile type for determination of pile class factor alpha_p :
User defined
alpha_p : 0,5600
Evidence to support chosen alpha_p should be provided.

Pile type for use in load/settlement curve :	1
Materialtype for pile :	Concrete
Slip layer :	None
Pile shape :	Round pile
beta (user defined : Pile tip, shape factor) :	1,00
s (user defined : factor for the influence of the shape of the crosssection of the pile base) :	1,00

Pile dimensions :
Diameter [m] : 0,460

2.8 Foundation Plan

Number of piles :	1
Number of collaborating piles* :	1

* : 0 = not defined, 1 = non rigid superstructure, >1 = rigid superstructure


2.8.1 View of Foundation Plan



Pile nr/name	X-coor-dinate [m]	Y-coor-dinate [m]	Fc;d (STR/GEO) [kN]	Fc;d (SLS) [kN]	P0 [kN/m2]	Pile head level [m R.L.]
1: 1	-5,00	-5,00	0,00	0,00	0,00	-2,60

2. Excavation Data

Excavation level in [m. reference level] : -2,60
Reduction model : Safe (NEN)



2.10 Overruled Parameters

User defined gamma;b [-] : 1,20
User defined gamma;s [-] : 1,20

2.11 Model Options

Use pilegroup for negative skin friction (standard)
Do not create intermediate results file
Use reduction for continuous flight auger piles (standard)
Use the influence of excavations (standard).

2.12 Model Options

Selected pile types :
- -fundex 460-560
- -DPA 410
- -fundex 380-450
- -DPA 460

Selected profiles :
- -3
- -5
- -6
- -8
- -9

Trajectory
- -begin [m] : -18,00
- -end [m] : -21,50
- -interval [m] : 0,50

3 Bearing Piles EC7-□□: Results of t□e □ption Preliminar□ Design, ndication Bearing Ca

3.1 Errors and □arnings

Warning : The factor gamma;b (NEN 9997-1:2016) is user defined. Evidence to support this from the NEN deviating value has to be provided.
Warning : The factor gamma;s (NEN 9997-1:2016) is user defined. Evidence to support this from the NEN deviating value has to be provided.
Pile Type fundex 460-560: Warning : The factor Beta (NEN 9997-1:2016 art. 7.6.2.3(g)) is user defined. Evidence to support this from the NEN deviating value has to be provided.
Pile Type fundex 460-560: Warning : The factor s (NEN 9997-1:2016 art. 7.6.2.3(h)) is user defined. Evidence to support this from the NEN deviating value has to be provided.
Pile Type DPA 410: Warning : The factor Beta (NEN 9997-1:2016 art. 7.6.2.3(g)) is user defined. Evidence to support this from the NEN deviating value has to be provided.
Pile Type DPA 410: Warning : The factor s (NEN 9997-1:2016 art. 7.6.2.3(h)) is user defined. Evidence to support this from the NEN deviating value has to be provided.
Pile Type fundex 380-450: Warning : The factor Beta (NEN 9997-1:2016 art. 7.6.2.3(g)) is user defined. Evidence to support this from the NEN deviating value has to be provided.
Pile Type fundex 380-450: Warning : The factor s (NEN 9997-1:2016 art. 7.6.2.3(h)) is user defined. Evidence to support this from the NEN deviating value has to be provided.
Pile Type DPA 460: Warning : The factor Beta (NEN 9997-1:2016 art. 7.6.2.3(g)) is user defined. Evidence to support this from the NEN deviating value has to be provided.
Pile Type DPA 460: Warning : The factor s (NEN 9997-1:2016 art. 7.6.2.3(h)) is user defined. Evidence to support this from the NEN deviating value has to be provided.

3.2 Remarks

When checking the survey and testing of soil according to NEN 9997-1:2016 art. 3.2.3 lid (e), the program uses the provided CPT test level. It does NOT take into account possible different pile tip levels. When different pile tip levels are used in this calculation, the user itself must check for possibly required additional survey and testing of soil.

Note : The calculations performed are based on a single pile for limit state STR/GEO (= ultimate limit state).
Due to the nature of preliminary design, a single pile is always assumed. A possible pileplan is disregarded when using the preliminary design option. Hence a non rigid superstructure is assumed and pile group effects are not considered.

3.3 Calculation Parameters

3.3.1 Pile Factors

gamma;b (Limit State STR/GEO, user defined) :	1,20
gamma;s (Limit State STR/GEO, user defined) :	1,20
xi3 (NEN 9997-1:2016, table A.10a, for N = 5) :	1,28
xi4 (NEN 9997-1:2016, table A.10a, for N = 5) :	1,03

3.3.2 Pile t□pe : funde□ 460-560

Pile type : User defined (vibrating)
Note: This user defined pile type is considered not to be of a in place formed type.
Hence the characteristic value of the friction angle at the pile shaft (delta) will be taken as 0.75 * phi.

Pile type for determination of execution factor alpha_s in sand/gravel:
Screw pile, cast in place, lost tip

Pile type for determination of exectution factor alpha_s in clay/loam/peat:
User defined
alpha_s clay/loam/peat : 0,0000
Evidence to support chosen alpha_s should be provided.

Pile type for determination of pile class factor alpha_p :
Screw pile, cast in place, lost tip

Pile type for use in load/settlement curve : 1
Materialtype for pile : Concrete
Slip layer : None
Pile shape : Round pile with lost tip
beta (user defined : Pile tip, shape factor) : 1,00
s (user defined : factor for the influence of the shape of the crosssection of the pile base) : 1,00

Pile dimensions :
Diameter at tip [m] : 0,560
Diameter shaft [m] : 0,510
Effective heigth enlarged base [m] : 0,000

CPT	Alpha_s Sand/ Gravel	Alpha_s Clay/Loam Peat	Alpha_p
3	0,0090	--	0,6300
5	0,0090	--	0,6300
6	0,0090	--	0,6300
8	0,0090	--	0,6300
9	0,0090	--	0,6300

3.3.3 Pile t□pe : DP□ 410

Pile type : User defined (vibrating)
Note: This user defined pile type is considered to be of a in place formed type.
Hence the characteristic value of the friction angle at the pile shaft (delta) will be taken as 1.0 * phi.

Pile type for determination of execution factor alpha_s in sand/gravel:
User defined
alpha_s Sand : 0,0100
Evidence to support chosen alpha_s should be provided.

Pile type for determination of exectution factor alpha_s in clay/loam/peat:
User defined
alpha_s clay/loam/peat : 0,0000
Evidence to support chosen alpha_s should be provided.

Pile type for determination of pile class factor alpha_p :
User defined
alpha_p : 0,5600
Evidence to support chosen alpha_p should be provided.

Pile type for use in load/settlement curve : 1
Materialtype for pile : Concrete
Slip layer : None
Pile shape : Round pile
beta (user defined : Pile tip, shape factor) : 1,00
s (user defined : factor for the influence of the shape of the crosssection of the pile base) : 1,00

Pile dimensions :
Diameter [m] : 0,410

CPT	Alpha_s Sand/ Gravel	Alpha_s Clay/Loam Peat	Alpha_p
3	0,0100	--	0,5600
5	0,0100	--	0,5600
6	0,0100	--	0,5600
8	0,0100	--	0,5600
9	0,0100	--	0,5600

3.3.4 Pile type : funde 380-450

Pile type : User defined (vibrating)
Note: This user defined pile type is considered not to be of a in place formed type.
Hence the characteristic value of the friction angle at the pile shaft (delta) will be taken as 0.75 * phi.

Pile type for determination of execution factor alpha_s in sand/gravel:
Screw pile, cast in place, with grout

Pile type for determination of exectution factor alpha_s in clay/loam/peat:
User defined
alpha_s clay/loam/peat : 0,0000
Evidence to support chosen alpha_s should be provided.

Pile type for determination of pile class factor alpha_p :
Screw pile, cast in place, with grout

Pile type for use in load/settlement curve : 1
Materialtype for pile : Concrete
Slip layer : None
Pile shape : Round pile with lost tip
beta (user defined : Pile tip, shape factor) : 1,00
s (user defined : factor for the influence of the
shape of the crosssection of the pile base) : 1,00

Pile dimensions :
Diameter at tip [m] : 0,450
Diameter shaft [m] : 0,415
Effective heigth enlarged base [m] : 0,000

CPT	Alpha_s Sand/ Gravel	Alpha_s Clay/Loam Peat	Alpha_p
3	0,0090	--	0,6300
5	0,0090	--	0,6300
6	0,0090	--	0,6300
8	0,0090	--	0,6300
9	0,0090	--	0,6300

3.3.5 Pile type : DP 460

Pile type : User defined (vibrating)
Note: This user defined pile type is considered to be of a in place formed type.
Hence the characteristic value of the friction angle at the pile shaft (delta) will be taken as 1.0 * phi.

Pile type for determination of execution factor alpha_s in sand/gravel:
User defined
alpha_s Sand : 0,0100
Evidence to support chosen alpha_s should be provided.

Pile type for determination of exectution factor alpha_s in clay/loam/peat:
User defined
alpha_s clay/loam/peat : 0,0000
Evidence to support chosen alpha_s should be provided.

Pile type for determination of pile class factor alpha_p :
User defined
alpha_p : 0,5600
Evidence to support chosen alpha_p should be provided.

Pile type for use in load/settlement curve : 1
Materialtype for pile : Concrete
Slip layer : None
Pile shape : Round pile

beta (user defined : Pile tip, shape factor) : 1,00
s (user defined : factor for the influence of the
shape of the crosssection of the pile base) : 1,00

Pile dimensions :
Diameter [m] : 0,460

CPT	Alpha_s Sand/ Gravel	Alpha_s Clay/Loam Peat	Alpha_p
3	0,0100	--	0,5600
5	0,0100	--	0,5600
6	0,0100	--	0,5600
8	0,0100	--	0,5600
9	0,0100	--	0,5600

3.4 Results Bearing Forces for Pile type : funde 460-560

CPT name	Level [m R.L.]	Rb;cal;max [kN]	Rs;cal;max [kN]	Rc;cal;max [kN]	Rc;d [kN]	F;nsf;rep [kN]	Fnsf;d [kN]	Rc;net;d [kN]
3	-18.00	1588	851	2439	1588	0	0	1588
3	-18.50	2808	945	3753	2443	0	0	2443
3	-19.00	3593	1061	4654	3030	0	0	3030
3	-19.50	3506	1169	4675	3044	0	0	3044
3	-20.00	3569	1277	4846	3155	0	0	3155
3	-20.50	3669	1385	5054	3290	0	0	3290
3	-21.00	3695	1493	5188	3378	0	0	3378
3	-21.50	3695	1602	5297	3449	0	0	3449
5	-18.00	3097	822	3919	2551	0	0	2551
5	-18.50	3470	930	4400	2865	0	0	2865
5	-19.00	3695	1038	4733	3081	0	0	3081
5	-19.50	2590	1146	3736	2432	0	0	2432
5	-20.00	2209	1255	3464	2255	0	0	2255
5	-20.50	2103	1363	3466	2257	0	0	2257
5	-21.00	1952	1471	3423	2229	0	0	2229
5	-21.50	1711	1579	3290	2142	0	0	2142
6	-18.00	2051	838	2889	1881	0	0	1881
6	-18.50	2162	946	3108	2023	0	0	2023
6	-19.00	2185	1054	3239	2109	0	0	2109
6	-19.50	2530	1162	3692	2404	0	0	2404
6	-20.00	3237	1270	4507	2934	0	0	2934
6	-20.50	3695	1379	5074	3303	0	0	3303
6	-21.00	3695	1487	5182	3374	0	0	3374
6	-21.50	3695	1595	5290	3444	0	0	3444
8	-18.00	1643	941	2584	1682	0	0	1682
8	-18.50	3098	1040	4138	2694	0	0	2694
8	-19.00	3272	1148	4420	2878	0	0	2878
8	-19.50	2913	1256	4169	2714	0	0	2714
8	-20.00	2862	1365	4227	2752	0	0	2752
8	-20.50	2761	1473	4234	2757	0	0	2757
8	-21.00	2782	1581	4363	2840	0	0	2840
8	-21.50	2763	1689	4452	2898	0	0	2898
9	-18.00	2604	1063	3667	2387	0	0	2387
9	-18.50	3228	1171	4399	2864	0	0	2864
9	-19.00	3391	1280	4671	3041	0	0	3041
9	-19.50	3247	1388	4635	3018	0	0	3018
9	-20.00	3355	1496	4851	3158	0	0	3158
9	-20.50	3485	1604	5089	3313	0	0	3313
9	-21.00	3590	1712	5302	3452	0	0	3452
9	-21.50	3695	1820	5515	3590	0	0	3590

* Rc;net;d = Rc;d - Fnsf;d

3.5 Results Bearing Forces for Pile type : DP 410

CPT name	Level [m R.L.]	Rb;cal;max [kN]	Rs;cal;max [kN]	Rc;cal;max [kN]	Rc;d [kN]	F;nsf;rep [kN]	Fnsf;d [kN]	Rc;net;d [kN]
3	-18.00	783	760	1543	1005	0	0	1005
3	-18.50	1266	844	2110	1374	0	0	1374
3	-19.00	1875	948	2823	1838	0	0	1838
3	-19.50	1980	1044	3024	1969	0	0	1969
3	-20.00	1839	1141	2980	1940	0	0	1940
3	-20.50	1890	1237	3127	2036	0	0	2036
3	-21.00	1944	1334	3278	2134	0	0	2134
3	-21.50	1980	1431	3411	2221	0	0	2221
5	-18.00	1468	734	2202	1434	0	0	1434
5	-18.50	1748	831	2579	1679	0	0	1679
5	-19.00	1980	927	2907	1893	0	0	1893
5	-19.50	1980	1024	3004	1956	0	0	1956
5	-20.00	1502	1121	2623	1708	0	0	1708
5	-20.50	1057	1217	2274	1480	0	0	1480
5	-21.00	930	1314	2244	1461	0	0	1461
5	-21.50	815	1410	2225	1449	0	0	1449
6	-18.00	1002	748	1750	1139	0	0	1139
6	-18.50	1075	845	1920	1250	0	0	1250
6	-19.00	1097	942	2039	1327	0	0	1327
6	-19.50	1255	1038	2293	1493	0	0	1493
6	-20.00	1594	1135	2729	1777	0	0	1777
6	-20.50	1928	1231	3159	2057	0	0	2057
6	-21.00	1980	1328	3308	2154	0	0	2154
6	-21.50	1980	1425	3405	2217	0	0	2217
8	-18.00	748	840	1588	1034	0	0	1034
8	-18.50	1543	929	2472	1609	0	0	1609
8	-19.00	1655	1026	2681	1745	0	0	1745
8	-19.50	1757	1122	2879	1874	0	0	1874
8	-20.00	1607	1219	2826	1840	0	0	1840
8	-20.50	1502	1316	2818	1835	0	0	1835
8	-21.00	1416	1412	2828	1841	0	0	1841
8	-21.50	1396	1509	2905	1891	0	0	1891
9	-18.00	1253	950	2203	1434	0	0	1434
9	-18.50	1657	1046	2703	1760	0	0	1760
9	-19.00	1717	1143	2860	1862	0	0	1862
9	-19.50	1810	1240	3050	1986	0	0	1986
9	-20.00	1735	1336	3071	1999	0	0	1999
9	-20.50	1818	1433	3251	2117	0	0	2117
9	-21.00	1864	1529	3393	2209	0	0	2209
9	-21.50	1844	1626	3470	2259	0	0	2259

* Rc;net;d = Rc;d - Fnsf;d

3.6 Results Bearing Forces for Pile type : funde 380-450

CPT name	Level [m R.L.]	Rb;cal;max [kN]	Rs;cal;max [kN]	Rc;cal;max [kN]	Rc;d [kN]	F;nsf;rep [kN]	Fnsf;d [kN]	Rc;net;d [kN]
3	-18.00	1051	692	1743	1135	0	0	1135
3	-18.50	1739	769	2508	1633	0	0	1633
3	-19.00	2386	863	3249	2115	0	0	2115
3	-19.50	2384	951	3335	2171	0	0	2171
3	-20.00	2386	1039	3425	2230	0	0	2230
3	-20.50	2386	1127	3513	2287	0	0	2287
3	-21.00	2386	1215	3601	2344	0	0	2344
3	-21.50	2386	1303	3689	2402	0	0	2402
5	-18.00	1985	669	2654	1728	0	0	1728
5	-18.50	2327	757	3084	2008	0	0	2008
5	-19.00	2386	845	3231	2104	0	0	2104
5	-19.50	2386	933	3319	2161	0	0	2161
5	-20.00	1667	1021	2688	1750	0	0	1750
5	-20.50	1399	1109	2508	1633	0	0	1633

CPT name	Level [m R.L.]	Rb;cal;max [kN]	Rs;cal;max [kN]	Rc;cal;max [kN]	Rc;d [kN]	F;nsf;rep [kN]	Fnsf;d [kN]	Rc;net;d [kN]
5	-21.00	1260	1197	2457	1600	0	0	1600
5	-21.50	1105	1285	2390	1556	0	0	1556
6	-18.00	1346	682	2028	1320	0	0	1320
6	-18.50	1437	770	2207	1437	0	0	1437
6	-19.00	1466	858	2324	1513	0	0	1513
6	-19.50	1678	946	2624	1708	0	0	1708
6	-20.00	2129	1034	3163	2059	0	0	2059
6	-20.50	2386	1122	3508	2284	0	0	2284
6	-21.00	2386	1210	3596	2341	0	0	2341
6	-21.50	2386	1298	3684	2398	0	0	2398
8	-18.00	1029	765	1794	1168	0	0	1168
8	-18.50	2069	846	2915	1898	0	0	1898
8	-19.00	2215	934	3149	2050	0	0	2050
8	-19.50	2319	1022	3341	2175	0	0	2175
8	-20.00	2016	1110	3126	2035	0	0	2035
8	-20.50	1905	1198	3103	2020	0	0	2020
8	-21.00	1889	1286	3175	2067	0	0	2067
8	-21.50	1865	1374	3239	2109	0	0	2109
9	-18.00	1692	865	2557	1665	0	0	1665
9	-18.50	2230	953	3183	2072	0	0	2072
9	-19.00	2282	1041	3323	2163	0	0	2163
9	-19.50	2386	1129	3515	2288	0	0	2288
9	-20.00	2284	1217	3501	2279	0	0	2279
9	-20.50	2386	1305	3691	2403	0	0	2403
9	-21.00	2386	1393	3779	2460	0	0	2460
9	-21.50	2386	1481	3867	2518	0	0	2518

* Rc;net;d = Rc;d - Fnsf;d

3.7 Results Bearing Forces for Pile type : DP 460

CPT name	Level [m R.L.]	Rb;cal;max [kN]	Rs;cal;max [kN]	Rc;cal;max [kN]	Rc;d [kN]	F;nsf;rep [kN]	Fnsf;d [kN]	Rc;net;d [kN]
3	-18.00	973	853	1826	1189	0	0	1189
3	-18.50	1614	947	2561	1667	0	0	1667
3	-19.00	2334	1063	3397	2212	0	0	2212
3	-19.50	2176	1172	3348	2180	0	0	2180
3	-20.00	2263	1280	3543	2307	0	0	2307
3	-20.50	2301	1388	3689	2402	0	0	2402
3	-21.00	2378	1497	3875	2523	0	0	2523
3	-21.50	2478	1605	4083	2658	0	0	2658
5	-18.00	1838	824	2662	1733	0	0	1733
5	-18.50	2152	932	3084	2008	0	0	2008
5	-19.00	2432	1041	3473	2261	0	0	2261
5	-19.50	2433	1149	3582	2332	0	0	2332
5	-20.00	1515	1257	2772	1805	0	0	1805
5	-20.50	1292	1366	2658	1730	0	0	1730
5	-21.00	1171	1474	2645	1722	0	0	1722
5	-21.50	1026	1582	2608	1698	0	0	1698
6	-18.00	1248	840	2088	1359	0	0	1359
6	-18.50	1330	948	2278	1483	0	0	1483
6	-19.00	1357	1056	2413	1571	0	0	1571
6	-19.50	1558	1165	2723	1773	0	0	1773
6	-20.00	1979	1273	3252	2117	0	0	2117
6	-20.50	2321	1382	3703	2411	0	0	2411
6	-21.00	2450	1490	3940	2565	0	0	2565
6	-21.50	2493	1598	4091	2663	0	0	2663
8	-18.00	953	943	1896	1234	0	0	1234
8	-18.50	1917	1042	2959	1926	0	0	1926
8	-19.00	2049	1151	3200	2083	0	0	2083
8	-19.50	2145	1259	3404	2216	0	0	2216
8	-20.00	1862	1368	3230	2103	0	0	2103
8	-20.50	1738	1476	3214	2092	0	0	2092
8	-21.00	1745	1584	3329	2167	0	0	2167

CPT name	Level [m R.L.]	Rb;cal;max [kN]	Rs;cal;max [kN]	Rc;cal;max [kN]	Rc;d [kN]	F;nsf;rep [kN]	Fnsf;d [kN]	Rc;net;d [kN]
8	-21.50	1727	1693	3420	2227	0	0	2227
9	-18.00	1570	1066	2636	1716	0	0	1716
9	-18.50	2031	1174	3205	2087	0	0	2087
9	-19.00	2112	1282	3394	2210	0	0	2210
9	-19.50	2217	1391	3608	2349	0	0	2349
9	-20.00	2109	1499	3608	2349	0	0	2349
9	-20.50	2208	1608	3816	2484	0	0	2484
9	-21.00	2290	1716	4006	2608	0	0	2608
9	-21.50	2320	1824	4144	2698	0	0	2698

* Rc;net;d = Rc;d - Fnsf;d

3.8 Summar et Bearing Capacit in k

CPT name	Groundlevel [m R.L.]	Level [m R.L.]	fundex 460-560 Rc;net;d [kN]	DPA 410 Rc;net;d [kN]	fundex 380-450 Rc;net;d [kN]	DPA 460 Rc;net;d [kN]
3	0,84	-18,00	1588,00	1005,00	1135,00	1189,0
3	0,84	-18,50	2443,00	1374,00	1633,00	1667,0
3	0,84	-19,00	3030,00	1838,00	2115,00	2212,0
3	0,84	-19,50	3044,00	1969,00	2171,00	2180,0
3	0,84	-20,00	3155,00	1940,00	2230,00	2307,0
3	0,84	-20,50	3290,00	2036,00	2287,00	2402,0
3	0,84	-21,00	3378,00	2134,00	2344,00	2523,0
3	0,84	-21,50	3449,00	2221,00	2402,00	2658,0
5	0,84	-18,00	2551,00	1434,00	1728,00	1733,0
5	0,84	-18,50	2865,00	1679,00	2008,00	2008,0
5	0,84	-19,00	3081,00	1893,00	2104,00	2261,0
5	0,84	-19,50	2432,00	1956,00	2161,00	2332,0
5	0,84	-20,00	2255,00	1708,00	1750,00	1805,0
5	0,84	-20,50	2257,00	1480,00	1633,00	1730,0
5	0,84	-21,00	2229,00	1461,00	1600,00	1722,0
5	0,84	-21,50	2142,00	1449,00	1556,00	1698,0
6	0,85	-18,00	1881,00	1139,00	1320,00	1359,0
6	0,85	-18,50	2023,00	1250,00	1437,00	1483,0
6	0,85	-19,00	2109,00	1327,00	1513,00	1571,0
6	0,85	-19,50	2404,00	1493,00	1708,00	1773,0
6	0,85	-20,00	2934,00	1777,00	2059,00	2117,0
6	0,85	-20,50	3303,00	2057,00	2284,00	2411,0
6	0,85	-21,00	3374,00	2154,00	2341,00	2565,0
6	0,85	-21,50	3444,00	2217,00	2398,00	2663,0
8	0,85	-18,00	1682,00	1034,00	1168,00	1234,0
8	0,85	-18,50	2694,00	1609,00	1898,00	1926,0
8	0,85	-19,00	2878,00	1745,00	2050,00	2083,0
8	0,85	-19,50	2714,00	1874,00	2175,00	2216,0
8	0,85	-20,00	2752,00	1840,00	2035,00	2103,0
8	0,85	-20,50	2757,00	1835,00	2020,00	2092,0
8	0,85	-21,00	2840,00	1841,00	2067,00	2167,0
8	0,85	-21,50	2898,00	1891,00	2109,00	2227,0
9	0,79	-18,00	2387,00	1434,00	1665,00	1716,0
9	0,79	-18,50	2864,00	1760,00	2072,00	2087,0
9	0,79	-19,00	3041,00	1862,00	2163,00	2210,0
9	0,79	-19,50	3018,00	1986,00	2288,00	2349,0
9	0,79	-20,00	3158,00	1999,00	2279,00	2349,0
9	0,79	-20,50	3313,00	2117,00	2403,00	2484,0
9	0,79	-21,00	3452,00	2209,00	2460,00	2608,0
9	0,79	-21,50	3590,00	2259,00	2518,00	2698,0

* Rc;net;d = Rc;d - Fnsf;d

End of Report

Bijlage 4 Uitvoer D-Foundation trek, rekenwaarde

Report for D-Foundations 17.1

Design and Verification according to Eurocode 7 of Bearing/Tension Piles and Shallow Foundations
Developed by Deltares

Company:	CRUX Engineering B.V.
Date of report:	5-3-2018
Time of report:	14:02:47
Date of calculation:	5-3-2018
Time of calculation:	14:01:03
Filename:	P:\..\04 REK\GEO\Paal\DFoub1 Trekdraagvermogen kelder -2,6
Project identification:	
	D-Foundations DFoub1 Trekdraagvermogen kelder -2,6

1 Table of Contents

1 Table of Contents 2
2 Input Data 4
2.1 General Input Data 4
2.2 General Report Data 4
2.3 Application Area Model Tension Piles (EC7-NL) 4
2.4 General CPT Data 4
2.4.1 View of CPT's in Foundation Plan 4
2.5 Soil Data 5
2.5.1 Soil Profile 3 5
2.5.2 Soil Profile 5 6
2.5.3 Soil Profile 6 7
2.5.4 Soil Profile 8 8
2.5.5 Soil Profile 9 9
2.6 Pile Types 11
2.6.1 Pile type : fundex 380/450 11
2.6.2 Pile type : fundex 460/560 11
2.6.3 Pile type : DPA 360 12
2.6.4 Pile type : DPA 410 12
2.6.5 Pile type : DPA 460 12
2.6.6 Pile type : fundex 406/560 12
2.7 Foundation Plan 13
2.7.1 View of Foundation Plan 13
2.8 Excavation Data 13
2.9 Optional Parameters 14
2.10 Overruled Parameters 14
2.11 Model Options 14
2.12 Model Options 14
3 Tension Piles (EC7-NL): Indication Bearing Capacity 16
3.1 Errors and Warnings 16
3.2 Remarks 16
3.3 Calculation Parameters 16
3.3.1 Pile Factors 16
3.3.2 Pile type : fundex 460/560 16
3.3.3 Pile type : DPA 410 16
3.3.4 Pile type : DPA 460 17
3.3.5 Pile type : fundex 380/450 17
3.4 Results for all CPT's 17
3.4.1 Results for pile type : fundex 460/560 17
3.4.1.1 Pile group 1 17
3.4.1.2 Pile group 2 17
3.4.1.3 Pile group 3 18
3.4.1.4 Pile group 4 18
3.4.2 Results for pile type : DPA 410 18
3.4.2.1 Pile group 1 18
3.4.2.2 Pile group 2 19
3.4.2.3 Pile group 3 19
3.4.2.4 Pile group 4 19
3.4.3 Results for pile type : DPA 460 19
3.4.3.1 Pile group 1 20
3.4.3.2 Pile group 2 20
3.4.3.3 Pile group 3 20
3.4.3.4 Pile group 4 20
3.4.4 Results for pile type : fundex 380/450 21
3.4.4.1 Pile group 1 21
3.4.4.2 Pile group 2 21
3.4.4.3 Pile group 3 21
3.4.4.4 Pile group 4 22
3.5 INDICATIVE: Results using Ksi3 22
3.5.1 Results for pile type : fundex 460/560 22
3.5.1.1 Pile group 1 22
3.5.1.2 Pile group 2 23
3.5.1.3 Pile group 3 24
3.5.1.4 Pile group 4 25

3.5.2 Results for pile type : DPA 410 26
3.5.2.1 Pile group 1 26
3.5.2.2 Pile group 2 27
3.5.2.3 Pile group 3 28
3.5.2.4 Pile group 4 29
3.5.3 Results for pile type : DPA 460 30
3.5.3.1 Pile group 1 30
3.5.3.2 Pile group 2 31
3.5.3.3 Pile group 3 32
3.5.3.4 Pile group 4 33
3.5.4 Results for pile type : fundex 380/450 34
3.5.4.1 Pile group 1 34
3.5.4.2 Pile group 2 35
3.5.4.3 Pile group 3 36
3.5.4.4 Pile group 4 37

2 nput Data

2.1 General nput Data

Model	Tension Piles (EC7-NL)

2.2 General Report Data

Geotechnical consultant :	
Design engineer superstructure :	
Principal :	
Title 1 :	
Title 2 :	
Title 3 :	D-Foundations DFoub1 Trekdraagvermogen kelder -2,6
Number of project :	
Location of project :	

2.3 pplication rea odel Tension Piles EC7-

The design and verifications performed by the TENSION PILES (EC7-NL) model of D-FOUNDATIONS concern pile foundations on which axial static or quasi-static loads cause tensile forces in the piles. Pilegroup effects are taken into account. Calculation of pile forces is based on Cone Penetration Tests. Pile capacities are based on the NEN 9997-1:2016, chapter 7 and where pile/safety factors are concerned, on Dutch Standards NEN 9997-1:2016. Horizontal displacements of piles are not taken into account. Vertical displacements of piles are not calculated. Design of Tension piles based on NEN 9997-1:2016 is limited to piles with lengths between 7 and 50 m and a minimum Length over (equivalent) diameter ratio of 13.5.

2.4 General CPT Data

Number of CPT's :	5
Timing of CPT's :	CPT - Install - Excavation

2.4.1 View of CPT's in Foundation Plan




Number/name CPT	X-coor-dinate [m]	Y-coor-dinate [m]
1: 3	118155,78	484051,62
2: 5	0,00	0,00
3: 6	118139,99	484052,09
4: 8	0,00	0,00
5: 9	118121,90	484051,98

2.5 Soil Data

Number of soil profiles (= number of CPT's) : 5

2.5.1 Soil Profile 3

Belonging to CPT	3
Surface level in [m. reference level] :	0,84
Phreatic level in [m. reference level] :	-0,50
Top of tension zone [m. reference level]:	-11,80
Pile tip level in [m. reference level] :	-20,00
Number of layers in profile :	14




Number layer	Top layer [m R.L.]	Soil Type	Gamma [kN/m3]	Gamma sat [kN/m3]	Min. Void Ratio [%]	Max. Void Ratio [%]	Median [mm]	Max. Cone resistance [kPa]	Use Max. Cone resistance
1	0,840	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
2	0,340	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
3	0,240	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
4	-2,760	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
5	-2,860	Peat	10,00	10,00	0,40	0,80		12/15	Standa...
6	-5,220	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
7	-8,139	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
8	-8,239	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
9	-8,459	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
10	-9,278	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
11	-9,778	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...

Number layer	Top layer [m R.L.]	Soil Type	Gamma [kN/m3]	Gamma sat [kN/m3]	Min. Void Ratio [%]	Max. Void Ratio [%]	Median [mm]	Max. Cone resistance [kPa]	Use Max. Cone resistance
12	-9,978	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
13	-12,016	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
14	-24,024	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...

Number layer	Top layer [m R.L.]	Soil Type	Phi [deg]	Addit. PP at top [kN/m2]	Addit. PP at bottom [kN/m2]	OCR value [-]	Use Tension
1	0,840	Sand	27,00	0,00	0,00	1,000	True
2	0,340	Sand	27,00	0,00	0,00	1,000	True
3	0,240	Sand	27,00	0,00	0,00	1,000	True
4	-2,760	Clay	17,50	0,00	0,00	1,000	True
5	-2,860	Peat	15,00	0,00	0,00	1,000	False
6	-5,220	Clay	17,50	0,00	0,00	1,000	True
7	-8,139	Sand	27,00	0,00	0,00	1,000	True
8	-8,239	Clay	17,50	0,00	0,00	1,000	True
9	-8,459	Sand	27,00	0,00	0,00	1,000	True
10	-9,278	Clay	17,50	0,00	0,00	1,000	True
11	-9,778	Sand	27,00	0,00	0,00	1,000	True
12	-9,978	Clay	17,50	0,00	0,00	1,000	True
13	-12,016	Sand	27,00	0,00	0,00	1,000	True
14	-24,024	Sand	27,00	0,00	0,00	1,000	True

2.5.2 Soil Profile 5

Belonging to CPT	5
Surface level in [m. reference level] :	0,84
Phreatic level in [m. reference level] :	-0,50
Top of tension zone [m. reference level]:	-11,40
Pile tip level in [m. reference level] :	-19,26
Number of layers in profile :	13




Number layer	Top layer [m R.L.]	Soil Type	Gamma [kN/m3]	Gamma sat [kN/m3]	Min. Void Ratio [%]	Max. Void Ratio [%]	Median [mm]	Max. Cone resistance [kPa]	Use Max. Cone resistance
1	0,840	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
2	0,440	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
3	0,340	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
4	0,240	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
5	-2,879	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
6	-3,079	Peat	10,00	10,00	0,40	0,80		12/15	Standa...
7	-5,218	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
8	-7,795	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
9	-8,814	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
10	-9,633	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
11	-9,852	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
12	-11,509	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
13	-25,770	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...

Number layer	Top layer [m R.L.]	Soil Type	Phi [deg]	Addit. PP at top [kN/m2]	Addit. PP at bottom [kN/m2]	OCR value [-]	Use Tension
1	0,840	Clay	17,50	0,00	0,00	1,000	True
2	0,440	Clay	17,50	0,00	0,00	1,000	True
3	0,340	Clay	17,50	0,00	0,00	1,000	True
4	0,240	Sand	27,00	0,00	0,00	1,000	True
5	-2,879	Clay	17,50	0,00	0,00	1,000	True
6	-3,079	Peat	15,00	0,00	0,00	1,000	False
7	-5,218	Clay	17,50	0,00	0,00	1,000	True
8	-7,795	Sand	27,00	0,00	0,00	1,000	True
9	-8,814	Clay	17,50	0,00	0,00	1,000	True
10	-9,633	Sand	27,00	0,00	0,00	1,000	True
11	-9,852	Clay	17,50	0,00	0,00	1,000	True
12	-11,509	Sand	27,00	0,00	0,00	1,000	True
13	-25,770	Sand	27,00	0,00	0,00	1,000	True

2.5.3 Soil Profile 6

Belonging to CPT	6
Surface level in [m. reference level] :	0,85
Phreatic level in [m. reference level] :	-0,50
Top of tension zone [m. reference level]:	-11,80
Pile tip level in [m. reference level] :	-20,00
Number of layers in profile :	12




Number layer	Top layer [m R.L.]	Soil Type	Gamma [kN/m3]	Gamma sat [kN/m3]	Min. Void Ratio [%]	Max. Void Ratio [%]	Median [mm]	Max. Cone resistance [kPa]	Use Max. Cone resistance
1	0,850	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
2	-0,350	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
3	-0,450	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
4	-2,589	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
5	-2,689	Peat	10,00	10,00	0,40	0,80		12/15	Standa...
6	-5,108	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
7	-7,865	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
8	-9,184	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
9	-11,479	Peat	10,00	10,00	0,40	0,80		12/15	Standa...
10	-11,798	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
11	-11,898	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
12	-23,987	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...

Number layer	Top layer [m R.L.]	Soil Type	Phi [deg]	Addit. PP at top [kN/m2]	Addit. PP at bottom [kN/m2]	OCR value [-]	Use Tension
1	0,850	Sand	27,00	0,00	0,00	1,000	True
2	-0,350	Sand	27,00	0,00	0,00	1,000	True
3	-0,450	Sand	27,00	0,00	0,00	1,000	True
4	-2,589	Clay	17,50	0,00	0,00	1,000	True
5	-2,689	Peat	15,00	0,00	0,00	1,000	False
6	-5,108	Clay	17,50	0,00	0,00	1,000	True
7	-7,865	Sand	27,00	0,00	0,00	1,000	True
8	-9,184	Clay	17,50	0,00	0,00	1,000	True
9	-11,479	Peat	15,00	0,00	0,00	1,000	False
10	-11,798	Clay	17,50	0,00	0,00	1,000	True
11	-11,898	Sand	27,00	0,00	0,00	1,000	True
12	-23,987	Sand	27,00	0,00	0,00	1,000	True

2.5.4 Soil Profile 8

Belonging to CPT	8
Surface level in [m. reference level] :	0,85

Phreatic level in [m. reference level] :	-0,50
Top of tension zone [m. reference level]:	-11,40
Pile tip level in [m. reference level] :	-19,26
Number of layers in profile :	9




Number layer	Top layer [m R.L.]	Soil Type	Gamma [kN/m3]	Gamma sat [kN/m3]	Min. Void Ratio [%]	Max. Void Ratio [%]	Median [mm]	Max. Cone resistance [kPa]	Use Max. Cone resistance
1	0,850	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
2	0,450	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
3	0,350	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
4	-3,550	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
5	-3,750	Peat	10,00	10,00	0,40	0,80		12/15	Standa...
6	-5,389	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
7	-8,428	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
8	-8,728	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
9	-11,466	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...

Number layer	Top layer [m R.L.]	Soil Type	Phi [deg]	Addit. PP at top [kN/m2]	Addit. PP at bottom [kN/m2]	OCR value [-]	Use Tension
1	0,850	Sand	27,00	0,00	0,00	1,000	True
2	0,450	Sand	27,00	0,00	0,00	1,000	True
3	0,350	Sand	27,00	0,00	0,00	1,000	True
4	-3,550	Clay	17,50	0,00	0,00	1,000	True
5	-3,750	Peat	15,00	0,00	0,00	1,000	False
6	-5,389	Clay	17,50	0,00	0,00	1,000	True
7	-8,428	Sand	27,00	0,00	0,00	1,000	True
8	-8,728	Clay	17,50	0,00	0,00	1,000	True
9	-11,466	Sand	27,00	0,00	0,00	1,000	True

2.5.5 Soil Profile

Belonging to CPT	9
Surface level in [m. reference level] :	0,79
Phreatic level in [m. reference level] :	-0,50
Top of tension zone [m. reference level]:	-11,10

Pile tip level in [m. reference level] :	-19,26
Number of layers in profile :	28



Number layer	Top layer [m R.L.]	Soil Type	Gamma [kN/m3]	Gamma sat [kN/m3]	Min. Void Ratio [%]	Max. Void Ratio [%]	Median [mm]	Max. Cone resistance [kPa]	Use Max. Cone resistance
1	0,790	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
2	0,290	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
3	0,190	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
4	-0,210	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
5	-2,510	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
6	-2,710	Loam	19,00	19,00	0,40	0,80		12/15	Standa...
7	-2,810	Clay	14,00	14,00	0,40	0,80		12/15	Standa...
8	-3,010	Peat	12,00	12,00	0,40	0,80		12/15	Standa...
9	-3,810	Peat	12,00	12,00	0,40	0,80		12/15	Standa...
10	-4,010	Peat	12,00	12,00	0,40	0,80		12/15	Standa...
11	-5,010	Clay	14,00	14,00	0,40	0,80		12/15	Standa...
12	-5,510	Clay	18,00	18,00	0,40	0,80		12/15	Standa...
13	-6,790	Loam	19,00	19,00	0,40	0,80		12/15	Standa...
14	-7,009	Clay	18,00	18,00	0,40	0,80		12/15	Standa...
15	-7,409	Loam	19,00	19,00	0,40	0,80		12/15	Standa...
16	-8,509	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
17	-8,709	Loam	19,00	19,00	0,40	0,80		12/15	Standa...
18	-8,809	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
19	-8,909	Loam	19,00	19,00	0,40	0,80		12/15	Standa...
20	-9,109	Clay	18,00	18,00	0,40	0,80		12/15	Standa...
21	-9,509	Loam	19,00	19,00	0,40	0,80		12/15	Standa...
22	-10,028	Clay	18,00	18,00	0,40	0,80		12/15	Standa...
23	-10,828	Loam	19,00	19,00	0,40	0,80		12/15	Standa...
24	-10,928	Clay	18,00	18,00	0,40	0,80		12/15	Standa...
25	-11,028	Loam	19,00	19,00	0,40	0,80		12/15	Standa...
26	-11,128	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
27	-11,228	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
28	-24,059	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...

Number layer	Top layer [m R.L.]	Soil Type	Phi [deg]	Addit. PP at top [kN/m2]	Addit. PP at bottom [kN/m2]	OCR value [-]	Use Tension
1	0,790	Sand	25,00	0,00	0,00	1,000	True
2	0,290	Sand	25,00	0,00	0,00	1,000	True
3	0,190	Sand	25,00	0,00	0,00	1,000	True
4	-0,210	Sand	27,00	0,00	0,00	1,000	True
5	-2,510	Sand	25,00	0,00	0,00	1,000	True
6	-2,710	Loam	27,50	0,00	0,00	1,000	True
7	-2,810	Clay	17,50	0,00	0,00	1,000	True
8	-3,010	Peat	15,00	0,00	0,00	1,000	False
9	-3,810	Peat	15,00	0,00	0,00	1,000	False
10	-4,010	Peat	15,00	0,00	0,00	1,000	False
11	-5,010	Clay	17,50	0,00	0,00	1,000	True
12	-5,510	Clay	22,50	0,00	0,00	1,000	True
13	-6,790	Loam	27,50	0,00	0,00	1,000	True
14	-7,009	Clay	22,50	0,00	0,00	1,000	True
15	-7,409	Loam	27,50	0,00	0,00	1,000	True
16	-8,509	Sand	25,00	0,00	0,00	1,000	True
17	-8,709	Loam	27,50	0,00	0,00	1,000	True
18	-8,809	Sand	25,00	0,00	0,00	1,000	True
19	-8,909	Loam	27,50	0,00	0,00	1,000	True
20	-9,109	Clay	22,50	0,00	0,00	1,000	True
21	-9,509	Loam	27,50	0,00	0,00	1,000	True
22	-10,028	Clay	22,50	0,00	0,00	1,000	True
23	-10,828	Loam	27,50	0,00	0,00	1,000	True
24	-10,928	Clay	22,50	0,00	0,00	1,000	True
25	-11,028	Loam	27,50	0,00	0,00	1,000	True
26	-11,128	Sand	25,00	0,00	0,00	1,000	True
27	-11,228	Sand	27,00	0,00	0,00	1,000	True
28	-24,059	Sand	27,00	0,00	0,00	1,000	True

2.6 Pile Types

Note : if alpha;t is not user defined, the next rules apply :
- alpha;t according to table 7.g and table 7.h of NEN 9997-1:2016
- for clay: alpha;t depends on the CPT-value and relative depth
- for peat: alpha;t = 0
- for sand/gravel: alpha;t also depends on the median

Number of pile types : 6

2.6.1 Pile type : funde 380/450

Pile type for shaft friction factor (alpha;t) sand/gravel : Screw pile, cast in place, lost tip

Pile type for shaft friction factor (alpha;t) clay : User defined
Shaft friction factor clay [-] : 0,0000
Materialtype for pile : Concrete
Pile shape : Round pile with lost tip

Pile dimensions :
- Diameter at tip [m] : 0,450
- Diameter shaft [m] : 0,415
- Effective heigth enlarged base [m] : 0,000

2.6.2 Pile type : funde 460/560

Pile type for shaft friction factor (alpha;t) sand/gravel : Screw pile, cast in place, lost tip

Pile type for shaft friction factor (alpha;t) clay : User defined
Shaft friction factor clay [-] : 0,0000
Materialtype for pile : Concrete
Pile shape : Round pile with lost tip

Pile dimensions :
- Diameter at tip [m] : 0,560
- Diameter shaft [m] : 0,510
- Effective heigth enlarged base [m] : 0,000

2.6.3 Pile type : DP 360

Pile type for shaft friction factor (alpha;t) sand/gravel : User defined (vibrating)

Shaft friction factor sand/gravel [-] : 0,0090
Pile type for shaft friction factor (alpha;t) clay : User defined
Shaft friction factor clay [-] : 0,0000
Materialtype for pile : Concrete
Pile shape : Round pile

Pile dimensions :
- Diameter [m] : 0,360

2.6.4 Pile type : DP 410

Pile type for shaft friction factor (alpha;t) sand/gravel : User defined (vibrating)

Shaft friction factor sand/gravel [-] : 0,0090
Pile type for shaft friction factor (alpha;t) clay : User defined
Shaft friction factor clay [-] : 0,0000
Materialtype for pile : Concrete
Pile shape : Round pile

Pile dimensions :
- Diameter [m] : 0,410

2.6.5 Pile type : DP 460

Pile type for shaft friction factor (alpha;t) sand/gravel : User defined (vibrating)

Shaft friction factor sand/gravel [-] : 0,0090
Pile type for shaft friction factor (alpha;t) clay : User defined
Shaft friction factor clay [-] : 0,0000
Materialtype for pile : Concrete
Pile shape : Round pile

Pile dimensions :
- Diameter [m] : 0,460

2.6.6 Pile type : funde 406/560

Pile type for shaft friction factor (alpha;t) sand/gravel : Screw pile, cast in place, lost tip


Pile type for shaft friction factor (alpha;t) clay : User defined
Shaft friction factor clay [-] : 0,0000
Materialtype for pile : Concrete
Pile shape : Round pile with lost tip

Pile dimensions :
- Diameter at tip [m] : 0,560
- Diameter shaft [m] : 0,483
- Effective heigth enlarged base [m] : 0,000

2.7 Foundation Plan

Number of piles : 9
Number of collaborating piles* : 1
* : 0 = not defined, 1 = non rigid superstructure, >1 = rigid superstructure

2.7.1 View of Foundation Plan




Pile nr./code	X-coor-dinate [m]	Y-coor-dinate [m]	Maximum load [kN]	Minimum load [kN]	Pile head level [m R.L.]	Use alternat. loads	Factor Gamma;var
1: 1	0,00	0,00	0,00	0,00	-2,60	False	n.a.
2: 2	0,00	2,00	0,00	0,00	-2,60	False	n.a.
3: 3	2,00	0,00	0,00	0,00	-2,60	False	n.a.
4: 4	-2,00	-2,00	0,00	0,00	-2,60	False	n.a.
5: 5	2,00	-2,00	0,00	0,00	-2,60	False	n.a.
6: 6	-2,00	2,00	0,00	0,00	-2,60	False	n.a.
7: 7	-2,00	0,00	0,00	0,00	-2,60	False	n.a.
8: 9	2,00	2,00	0,00	0,00	-2,60	False	n.a.
9: 10	0,00	-2,00	0,00	0,00	-2,60	False	n.a.

Note regarding the loads: tension forces are positive, compressive forces are negative
Note 2: See OVERRULED PARAMETERS for gamma;var

2.8 E□cavation Data

Excavation level in [m. reference level] : -2,60
Reduction model : Safe (NEN)



2.□□□ptional Parameters

Unit weight water [kN/m3] : 9,81
Surcharge [kN/m2] : 0,00

2.10 □verruled Parameters

User defined gamma;var [-]	1,00
User defined Factor xi3 [-] :	1,28
User defined Factor xi4 [-] :	1,03
User defined gamma;st [-]	1,35

2.11 □odel □ptions

Suppress compaction
If compaction is used, according to NEN 9997-1:2016 CPT's should be made after installation to verify this assumption
Use the influence of excavations (standard).
Suppress excess pore pressure

2.12 □odel □ptions

Selected pile types :
-fundex 460/560
-DPA 410
-DPA 460
-fundex 380/450

Selected profiles :
-3
-5
-6
-8
-9
Trajectory
-begin [m] : -18,00

-end [m] :	-21,75
-interval [m] :	0,50

3 Tension Piles EC7- : ndication Bearing Capacit

3.1 Errors and arnings

Warning : The factor xi3 (NEN 9997-1:2016) is user defined. Evidence to support this from the NEN deviating value has to be provided.
Warning : The factor xi4 (NEN 9997-1:2016) is user defined. Evidence to support this from the NEN deviating value has to be provided.
Warning : The factor gamma;st (NEN 9997-1:2016) is user defined. Evidence to support this from the NEN deviating value has to be provided.
Warning : The factor gamma;var (NEN 9997-1:2016) is user defined. Evidence to support this from the NEN deviating value has to be provided.
At pile type fundex 460/560 :
Due to the use of a low vibrating pile type, the reduction of CPT-value due to the excavation is done using NEN 9997-1:2016.

At pile type fundex 380/450 :
Due to the use of a low vibrating pile type, the reduction of CPT-value due to the excavation is done using NEN 9997-1:2016.

When reviewing the following results, warnings listed above should be considered.

3.2 Remarks

When calculating the max. mobilized soil weight, the topangle is used according to NEN 9997-1:2016.

3.3 Calculation Parameters

3.3.1 Pile Factors

xi3 (user defined) :	1,28
xi4 (user defined) :	1,03
User defined gamma;var [-]	1,000
User defined gamma;st [-]	1,350
Factor gamma;gamma according to NEN 9997-1:2016 table A.2 [-]	
Above excavation level	1,0
Below excavation level	1,1

3.3.2 Pile t pe : funde 460 560

Pile type for shaft friction factor (alpha;t) sand/gravel :	Screw pile, cast in place, lost tip
Pile type for shaft friction factor (alpha;t) clay :	User defined
Shaft friction factor clay [-] :	0,0000
Materialtype for pile :	Concrete
Pile shape :	Round pile with lost tip
Pile dimensions :	
Diameter at tip [m] :	0,560
Diameter shaft [m] :	0,510
Effective heigth enlarged base [m] :	0,000

3.3.3 Pile t pe : DP 410

Pile type for shaft friction factor (alpha;t) sand/gravel :	User defined (vibrating)
Shaft friction factor sand/gravel [-] :	0,0090
Pile type for shaft friction factor (alpha;t) clay :	User defined
Shaft friction factor clay [-] :	0,0000
Materialtype for pile :	Concrete
Pile shape :	Round pile

Pile dimensions :
Diameter [m] : 0,410

3.3.4 Pile type : DP 460

Pile type for shaft friction factor (alpha;t) sand/gravel : User defined (vibrating)

Shaft friction factor sand/gravel [-] : 0,0090
Pile type for shaft friction factor (alpha;t) clay : User defined
Shaft friction factor clay [-] : 0,0000
Materialtype for pile : Concrete
Pile shape : Round pile

Pile dimensions :
Diameter [m] : 0,460

3.3.5 Pile type : funde 380/450

Pile type for shaft friction factor (alpha;t) sand/gravel : Screw pile, cast in place, lost tip

Pile type for shaft friction factor (alpha;t) clay : User defined
Shaft friction factor clay [-] : 0,0000
Materialtype for pile : Concrete
Pile shape : Round pile with lost tip

Pile dimensions :
Diameter at tip [m] : 0,450
Diameter shaft [m] : 0,415
Effective heigth enlarged base [m] : 0,000

3.4 Results for all CPT's

3.4.1 Results for pile type : funde 460/560

3.4.1.1 Pile group 1

Number of piles belonging to this pile group : 1
Names of piles belonging to this pile group
1

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	360,04	358,07	358,07	Ksi3
-18,50	375,93	381,91	375,93	Ksi4
-19,00	391,82	405,61	391,82	Ksi4
-19,50	407,71	423,93	407,71	Ksi4
-20,00	423,60	439,82	423,60	Ksi4
-20,50	439,49	455,71	439,49	Ksi4
-21,00	455,38	471,60	455,38	Ksi4
-21,50	471,27	487,49	471,27	Ksi4

3.4.1.2 Pile group 2

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
2
10

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	403,59	388,88	388,88	Ksi3
-18,50	439,28	419,71	419,71	Ksi3
-19,00	472,56	450,87	450,87	Ksi3
-19,50	504,06	480,64	480,64	Ksi3
-20,00	534,29	509,30	509,30	Ksi3
-20,50	563,61	537,07	537,07	Ksi3
-21,00	592,26	564,14	564,14	Ksi3
-21,50	620,42	590,63	590,63	Ksi3

3.4.1.3 Pile group 3

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
3
7

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	403,59	388,88	388,88	Ksi3
-18,50	439,28	419,71	419,71	Ksi3
-19,00	472,56	450,87	450,87	Ksi3
-19,50	504,06	480,64	480,64	Ksi3
-20,00	534,29	509,30	509,30	Ksi3
-20,50	563,61	537,07	537,07	Ksi3
-21,00	592,26	564,14	564,14	Ksi3
-21,50	620,42	590,63	590,63	Ksi3

3.4.1.4 Pile group 4

Number of piles belonging to this pile group : 4
Names of piles belonging to this pile group
4
5
6
9

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	465,02	439,15	439,15	Ksi3
-18,50	514,14	479,04	479,04	Ksi3
-19,00	561,57	520,32	520,32	Ksi3
-19,50	607,74	560,64	560,64	Ksi3
-20,00	652,99	600,18	600,18	Ksi3
-20,50	697,57	639,08	639,08	Ksi3
-21,00	741,64	677,48	677,48	Ksi3
-21,50	785,34	715,47	715,47	Ksi3

3.4.2 Results for pile type : DP 410

3.4.2.1 Pile group 1

Number of piles belonging to this pile group : 1
Names of piles belonging to this pile group
1

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	324,89	312,53	312,53	Ksi3
-18,50	353,39	337,52	337,52	Ksi3
-19,00	379,47	362,64	362,64	Ksi3
-19,50	403,53	386,41	386,41	Ksi3
-20,00	425,93	409,01	409,01	Ksi3

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-20,50	446,57	430,60	430,60	Ksi3
-21,00	462,77	451,31	451,31	Ksi3
-21,50	478,96	471,28	471,28	Ksi3

3.4.2.2 Pile group 2

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
2
10

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	348,36	331,55	331,55	Ksi3
-18,50	382,43	360,17	360,17	Ksi3
-19,00	414,54	389,39	389,39	Ksi3
-19,50	445,04	417,53	417,53	Ksi3
-20,00	474,24	444,72	444,72	Ksi3
-20,50	502,40	471,10	471,10	Ksi3
-21,00	529,73	496,80	496,80	Ksi3
-21,50	556,41	521,90	521,90	Ksi3

3.4.2.3 Pile group 3

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
3
7

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	348,36	331,55	331,55	Ksi3
-18,50	382,43	360,17	360,17	Ksi3
-19,00	414,54	389,39	389,39	Ksi3
-19,50	445,04	417,53	417,53	Ksi3
-20,00	474,24	444,72	444,72	Ksi3
-20,50	502,40	471,10	471,10	Ksi3
-21,00	529,73	496,80	496,80	Ksi3
-21,50	556,41	521,90	521,90	Ksi3

3.4.2.4 Pile group 4

Number of piles belonging to this pile group : 4
Names of piles belonging to this pile group
4
5
6
9

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	388,47	364,21	364,21	Ksi3
-18,50	431,64	398,88	398,88	Ksi3
-19,00	473,44	434,90	434,90	Ksi3
-19,50	514,12	470,18	470,18	Ksi3
-20,00	553,89	504,80	504,80	Ksi3
-20,50	592,93	538,86	538,86	Ksi3
-21,00	631,38	572,43	572,43	Ksi3
-21,50	669,35	605,59	605,59	Ksi3

3.4.3 Results for pile t pe : DP 460

3.4.3.1 Pile group 1

Number of piles belonging to this pile group : 1
Names of piles belonging to this pile group
1

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	347,50	337,23	337,23	Ksi3
-18,50	375,50	362,53	362,53	Ksi3
-19,00	395,13	387,68	387,68	Ksi3
-19,50	411,18	411,15	411,15	Ksi3
-20,00	427,23	432,69	427,23	Ksi4
-20,50	443,27	453,25	443,27	Ksi4
-21,00	459,32	473,00	459,32	Ksi4
-21,50	475,37	491,24	475,37	Ksi4

3.4.3.2 Pile group 2

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
2
10

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	377,25	361,29	361,29	Ksi3
-18,50	412,30	391,18	391,18	Ksi3
-19,00	445,12	421,53	421,53	Ksi3
-19,50	476,19	450,63	450,63	Ksi3
-20,00	505,94	478,67	478,67	Ksi3
-20,50	534,68	505,84	505,84	Ksi3
-21,00	562,65	532,28	532,28	Ksi3
-21,50	590,04	558,14	558,14	Ksi3

3.4.3.3 Pile group 3

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
3
7

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	377,25	361,29	361,29	Ksi3
-18,50	412,30	391,18	391,18	Ksi3
-19,00	445,12	421,53	421,53	Ksi3
-19,50	476,19	450,63	450,63	Ksi3
-20,00	505,94	478,67	478,67	Ksi3
-20,50	534,68	505,84	505,84	Ksi3
-21,00	562,65	532,28	532,28	Ksi3
-21,50	590,04	558,14	558,14	Ksi3

3.4.3.4 Pile group 4

Number of piles belonging to this pile group : 4
Names of piles belonging to this pile group
4
5
6
9

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	427,52	402,31	402,31	Ksi3
-18,50	473,78	439,70	439,70	Ksi3
-19,00	518,48	478,46	478,46	Ksi3
-19,50	561,97	516,36	516,36	Ksi3
-20,00	604,51	553,52	553,52	Ksi3
-20,50	646,32	590,07	590,07	Ksi3
-21,00	687,58	626,10	626,10	Ksi3
-21,50	728,40	661,72	661,72	Ksi3

3.4.4 Results for pile t pe : funde 380 450

3.4.4.1 Pile group 1

Number of piles belonging to this pile group : 1
Names of piles belonging to this pile group
1

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	327,31	315,13	315,13	Ksi3
-18,50	355,79	340,18	340,18	Ksi3
-19,00	381,81	365,32	365,32	Ksi3
-19,50	405,78	389,09	389,09	Ksi3
-20,00	428,07	411,68	411,68	Ksi3
-20,50	446,27	433,24	433,24	Ksi3
-21,00	462,45	453,92	453,92	Ksi3
-21,50	478,63	473,84	473,84	Ksi3

3.4.4.2 Pile group 2

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
2
10

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	351,37	334,62	334,62	Ksi3
-18,50	385,56	363,38	363,38	Ksi3
-19,00	417,75	392,74	392,74	Ksi3
-19,50	448,32	420,99	420,99	Ksi3
-20,00	477,58	448,28	448,28	Ksi3
-20,50	505,81	474,75	474,75	Ksi3
-21,00	533,21	500,53	500,53	Ksi3
-21,50	559,95	525,72	525,72	Ksi3

3.4.4.3 Pile group 3

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
3
7

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	351,37	334,62	334,62	Ksi3
-18,50	385,56	363,38	363,38	Ksi3
-19,00	417,75	392,74	392,74	Ksi3
-19,50	448,32	420,99	420,99	Ksi3
-20,00	477,58	448,28	448,28	Ksi3
-20,50	505,81	474,75	474,75	Ksi3
-21,00	533,21	500,53	500,53	Ksi3

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-21,50	559,95	525,72	525,72	Ksi3

3.4.4.4 Pile group 4

Number of piles belonging to this pile group : 4
Names of piles belonging to this pile group
4
5
6
9

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	392,45	368,08	368,08	Ksi3
-18,50	435,94	403,03	403,03	Ksi3
-19,00	478,04	439,34	439,34	Ksi3
-19,50	519,01	474,89	474,89	Ksi3
-20,00	559,07	509,77	509,77	Ksi3
-20,50	598,39	544,09	544,09	Ksi3
-21,00	637,12	577,91	577,91	Ksi3
-21,50	675,38	611,32	611,32	Ksi3

3.5 D C T VE: Results using si3

3.5.1 Results for pile t pe : funde 460 560

3.5.1.1 Pile group 1

Number of piles belonging to this pile group : 1
Names of piles belonging to this pile group
1

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	354,46	371,24	37,78	0,00
3	-18,50	376,50	387,13	39,00	0,00
3	-19,00	401,88	403,02	40,23	0,00
3	-19,50	418,91	418,91	41,46	0,00
3	-20,00	434,80	434,80	42,68	0,00
3	-20,50	450,69	450,69	43,91	0,00
3	-21,00	466,58	466,58	45,14	0,00
3	-21,50	482,47	482,47	46,36	0,00
5	-18,00	351,42	380,67	37,78	0,00
5	-18,50	379,98	396,56	39,00	0,00
5	-19,00	406,20	412,45	40,23	0,00
5	-19,50	428,34	428,34	41,46	0,00
5	-20,00	444,23	444,23	42,68	0,00
5	-20,50	460,13	460,13	43,91	0,00
5	-21,00	476,01	476,01	45,14	0,00
5	-21,50	491,90	491,90	46,36	0,00
6	-18,00	335,74	360,04	37,78	0,00
6	-18,50	364,13	375,93	39,00	0,00
6	-19,00	390,08	391,82	40,23	0,00
6	-19,50	407,71	407,71	41,46	0,00
6	-20,00	423,60	423,60	42,68	0,00
6	-20,50	439,49	439,49	43,91	0,00
6	-21,00	455,38	455,38	45,14	0,00
6	-21,50	471,27	471,27	46,36	0,00
8	-18,00	374,79	395,43	37,78	0,00
8	-18,50	399,10	411,32	39,00	0,00
8	-19,00	424,19	427,21	40,23	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
8	-19,50	443,10	443,10	41,46	0,00
8	-20,00	458,99	458,99	42,68	0,00
8	-20,50	474,88	474,88	43,91	0,00
8	-21,00	490,77	490,77	45,14	0,00
8	-21,50	506,66	506,66	46,36	0,00
9	-18,00	373,93	373,93	37,78	0,00
9	-18,50	389,82	389,82	39,00	0,00
9	-19,00	405,71	405,71	40,23	0,00
9	-19,50	421,60	421,60	41,46	0,00
9	-20,00	437,49	437,49	42,68	0,00
9	-20,50	453,38	453,38	43,91	0,00
9	-21,00	469,27	469,27	45,14	0,00
9	-21,50	485,16	485,16	46,36	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.1.2 Pile group 2

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
2
10

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	380,56	987,67	37,78	0,00
3	-18,50	407,32	1070,10	39,00	0,00
3	-19,00	438,96	1157,34	40,23	0,00
3	-19,50	469,19	1249,57	41,46	0,00
3	-20,00	498,20	1346,96	42,68	0,00
3	-20,50	526,26	1449,71	43,91	0,00
3	-21,00	553,56	1557,99	45,14	0,00
3	-21,50	580,25	1671,99	46,36	0,00
5	-18,00	375,92	1042,98	37,78	0,00
5	-18,50	410,08	1128,45	39,00	0,00
5	-19,00	442,35	1218,84	40,23	0,00
5	-19,50	473,07	1314,32	41,46	0,00
5	-20,00	502,54	1415,09	42,68	0,00
5	-20,50	531,00	1521,31	43,91	0,00
5	-21,00	558,64	1633,17	45,14	0,00
5	-21,50	585,63	1750,86	46,36	0,00
6	-18,00	359,64	946,78	37,78	0,00
6	-18,50	393,71	1026,81	39,00	0,00
6	-19,00	425,81	1111,51	40,23	0,00
6	-19,50	456,31	1201,07	41,46	0,00
6	-20,00	485,52	1295,68	42,68	0,00
6	-20,50	513,72	1395,51	43,91	0,00
6	-21,00	541,11	1500,74	45,14	0,00
6	-21,50	567,87	1611,56	46,36	0,00
8	-18,00	406,88	1153,85	37,78	0,00
8	-18,50	436,57	1245,10	39,00	0,00
8	-19,00	468,03	1341,44	40,23	0,00
8	-19,50	498,09	1443,04	41,46	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
8	-20,00	527,01	1550,09	42,68	0,00
8	-20,50	555,02	1662,76	43,91	0,00
8	-21,00	582,29	1781,26	45,14	0,00
8	-21,50	608,98	1905,74	46,36	0,00
9	-18,00	421,42	1026,15	37,78	0,00
9	-18,50	450,89	1110,35	39,00	0,00
9	-19,00	479,19	1199,38	40,23	0,00
9	-19,50	506,56	1293,42	41,46	0,00
9	-20,00	533,24	1392,67	42,68	0,00
9	-20,50	559,37	1497,30	43,91	0,00
9	-21,00	585,08	1607,50	45,14	0,00
9	-21,50	610,44	1723,44	46,36	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.1.3 Pile group 3

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
3
7

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	380,56	987,67	37,78	0,00
3	-18,50	407,32	1070,10	39,00	0,00
3	-19,00	438,96	1157,34	40,23	0,00
3	-19,50	469,19	1249,57	41,46	0,00
3	-20,00	498,20	1346,96	42,68	0,00
3	-20,50	526,26	1449,71	43,91	0,00
3	-21,00	553,56	1557,99	45,14	0,00
3	-21,50	580,25	1671,99	46,36	0,00
5	-18,00	375,92	1042,98	37,78	0,00
5	-18,50	410,08	1128,45	39,00	0,00
5	-19,00	442,35	1218,84	40,23	0,00
5	-19,50	473,07	1314,32	41,46	0,00
5	-20,00	502,54	1415,09	42,68	0,00
5	-20,50	531,00	1521,31	43,91	0,00
5	-21,00	558,64	1633,17	45,14	0,00
5	-21,50	585,63	1750,86	46,36	0,00
6	-18,00	359,64	946,78	37,78	0,00
6	-18,50	393,71	1026,81	39,00	0,00
6	-19,00	425,81	1111,51	40,23	0,00
6	-19,50	456,31	1201,07	41,46	0,00
6	-20,00	485,52	1295,68	42,68	0,00
6	-20,50	513,72	1395,51	43,91	0,00
6	-21,00	541,11	1500,74	45,14	0,00
6	-21,50	567,87	1611,56	46,36	0,00
8	-18,00	406,88	1153,85	37,78	0,00
8	-18,50	436,57	1245,10	39,00	0,00
8	-19,00	468,03	1341,44	40,23	0,00
8	-19,50	498,09	1443,04	41,46	0,00
8	-20,00	527,01	1550,09	42,68	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
8	-20,50	555,02	1662,76	43,91	0,00
8	-21,00	582,29	1781,26	45,14	0,00
8	-21,50	608,98	1905,74	46,36	0,00
9	-18,00	421,42	1026,15	37,78	0,00
9	-18,50	450,89	1110,35	39,00	0,00
9	-19,00	479,19	1199,38	40,23	0,00
9	-19,50	506,56	1293,42	41,46	0,00
9	-20,00	533,24	1392,67	42,68	0,00
9	-20,50	559,37	1497,30	43,91	0,00
9	-21,00	585,08	1607,50	45,14	0,00
9	-21,50	610,44	1723,44	46,36	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.1.4 Pile group 4

Number of piles belonging to this pile group : 4
Names of piles belonging to this pile group
4
5
6
9

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	425,39	2486,08	37,78	0,00
3	-18,50	459,78	2751,91	39,00	0,00
3	-19,00	501,38	3036,95	40,23	0,00
3	-19,50	542,03	3341,93	41,46	0,00
3	-20,00	581,84	3667,60	42,68	0,00
3	-20,50	620,96	4014,67	43,91	0,00
3	-21,00	659,54	4383,89	45,14	0,00
3	-21,50	697,68	4775,97	46,36	0,00
5	-18,00	417,87	2669,37	37,78	0,00
5	-18,50	461,26	2947,36	39,00	0,00
5	-19,00	503,35	3244,99	40,23	0,00
5	-19,50	544,35	3563,00	41,46	0,00
5	-20,00	584,47	3902,13	42,68	0,00
5	-20,50	623,87	4263,10	43,91	0,00
5	-21,00	662,70	4646,64	45,14	0,00
5	-21,50	701,06	5053,48	46,36	0,00
6	-18,00	400,57	2367,55	37,78	0,00
6	-18,50	443,90	2623,75	39,00	0,00
6	-19,00	485,85	2898,65	40,23	0,00
6	-19,50	526,69	3192,99	41,46	0,00
6	-20,00	566,63	3507,49	42,68	0,00
6	-20,50	605,85	3842,88	43,91	0,00
6	-21,00	644,50	4199,89	45,14	0,00
6	-21,50	682,68	4579,26	46,36	0,00
8	-18,00	460,94	3053,49	37,78	0,00
8	-18,50	499,18	3354,58	39,00	0,00
8	-19,00	540,68	3676,01	40,23	0,00
8	-19,50	581,19	4018,50	41,46	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
8	-20,00	620,91	4382,77	42,68	0,00
8	-20,50	659,98	4769,57	43,91	0,00
8	-21,00	698,53	5179,62	45,14	0,00
8	-21,50	736,65	5613,65	46,36	0,00
9	-18,00	490,97	2629,20	37,78	0,00
9	-18,50	531,06	2902,07	39,00	0,00
9	-19,00	570,32	3194,27	40,23	0,00
9	-19,50	608,93	3506,54	41,46	0,00
9	-20,00	647,04	3839,62	42,68	0,00
9	-20,50	684,75	4194,22	43,91	0,00
9	-21,00	722,15	4571,09	45,14	0,00
9	-21,50	759,29	4970,95	46,36	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.2 Results for pile t pe : DP 410

3.5.2.1 Pile group 1

Number of piles belonging to this pile group : 1
Names of piles belonging to this pile group
1

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	306,29	377,02	24,41	0,00
3	-18,50	328,16	393,21	25,21	0,00
3	-19,00	353,90	409,40	26,00	0,00
3	-19,50	378,26	425,60	26,79	0,00
3	-20,00	401,37	441,79	27,59	0,00
3	-20,50	423,40	457,98	28,38	0,00
3	-21,00	444,49	474,18	29,17	0,00
3	-21,50	464,78	490,37	29,96	0,00
5	-18,00	301,77	386,63	24,41	0,00
5	-18,50	329,85	402,83	25,21	0,00
5	-19,00	356,25	419,02	26,00	0,00
5	-19,50	381,19	435,21	26,79	0,00
5	-20,00	404,85	451,40	27,59	0,00
5	-20,50	427,39	467,60	28,38	0,00
5	-21,00	448,95	483,79	29,17	0,00
5	-21,50	469,68	499,98	29,96	0,00
6	-18,00	288,67	365,61	24,41	0,00
6	-18,50	316,55	381,80	25,21	0,00
6	-19,00	342,70	398,00	26,00	0,00
6	-19,50	367,33	414,19	26,79	0,00
6	-20,00	390,65	430,38	27,59	0,00
6	-20,50	412,84	446,57	28,38	0,00
6	-21,00	434,06	462,77	29,17	0,00
6	-21,50	454,44	478,96	29,96	0,00
8	-18,00	327,37	401,67	24,41	0,00
8	-18,50	351,33	417,87	25,21	0,00
8	-19,00	376,63	434,06	26,00	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
8	-19,50	400,60	450,25	26,79	0,00
8	-20,00	423,43	466,44	27,59	0,00
8	-20,50	445,25	482,63	28,38	0,00
8	-21,00	466,20	498,83	29,17	0,00
8	-21,50	486,40	515,02	29,96	0,00
9	-18,00	338,57	379,76	24,41	0,00
9	-18,50	361,74	395,95	25,21	0,00
9	-19,00	383,71	412,14	26,00	0,00
9	-19,50	404,66	428,34	26,79	0,00
9	-20,00	424,75	444,53	27,59	0,00
9	-20,50	444,11	460,72	28,38	0,00
9	-21,00	462,87	476,92	29,17	0,00
9	-21,50	481,12	493,11	29,96	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for sand and gravel are adjusted for the coarsness of the actual soil (sand when D50 > 0.6mm; gravel when D50 > 2 mm).
Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.2.2 Pile group 2

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
2
10

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	322,91	982,70	24,41	0,00
3	-18,50	347,77	1064,63	25,21	0,00
3	-19,00	377,49	1151,32	26,00	0,00
3	-19,50	406,09	1242,97	26,79	0,00
3	-20,00	433,68	1339,76	27,59	0,00
3	-20,50	460,40	1441,87	28,38	0,00
3	-21,00	486,39	1549,49	29,17	0,00
3	-21,50	511,75	1662,79	29,96	0,00
5	-18,00	317,44	1037,67	24,41	0,00
5	-18,50	349,09	1122,62	25,21	0,00
5	-19,00	379,35	1212,45	26,00	0,00
5	-19,50	408,42	1307,34	26,79	0,00
5	-20,00	436,44	1407,47	27,59	0,00
5	-20,50	463,56	1513,04	28,38	0,00
5	-21,00	489,91	1624,21	29,17	0,00
5	-21,50	515,61	1741,18	29,96	0,00
6	-18,00	303,93	942,00	24,41	0,00
6	-18,50	335,43	1021,54	25,21	0,00
6	-19,00	365,49	1105,72	26,00	0,00
6	-19,50	394,31	1194,74	26,79	0,00
6	-20,00	422,07	1288,76	27,59	0,00
6	-20,50	448,92	1387,97	28,38	0,00
6	-21,00	475,00	1492,56	29,17	0,00
6	-21,50	500,43	1602,70	29,96	0,00
8	-18,00	347,84	1147,84	24,41	0,00
8	-18,50	375,25	1238,54	25,21	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
8	-19,00	404,65	1334,28	26,00	0,00
8	-19,50	432,96	1435,26	26,79	0,00
8	-20,00	460,33	1541,65	27,59	0,00
8	-20,50	486,90	1653,64	28,38	0,00
8	-21,00	512,78	1771,42	29,17	0,00
8	-21,50	538,07	1895,16	29,96	0,00
9	-18,00	365,61	1020,93	24,41	0,00
9	-18,50	393,29	1104,61	25,21	0,00
9	-19,00	420,00	1193,09	26,00	0,00
9	-19,50	445,88	1286,56	26,79	0,00
9	-20,00	471,09	1385,20	27,59	0,00
9	-20,50	495,73	1489,19	28,38	0,00
9	-21,00	519,90	1598,71	29,17	0,00
9	-21,50	543,66	1713,95	29,96	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for sand and gravel are adjusted for the coarsness of the actual soil (sand when D50 > 0.6mm; gravel when D50 > 2 mm).
Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.2.3 Pile group 3

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
3
7

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	322,91	982,70	24,41	0,00
3	-18,50	347,77	1064,63	25,21	0,00
3	-19,00	377,49	1151,32	26,00	0,00
3	-19,50	406,09	1242,97	26,79	0,00
3	-20,00	433,68	1339,76	27,59	0,00
3	-20,50	460,40	1441,87	28,38	0,00
3	-21,00	486,39	1549,49	29,17	0,00
3	-21,50	511,75	1662,79	29,96	0,00
5	-18,00	317,44	1037,67	24,41	0,00
5	-18,50	349,09	1122,62	25,21	0,00
5	-19,00	379,35	1212,45	26,00	0,00
5	-19,50	408,42	1307,34	26,79	0,00
5	-20,00	436,44	1407,47	27,59	0,00
5	-20,50	463,56	1513,04	28,38	0,00
5	-21,00	489,91	1624,21	29,17	0,00
5	-21,50	515,61	1741,18	29,96	0,00
6	-18,00	303,93	942,00	24,41	0,00
6	-18,50	335,43	1021,54	25,21	0,00
6	-19,00	365,49	1105,72	26,00	0,00
6	-19,50	394,31	1194,74	26,79	0,00
6	-20,00	422,07	1288,76	27,59	0,00
6	-20,50	448,92	1387,97	28,38	0,00
6	-21,00	475,00	1492,56	29,17	0,00
6	-21,50	500,43	1602,70	29,96	0,00
8	-18,00	347,84	1147,84	24,41	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
8	-18,50	375,25	1238,54	25,21	0,00
8	-19,00	404,65	1334,28	26,00	0,00
8	-19,50	432,96	1435,26	26,79	0,00
8	-20,00	460,33	1541,65	27,59	0,00
8	-20,50	486,90	1653,64	28,38	0,00
8	-21,00	512,78	1771,42	29,17	0,00
8	-21,50	538,07	1895,16	29,96	0,00
9	-18,00	365,61	1020,93	24,41	0,00
9	-18,50	393,29	1104,61	25,21	0,00
9	-19,00	420,00	1193,09	26,00	0,00
9	-19,50	445,88	1286,56	26,79	0,00
9	-20,00	471,09	1385,20	27,59	0,00
9	-20,50	495,73	1489,19	28,38	0,00
9	-21,00	519,90	1598,71	29,17	0,00
9	-21,50	543,66	1713,95	29,96	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for sand and gravel are adjusted for the coarsness of the actual soil (sand when D50 > 0.6mm; gravel when D50 > 2 mm).
Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.2.4 Pile group 4

Number of piles belonging to this pile group : 4
Names of piles belonging to this pile group
4
5
6
9

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	351,79	2450,49	24,41	0,00
3	-18,50	381,70	2713,37	25,21	0,00
3	-19,00	418,03	2995,33	26,00	0,00
3	-19,50	453,64	3297,11	26,79	0,00
3	-20,00	488,55	3619,44	27,59	0,00
3	-20,50	522,85	3963,06	28,38	0,00
3	-21,00	556,63	4328,69	29,17	0,00
3	-21,50	589,97	4717,06	29,96	0,00
5	-18,00	344,56	2631,90	24,41	0,00
5	-18,50	382,27	2906,86	25,21	0,00
5	-19,00	419,03	3201,34	26,00	0,00
5	-19,50	454,96	3516,07	26,79	0,00
5	-20,00	490,16	3851,79	27,59	0,00
5	-20,50	524,74	4209,23	28,38	0,00
5	-21,00	558,78	4589,11	29,17	0,00
5	-21,50	592,35	4992,17	29,96	0,00
6	-18,00	330,35	2333,36	24,41	0,00
6	-18,50	367,96	2586,70	25,21	0,00
6	-19,00	404,58	2858,61	26,00	0,00
6	-19,50	440,33	3149,83	26,79	0,00
6	-20,00	475,35	3461,09	27,59	0,00
6	-20,50	509,74	3793,11	28,38	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
6	-21,00	543,59	4146,63	29,17	0,00
6	-21,50	576,98	4522,38	29,96	0,00
8	-18,00	383,00	3012,36	24,41	0,00
8	-18,50	416,13	3310,32	25,21	0,00
8	-19,00	452,28	3628,47	26,00	0,00
8	-19,50	487,67	3967,56	26,79	0,00
8	-20,00	522,42	4328,31	27,59	0,00
8	-20,50	556,60	4711,46	28,38	0,00
8	-21,00	590,30	5117,73	29,17	0,00
8	-21,50	623,59	5547,85	29,96	0,00
9	-18,00	411,37	2592,46	24,41	0,00
9	-18,50	446,33	2862,35	25,21	0,00
9	-19,00	480,60	3151,45	26,00	0,00
9	-19,50	514,31	3460,50	26,79	0,00
9	-20,00	547,53	3790,22	27,59	0,00
9	-20,50	580,36	4141,35	28,38	0,00
9	-21,00	612,84	4514,61	29,17	0,00
9	-21,50	645,05	4910,74	29,96	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for sand and gravel are adjusted for the coarsness of the actual soil (sand when D50 > 0.6mm; gravel when D50 > 2 mm).
Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.3 Results for pile t pe : DP 460

3.5.3.1 Pile group 1

Number of piles belonging to this pile group : 1
Names of piles belonging to this pile group
1

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	331,73	374,33	30,73	0,00
3	-18,50	353,89	390,38	31,73	0,00
3	-19,00	379,71	406,43	32,73	0,00
3	-19,50	403,90	422,48	33,73	0,00
3	-20,00	426,65	438,53	34,72	0,00
3	-20,50	448,19	454,58	35,72	0,00
3	-21,00	468,72	470,63	36,72	0,00
3	-21,50	486,68	486,68	37,72	0,00
5	-18,00	327,79	383,86	30,73	0,00
5	-18,50	356,39	399,91	31,73	0,00
5	-19,00	382,98	415,96	32,73	0,00
5	-19,50	407,82	432,01	33,73	0,00
5	-20,00	431,18	448,06	34,72	0,00
5	-20,50	453,28	464,11	35,72	0,00
5	-21,00	474,31	480,16	36,72	0,00
5	-21,50	494,46	496,21	37,72	0,00
6	-18,00	313,38	363,03	30,73	0,00
6	-18,50	341,78	379,08	31,73	0,00
6	-19,00	368,08	395,13	32,73	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
6	-19,50	392,60	411,18	33,73	0,00
6	-20,00	415,61	427,23	34,72	0,00
6	-20,50	437,34	443,27	35,72	0,00
6	-21,00	458,01	459,32	36,72	0,00
6	-21,50	475,37	475,37	37,72	0,00
8	-18,00	352,61	398,77	30,73	0,00
8	-18,50	376,95	414,82	31,73	0,00
8	-19,00	402,36	430,87	32,73	0,00
8	-19,50	426,22	446,92	33,73	0,00
8	-20,00	448,75	462,97	34,72	0,00
8	-20,50	470,16	479,02	35,72	0,00
8	-21,00	490,63	495,07	36,72	0,00
8	-21,50	510,31	511,12	37,72	0,00
9	-18,00	360,63	377,05	30,73	0,00
9	-18,50	383,64	393,10	31,73	0,00
9	-19,00	405,28	409,15	32,73	0,00
9	-19,50	425,20	425,20	33,73	0,00
9	-20,00	441,25	441,25	34,72	0,00
9	-20,50	457,30	457,30	35,72	0,00
9	-21,00	473,35	473,35	36,72	0,00
9	-21,50	489,40	489,40	37,72	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for sand and gravel are adjusted for the coarsness of the actual soil (sand when D50 > 0.6mm; gravel when D50 > 2 mm).
Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.3.2 Pile group 2

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
2
10

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	352,78	985,37	30,73	0,00
3	-18,50	378,75	1067,56	31,73	0,00
3	-19,00	409,61	1154,53	32,73	0,00
3	-19,50	439,17	1246,48	33,73	0,00
3	-20,00	467,60	1343,58	34,72	0,00
3	-20,50	495,10	1446,02	35,72	0,00
3	-21,00	521,81	1553,97	36,72	0,00
3	-21,50	547,89	1667,63	37,72	0,00
5	-18,00	347,61	1040,52	30,73	0,00
5	-18,50	380,73	1125,74	31,73	0,00
5	-19,00	412,20	1215,85	32,73	0,00
5	-19,50	442,26	1311,05	33,73	0,00
5	-20,00	471,16	1411,50	34,72	0,00
5	-20,50	499,06	1517,40	35,72	0,00
5	-21,00	526,15	1628,93	36,72	0,00
5	-21,50	552,56	1746,27	37,72	0,00
6	-18,00	332,69	944,57	30,73	0,00
6	-18,50	365,67	1024,36	31,73	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
6	-19,00	396,94	1108,82	32,73	0,00
6	-19,50	426,76	1198,11	33,73	0,00
6	-20,00	455,38	1292,43	34,72	0,00
6	-20,50	483,01	1391,96	35,72	0,00
6	-21,00	509,83	1496,87	36,72	0,00
6	-21,50	535,98	1607,36	37,72	0,00
8	-18,00	378,52	1151,04	30,73	0,00
8	-18,50	407,22	1242,02	31,73	0,00
8	-19,00	437,81	1338,07	32,73	0,00
8	-19,50	467,13	1439,37	33,73	0,00
8	-20,00	495,40	1546,10	34,72	0,00
8	-20,50	522,78	1658,44	35,72	0,00
8	-21,00	549,43	1776,58	36,72	0,00
8	-21,50	575,48	1900,70	37,72	0,00
9	-18,00	394,84	1023,73	30,73	0,00
9	-18,50	423,52	1107,68	31,73	0,00
9	-19,00	451,11	1196,44	32,73	0,00
9	-19,50	477,82	1290,20	33,73	0,00
9	-20,00	503,81	1389,15	34,72	0,00
9	-20,50	529,23	1493,47	35,72	0,00
9	-21,00	554,19	1603,34	36,72	0,00
9	-21,50	578,77	1718,94	37,72	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for sand and gravel are adjusted for the coarsness of the actual soil (sand when D50 > 0.6mm; gravel when D50 > 2 mm).
Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.3.3 Pile group 3

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
3
7

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	352,78	985,37	30,73	0,00
3	-18,50	378,75	1067,56	31,73	0,00
3	-19,00	409,61	1154,53	32,73	0,00
3	-19,50	439,17	1246,48	33,73	0,00
3	-20,00	467,60	1343,58	34,72	0,00
3	-20,50	495,10	1446,02	35,72	0,00
3	-21,00	521,81	1553,97	36,72	0,00
3	-21,50	547,89	1667,63	37,72	0,00
5	-18,00	347,61	1040,52	30,73	0,00
5	-18,50	380,73	1125,74	31,73	0,00
5	-19,00	412,20	1215,85	32,73	0,00
5	-19,50	442,26	1311,05	33,73	0,00
5	-20,00	471,16	1411,50	34,72	0,00
5	-20,50	499,06	1517,40	35,72	0,00
5	-21,00	526,15	1628,93	36,72	0,00
5	-21,50	552,56	1746,27	37,72	0,00
6	-18,00	332,69	944,57	30,73	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
6	-18,50	365,67	1024,36	31,73	0,00
6	-19,00	396,94	1108,82	32,73	0,00
6	-19,50	426,76	1198,11	33,73	0,00
6	-20,00	455,38	1292,43	34,72	0,00
6	-20,50	483,01	1391,96	35,72	0,00
6	-21,00	509,83	1496,87	36,72	0,00
6	-21,50	535,98	1607,36	37,72	0,00
8	-18,00	378,52	1151,04	30,73	0,00
8	-18,50	407,22	1242,02	31,73	0,00
8	-19,00	437,81	1338,07	32,73	0,00
8	-19,50	467,13	1439,37	33,73	0,00
8	-20,00	495,40	1546,10	34,72	0,00
8	-20,50	522,78	1658,44	35,72	0,00
8	-21,00	549,43	1776,58	36,72	0,00
8	-21,50	575,48	1900,70	37,72	0,00
9	-18,00	394,84	1023,73	30,73	0,00
9	-18,50	423,52	1107,68	31,73	0,00
9	-19,00	451,11	1196,44	32,73	0,00
9	-19,50	477,82	1290,20	33,73	0,00
9	-20,00	503,81	1389,15	34,72	0,00
9	-20,50	529,23	1493,47	35,72	0,00
9	-21,00	554,19	1603,34	36,72	0,00
9	-21,50	578,77	1718,94	37,72	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for sand and gravel are adjusted for the coarsness of the actual soil (sand when D50 > 0.6mm; gravel when D50 > 2 mm).
Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.3.4 Pile group 4

Number of piles belonging to this pile group : 4
Names of piles belonging to this pile group
4
5
6
9

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	389,20	2468,43	30,73	0,00
3	-18,50	421,45	2732,78	31,73	0,00
3	-19,00	460,54	3016,28	32,73	0,00
3	-19,50	498,78	3319,68	33,73	0,00
3	-20,00	536,22	3643,68	34,72	0,00
3	-20,50	573,00	3989,03	35,72	0,00
3	-21,00	609,24	4356,45	36,72	0,00
3	-21,50	645,02	4746,69	37,72	0,00
5	-18,00	381,74	2650,78	30,73	0,00
5	-18,50	422,44	2927,25	31,73	0,00
5	-19,00	462,00	3223,31	32,73	0,00
5	-19,50	500,58	3539,70	33,73	0,00
5	-20,00	538,35	3877,12	34,72	0,00
5	-20,50	575,42	4236,33	35,72	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
5	-21,00	611,92	4618,05	36,72	0,00
5	-21,50	647,93	5023,01	37,72	0,00
6	-18,00	365,97	2350,59	30,73	0,00
6	-18,50	406,57	2605,36	31,73	0,00
6	-19,00	445,98	2878,78	32,73	0,00
6	-19,50	484,39	3171,56	33,73	0,00
6	-20,00	521,97	3484,44	34,72	0,00
6	-20,50	558,85	3818,16	35,72	0,00
6	-21,00	595,15	4173,43	36,72	0,00
6	-21,50	630,98	4550,99	37,72	0,00
8	-18,00	422,66	3033,07	30,73	0,00
8	-18,50	458,45	3332,60	31,73	0,00
8	-19,00	497,38	3652,40	32,73	0,00
8	-19,50	535,43	3993,19	33,73	0,00
8	-20,00	572,74	4355,71	34,72	0,00
8	-20,50	609,44	4740,69	35,72	0,00
8	-21,00	645,62	5148,85	36,72	0,00
8	-21,50	681,36	5580,93	37,72	0,00
9	-18,00	451,98	2610,97	30,73	0,00
9	-18,50	489,58	2882,35	31,73	0,00
9	-19,00	526,41	3173,01	32,73	0,00
9	-19,50	562,62	3483,67	33,73	0,00
9	-20,00	598,33	3815,08	34,72	0,00
9	-20,50	633,62	4167,95	35,72	0,00
9	-21,00	668,59	4543,02	36,72	0,00
9	-21,50	703,28	4941,02	37,72	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for sand and gravel are adjusted for the coarsness of the actual soil (sand when D50 > 0.6mm; gravel when D50 > 2 mm).
Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.4 Results for pile t pe : funde 380 450

3.5.4.1 Pile group 1

Number of piles belonging to this pile group : 1
Names of piles belonging to this pile group
1

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	308,95	376,77	25,01	0,00
3	-18,50	330,88	392,95	25,83	0,00
3	-19,00	356,65	409,13	26,64	0,00
3	-19,50	381,02	425,31	27,45	0,00
3	-20,00	404,11	441,49	28,26	0,00
3	-20,50	426,11	457,67	29,07	0,00
3	-21,00	447,16	473,84	29,89	0,00
3	-21,50	467,40	490,02	30,70	0,00
5	-18,00	304,48	386,38	25,01	0,00
5	-18,50	332,63	402,56	25,83	0,00
5	-19,00	359,08	418,73	26,64	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
5	-19,50	384,04	434,91	27,45	0,00
5	-20,00	407,69	451,09	28,26	0,00
5	-20,50	430,21	467,27	29,07	0,00
5	-21,00	451,74	483,45	29,89	0,00
5	-21,50	472,42	499,63	30,70	0,00
6	-18,00	291,25	365,37	25,01	0,00
6	-18,50	319,21	381,55	25,83	0,00
6	-19,00	345,39	397,73	26,64	0,00
6	-19,50	370,04	413,91	27,45	0,00
6	-20,00	393,35	430,09	28,26	0,00
6	-20,50	415,51	446,27	29,07	0,00
6	-21,00	436,69	462,45	29,89	0,00
6	-21,50	457,03	478,63	30,70	0,00
8	-18,00	330,03	401,40	25,01	0,00
8	-18,50	354,05	417,58	25,83	0,00
8	-19,00	379,38	433,76	26,64	0,00
8	-19,50	403,37	449,94	27,45	0,00
8	-20,00	426,18	466,12	28,26	0,00
8	-20,50	447,98	482,30	29,07	0,00
8	-21,00	468,90	498,48	29,89	0,00
8	-21,50	489,06	514,65	30,70	0,00
9	-18,00	340,94	379,51	25,01	0,00
9	-18,50	364,12	395,69	25,83	0,00
9	-19,00	386,07	411,87	26,64	0,00
9	-19,50	406,99	428,04	27,45	0,00
9	-20,00	427,05	444,22	28,26	0,00
9	-20,50	446,37	460,40	29,07	0,00
9	-21,00	465,09	476,58	29,89	0,00
9	-21,50	483,30	492,76	30,70	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.4.2 Pile group 2

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
2
10

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	326,00	982,99	25,01	0,00
3	-18,50	350,98	1064,94	25,83	0,00
3	-19,00	380,83	1151,66	26,64	0,00
3	-19,50	409,54	1243,34	27,45	0,00
3	-20,00	437,23	1340,16	28,26	0,00
3	-20,50	464,05	1442,31	29,07	0,00
3	-21,00	490,12	1549,96	29,89	0,00
3	-21,50	515,56	1663,29	30,70	0,00
5	-18,00	320,54	1037,98	25,01	0,00
5	-18,50	352,36	1122,95	25,83	0,00
5	-19,00	382,76	1212,81	26,64	0,00
5	-19,50	411,94	1307,73	27,45	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
5	-20,00	440,07	1407,90	28,26	0,00
5	-20,50	467,29	1513,49	29,07	0,00
5	-21,00	493,72	1624,71	29,89	0,00
5	-21,50	519,50	1741,72	30,70	0,00
6	-18,00	306,88	942,27	25,01	0,00
6	-18,50	338,55	1021,84	25,83	0,00
6	-19,00	368,75	1106,05	26,64	0,00
6	-19,50	397,69	1195,09	27,45	0,00
6	-20,00	425,56	1289,14	28,26	0,00
6	-20,50	452,50	1388,39	29,07	0,00
6	-21,00	478,66	1493,01	29,89	0,00
6	-21,50	504,17	1603,19	30,70	0,00
8	-18,00	351,02	1148,18	25,01	0,00
8	-18,50	378,57	1238,90	25,83	0,00
8	-19,00	408,10	1334,68	26,64	0,00
8	-19,50	436,53	1435,69	27,45	0,00
8	-20,00	464,01	1542,12	28,26	0,00
8	-20,50	490,67	1654,15	29,07	0,00
8	-21,00	516,64	1771,96	29,89	0,00
8	-21,50	542,01	1895,73	30,70	0,00
9	-18,00	368,66	1021,23	25,01	0,00
9	-18,50	396,45	1104,94	25,83	0,00
9	-19,00	423,26	1193,45	26,64	0,00
9	-19,50	449,24	1286,94	27,45	0,00
9	-20,00	474,53	1385,61	28,26	0,00
9	-20,50	499,26	1489,64	29,07	0,00
9	-21,00	523,51	1599,19	29,89	0,00
9	-21,50	547,36	1714,47	30,70	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.4.3 Pile group 3

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
3
7

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	326,00	982,99	25,01	0,00
3	-18,50	350,98	1064,94	25,83	0,00
3	-19,00	380,83	1151,66	26,64	0,00
3	-19,50	409,54	1243,34	27,45	0,00
3	-20,00	437,23	1340,16	28,26	0,00
3	-20,50	464,05	1442,31	29,07	0,00
3	-21,00	490,12	1549,96	29,89	0,00
3	-21,50	515,56	1663,29	30,70	0,00
5	-18,00	320,54	1037,98	25,01	0,00
5	-18,50	352,36	1122,95	25,83	0,00
5	-19,00	382,76	1212,81	26,64	0,00
5	-19,50	411,94	1307,73	27,45	0,00
5	-20,00	440,07	1407,90	28,26	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
5	-20,50	467,29	1513,49	29,07	0,00
5	-21,00	493,72	1624,71	29,89	0,00
5	-21,50	519,50	1741,72	30,70	0,00
6	-18,00	306,88	942,27	25,01	0,00
6	-18,50	338,55	1021,84	25,83	0,00
6	-19,00	368,75	1106,05	26,64	0,00
6	-19,50	397,69	1195,09	27,45	0,00
6	-20,00	425,56	1289,14	28,26	0,00
6	-20,50	452,50	1388,39	29,07	0,00
6	-21,00	478,66	1493,01	29,89	0,00
6	-21,50	504,17	1603,19	30,70	0,00
8	-18,00	351,02	1148,18	25,01	0,00
8	-18,50	378,57	1238,90	25,83	0,00
8	-19,00	408,10	1334,68	26,64	0,00
8	-19,50	436,53	1435,69	27,45	0,00
8	-20,00	464,01	1542,12	28,26	0,00
8	-20,50	490,67	1654,15	29,07	0,00
8	-21,00	516,64	1771,96	29,89	0,00
8	-21,50	542,01	1895,73	30,70	0,00
9	-18,00	368,66	1021,23	25,01	0,00
9	-18,50	396,45	1104,94	25,83	0,00
9	-19,00	423,26	1193,45	26,64	0,00
9	-19,50	449,24	1286,94	27,45	0,00
9	-20,00	474,53	1385,61	28,26	0,00
9	-20,50	499,26	1489,64	29,07	0,00
9	-21,00	523,51	1599,19	29,89	0,00
9	-21,50	547,36	1714,47	30,70	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.4.4 Pile group 4

Number of piles belonging to this pile group : 4
Names of piles belonging to this pile group
4
5
6
9

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	355,59	2452,30	25,01	0,00
3	-18,50	385,74	2715,32	25,83	0,00
3	-19,00	422,36	2997,44	26,64	0,00
3	-19,50	458,25	3299,38	27,45	0,00
3	-20,00	493,41	3621,88	28,26	0,00
3	-20,50	527,97	3965,67	29,07	0,00
3	-21,00	562,01	4331,48	29,89	0,00
3	-21,50	595,60	4720,04	30,70	0,00
5	-18,00	348,33	2633,80	25,01	0,00
5	-18,50	386,35	2908,91	25,83	0,00
5	-19,00	423,40	3203,55	26,64	0,00
5	-19,50	459,61	3518,45	27,45	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
5	-20,00	495,08	3854,34	28,26	0,00
5	-20,50	529,91	4211,95	29,07	0,00
5	-21,00	564,21	4592,02	29,89	0,00
5	-21,50	598,04	4995,27	30,70	0,00
6	-18,00	333,96	2335,10	25,01	0,00
6	-18,50	371,88	2588,58	25,83	0,00
6	-19,00	408,79	2860,64	26,64	0,00
6	-19,50	444,83	3152,02	27,45	0,00
6	-20,00	480,11	3463,44	28,26	0,00
6	-20,50	514,76	3795,63	29,07	0,00
6	-21,00	548,86	4149,33	29,89	0,00
6	-21,50	582,50	4525,26	30,70	0,00
8	-18,00	387,03	3014,45	25,01	0,00
8	-18,50	420,44	3312,56	25,83	0,00
8	-19,00	456,88	3630,88	26,64	0,00
8	-19,50	492,55	3970,14	27,45	0,00
8	-20,00	527,56	4331,07	28,26	0,00
8	-20,50	562,00	4714,40	29,07	0,00
8	-21,00	595,96	5120,86	29,89	0,00
8	-21,50	629,50	5551,18	30,70	0,00
9	-18,00	415,51	2594,32	25,01	0,00
9	-18,50	450,74	2864,36	25,83	0,00
9	-19,00	485,28	3153,62	26,64	0,00
9	-19,50	519,24	3462,83	27,45	0,00
9	-20,00	552,72	3792,72	28,26	0,00
9	-20,50	585,80	4144,02	29,07	0,00
9	-21,00	618,53	4517,47	29,89	0,00
9	-21,50	650,99	4913,79	30,70	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

End of Report

Bijlage 5 Uitvoer D-Foundation trek representatief

Report for D-Foundations 17.1

Design and Verification according to Eurocode 7 of Bearing/Tension Piles and Shallow Foundations
Developed by Deltares

Company:	CRUX Engineering B.V.
Date of report:	5-3-2018
Time of report:	14:03:49
Date of calculation:	5-3-2018
Time of calculation:	14:03:26
Filename:	P:\..\04 REK\GEO\Paal\DFouc1 Trekdraagvermogen kelder -2,6_BGT
Project identification:	
	D-Foundations DFouc1 Trekdraagvermogen kelder -2,6_BGT

1 Table of Contents

1 Table of Contents 2
2 Input Data 4
2.1 General Input Data 4
2.2 General Report Data 4
2.3 Application Area Model Tension Piles (EC7-NL) 4
2.4 General CPT Data 4
2.4.1 View of CPT's in Foundation Plan 4
2.5 Soil Data 5
2.5.1 Soil Profile 3 5
2.5.2 Soil Profile 5 6
2.5.3 Soil Profile 6 7
2.5.4 Soil Profile 8 8
2.5.5 Soil Profile 9 9
2.6 Pile Types 11
2.6.1 Pile type : fundex 380/450 11
2.6.2 Pile type : fundex 460/560 11
2.6.3 Pile type : DPA 360 12
2.6.4 Pile type : DPA 410 12
2.6.5 Pile type : DPA 460 12
2.6.6 Pile type : fundex 406/560 12
2.6.7 Pile type : Round 510 13
2.7 Foundation Plan 13
2.7.1 View of Foundation Plan 13
2.8 Excavation Data 14
2.9 Optional Parameters 14
2.10 Overruled Parameters 14
2.11 Model Options 14
2.12 Model Options 14
3 Tension Piles (EC7-NL): Indication Bearing Capacity 16
3.1 Errors and Warnings 16
3.2 Remarks 16
3.3 Calculation Parameters 16
3.3.1 Pile Factors 16
3.3.2 Pile type : fundex 380/450 16
3.3.3 Pile type : fundex 460/560 16
3.3.4 Pile type : DPA 410 17
3.3.5 Pile type : DPA 460 17
3.3.6 Pile type : Round 510 17
3.4 Results for all CPT's 17
3.4.1 Results for pile type : fundex 380/450 17
3.4.1.1 Pile group 1 17
3.4.1.2 Pile group 2 18
3.4.1.3 Pile group 3 18
3.4.1.4 Pile group 4 18
3.4.2 Results for pile type : fundex 460/560 19
3.4.2.1 Pile group 1 19
3.4.2.2 Pile group 2 19
3.4.2.3 Pile group 3 19
3.4.2.4 Pile group 4 19
3.4.3 Results for pile type : DPA 410 20
3.4.3.1 Pile group 1 20
3.4.3.2 Pile group 2 20
3.4.3.3 Pile group 3 20
3.4.3.4 Pile group 4 21
3.4.4 Results for pile type : DPA 460 21
3.4.4.1 Pile group 1 21
3.4.4.2 Pile group 2 21
3.4.4.3 Pile group 3 22
3.4.4.4 Pile group 4 22
3.4.5 Results for pile type : Round 510 22
3.4.5.1 Pile group 1 22
3.4.5.2 Pile group 2 22
3.4.5.3 Pile group 3 23

3.4.5.4 Pile group 4 23
3.5 INDICATIVE: Results using Ksi3 23
3.5.1 Results for pile type : fundex 380/450 23
3.5.1.1 Pile group 1 23
3.5.1.2 Pile group 2 24
3.5.1.3 Pile group 3 25
3.5.1.4 Pile group 4 26
3.5.2 Results for pile type : fundex 460/560 27
3.5.2.1 Pile group 1 27
3.5.2.2 Pile group 2 28
3.5.2.3 Pile group 3 29
3.5.2.4 Pile group 4 30
3.5.3 Results for pile type : DPA 410 31
3.5.3.1 Pile group 1 31
3.5.3.2 Pile group 2 32
3.5.3.3 Pile group 3 33
3.5.3.4 Pile group 4 34
3.5.4 Results for pile type : DPA 460 35
3.5.4.1 Pile group 1 35
3.5.4.2 Pile group 2 36
3.5.4.3 Pile group 3 37
3.5.4.4 Pile group 4 38
3.5.5 Results for pile type : Round 510 39
3.5.5.1 Pile group 1 39
3.5.5.2 Pile group 2 40
3.5.5.3 Pile group 3 41
3.5.5.4 Pile group 4 42

2 Input Data

2.1 General Input Data

Model	Tension Piles (EC7-NL)

2.2 General Report Data

Geotechnical consultant :	
Design engineer superstructure :	
Principal :	
Title 1 :	
Title 2 :	
Title 3 :	D-Foundations DFouc1 Trekdraagvermogen kelder -2,6_BGT
Number of project :	
Location of project :	

2.3 Application Area Model Tension Piles (EC7-NL)

The design and verifications performed by the TENSION PILES (EC7-NL) model of D-FOUNDATIONS concern pile foundations on which axial static or quasi-static loads cause tensile forces in the piles. Pilegroup effects are taken into account. Calculation of pile forces is based on Cone Penetration Tests. Pile capacities are based on the NEN 9997-1:2016, chapter 7 and where pile/safety factors are concerned, on Dutch Standards NEN 9997-1:2016. Horizontal displacements of piles are not taken into account. Vertical displacements of piles are not calculated. Design of Tension piles based on NEN 9997-1:2016 is limited to piles with lengths between 7 and 50 m and a minimum Length over (equivalent) diameter ratio of 13.5.

2.4 General CPT Data

Number of CPT's :	5
Timing of CPT's :	CPT - Install - Excavation

2.4.1 View of CPT's in Foundation Plan




Number/name CPT	X-coor-dinate [m]	Y-coor-dinate [m]
1: 3	118155,78	484051,62
2: 5	0,00	0,00
3: 6	118139,99	484052,09
4: 8	0,00	0,00
5: 9	118121,90	484051,98

2.5 Soil Data

Number of soil profiles (= number of CPT's) : 5

2.5.1 Soil Profile 3

Belonging to CPT	3
Surface level in [m. reference level] :	0,84
Phreatic level in [m. reference level] :	-0,50
Top of tension zone [m. reference level]:	-11,80
Pile tip level in [m. reference level] :	-20,00
Number of layers in profile :	14




Number layer	Top layer [m R.L.]	Soil Type	Gamma [kN/m3]	Gamma sat [kN/m3]	Min. Void Ratio [%]	Max. Void Ratio [%]	Median [mm]	Max. Cone resistance [kPa]	Use Max. Cone resistance
1	0,840	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
2	0,340	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
3	0,240	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
4	-2,760	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
5	-2,860	Peat	10,00	10,00	0,40	0,80		12/15	Standa...
6	-5,220	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
7	-8,139	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
8	-8,239	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
9	-8,459	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
10	-9,278	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
11	-9,778	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...

Number layer	Top layer [m R.L.]	Soil Type	Gamma [kN/m3]	Gamma sat [kN/m3]	Min. Void Ratio [%]	Max. Void Ratio [%]	Median [mm]	Max. Cone resistance [kPa]	Use Max. Cone resistance
12	-9,978	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
13	-12,016	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
14	-24,024	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...

Number layer	Top layer [m R.L.]	Soil Type	Phi [deg]	Addit. PP at top [kN/m2]	Addit. PP at bottom [kN/m2]	OCR value [-]	Use Tension
1	0,840	Sand	27,00	0,00	0,00	1,000	True
2	0,340	Sand	27,00	0,00	0,00	1,000	True
3	0,240	Sand	27,00	0,00	0,00	1,000	True
4	-2,760	Clay	17,50	0,00	0,00	1,000	True
5	-2,860	Peat	15,00	0,00	0,00	1,000	False
6	-5,220	Clay	17,50	0,00	0,00	1,000	True
7	-8,139	Sand	27,00	0,00	0,00	1,000	True
8	-8,239	Clay	17,50	0,00	0,00	1,000	True
9	-8,459	Sand	27,00	0,00	0,00	1,000	True
10	-9,278	Clay	17,50	0,00	0,00	1,000	True
11	-9,778	Sand	27,00	0,00	0,00	1,000	True
12	-9,978	Clay	17,50	0,00	0,00	1,000	True
13	-12,016	Sand	27,00	0,00	0,00	1,000	True
14	-24,024	Sand	27,00	0,00	0,00	1,000	True

2.5.2 Soil Profile 5

Belonging to CPT	5
Surface level in [m. reference level] :	0,84
Phreatic level in [m. reference level] :	-0,50
Top of tension zone [m. reference level]:	-11,40
Pile tip level in [m. reference level] :	-19,26
Number of layers in profile :	13




Number layer	Top layer [m R.L.]	Soil Type	Gamma [kN/m3]	Gamma sat [kN/m3]	Min. Void Ratio [%]	Max. Void Ratio [%]	Median [mm]	Max. Cone resistance [kPa]	Use Max. Cone resistance
1	0,840	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
2	0,440	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
3	0,340	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
4	0,240	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
5	-2,879	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
6	-3,079	Peat	10,00	10,00	0,40	0,80		12/15	Standa...
7	-5,218	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
8	-7,795	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
9	-8,814	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
10	-9,633	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
11	-9,852	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
12	-11,509	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
13	-25,770	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...

Number layer	Top layer [m R.L.]	Soil Type	Phi [deg]	Addit. PP at top [kN/m2]	Addit. PP at bottom [kN/m2]	OCR value [-]	Use Tension
1	0,840	Clay	17,50	0,00	0,00	1,000	True
2	0,440	Clay	17,50	0,00	0,00	1,000	True
3	0,340	Clay	17,50	0,00	0,00	1,000	True
4	0,240	Sand	27,00	0,00	0,00	1,000	True
5	-2,879	Clay	17,50	0,00	0,00	1,000	True
6	-3,079	Peat	15,00	0,00	0,00	1,000	False
7	-5,218	Clay	17,50	0,00	0,00	1,000	True
8	-7,795	Sand	27,00	0,00	0,00	1,000	True
9	-8,814	Clay	17,50	0,00	0,00	1,000	True
10	-9,633	Sand	27,00	0,00	0,00	1,000	True
11	-9,852	Clay	17,50	0,00	0,00	1,000	True
12	-11,509	Sand	27,00	0,00	0,00	1,000	True
13	-25,770	Sand	27,00	0,00	0,00	1,000	True

2.5.3 Soil Profile 6

Belonging to CPT	6
Surface level in [m. reference level] :	0,85
Phreatic level in [m. reference level] :	-0,50
Top of tension zone [m. reference level]:	-11,80
Pile tip level in [m. reference level] :	-20,00
Number of layers in profile :	12




Number layer	Top layer [m R.L.]	Soil Type	Gamma [kN/m3]	Gamma sat [kN/m3]	Min. Void Ratio [%]	Max. Void Ratio [%]	Median [mm]	Max. Cone resistance [kPa]	Use Max. Cone resistance
1	0,850	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
2	-0,350	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
3	-0,450	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
4	-2,589	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
5	-2,689	Peat	10,00	10,00	0,40	0,80		12/15	Standa...
6	-5,108	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
7	-7,865	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
8	-9,184	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
9	-11,479	Peat	10,00	10,00	0,40	0,80		12/15	Standa...
10	-11,798	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
11	-11,898	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
12	-23,987	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...

Number layer	Top layer [m R.L.]	Soil Type	Phi [deg]	Addit. PP at top [kN/m2]	Addit. PP at bottom [kN/m2]	OCR value [-]	Use Tension
1	0,850	Sand	27,00	0,00	0,00	1,000	True
2	-0,350	Sand	27,00	0,00	0,00	1,000	True
3	-0,450	Sand	27,00	0,00	0,00	1,000	True
4	-2,589	Clay	17,50	0,00	0,00	1,000	True
5	-2,689	Peat	15,00	0,00	0,00	1,000	False
6	-5,108	Clay	17,50	0,00	0,00	1,000	True
7	-7,865	Sand	27,00	0,00	0,00	1,000	True
8	-9,184	Clay	17,50	0,00	0,00	1,000	True
9	-11,479	Peat	15,00	0,00	0,00	1,000	False
10	-11,798	Clay	17,50	0,00	0,00	1,000	True
11	-11,898	Sand	27,00	0,00	0,00	1,000	True
12	-23,987	Sand	27,00	0,00	0,00	1,000	True

2.5.4 Soil Profile 8

Belonging to CPT	8
Surface level in [m. reference level] :	0,85

Phreatic level in [m. reference level] :	-0,50
Top of tension zone [m. reference level]:	-11,40
Pile tip level in [m. reference level] :	-19,26
Number of layers in profile :	9




Number layer	Top layer [m R.L.]	Soil Type	Gamma [kN/m3]	Gamma sat [kN/m3]	Min. Void Ratio [%]	Max. Void Ratio [%]	Median [mm]	Max. Cone resistance [kPa]	Use Max. Cone resistance
1	0,850	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
2	0,450	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
3	0,350	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
4	-3,550	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
5	-3,750	Peat	10,00	10,00	0,40	0,80		12/15	Standa...
6	-5,389	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
7	-8,428	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
8	-8,728	Clay	19,00	19,00	0,40	0,80		12/15	Standa...
9	-11,466	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...

Number layer	Top layer [m R.L.]	Soil Type	Phi [deg]	Addit. PP at top [kN/m2]	Addit. PP at bottom [kN/m2]	OCR value [-]	Use Tension
1	0,850	Sand	27,00	0,00	0,00	1,000	True
2	0,450	Sand	27,00	0,00	0,00	1,000	True
3	0,350	Sand	27,00	0,00	0,00	1,000	True
4	-3,550	Clay	17,50	0,00	0,00	1,000	True
5	-3,750	Peat	15,00	0,00	0,00	1,000	False
6	-5,389	Clay	17,50	0,00	0,00	1,000	True
7	-8,428	Sand	27,00	0,00	0,00	1,000	True
8	-8,728	Clay	17,50	0,00	0,00	1,000	True
9	-11,466	Sand	27,00	0,00	0,00	1,000	True

2.5.5 Soil Profile

Belonging to CPT	9
Surface level in [m. reference level] :	0,79
Phreatic level in [m. reference level] :	-0,50
Top of tension zone [m. reference level]:	-11,10

Pile tip level in [m. reference level] :	-19,26
Number of layers in profile :	28



Number layer	Top layer [m R.L.]	Soil Type	Gamma [kN/m3]	Gamma sat [kN/m3]	Min. Void Ratio [%]	Max. Void Ratio [%]	Median [mm]	Max. Cone resistance [kPa]	Use Max. Cone resistance
1	0,790	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
2	0,290	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
3	0,190	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
4	-0,210	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
5	-2,510	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
6	-2,710	Loam	19,00	19,00	0,40	0,80		12/15	Standa...
7	-2,810	Clay	14,00	14,00	0,40	0,80		12/15	Standa...
8	-3,010	Peat	12,00	12,00	0,40	0,80		12/15	Standa...
9	-3,810	Peat	12,00	12,00	0,40	0,80		12/15	Standa...
10	-4,010	Peat	12,00	12,00	0,40	0,80		12/15	Standa...
11	-5,010	Clay	14,00	14,00	0,40	0,80		12/15	Standa...
12	-5,510	Clay	18,00	18,00	0,40	0,80		12/15	Standa...
13	-6,790	Loam	19,00	19,00	0,40	0,80		12/15	Standa...
14	-7,009	Clay	18,00	18,00	0,40	0,80		12/15	Standa...
15	-7,409	Loam	19,00	19,00	0,40	0,80		12/15	Standa...
16	-8,509	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
17	-8,709	Loam	19,00	19,00	0,40	0,80		12/15	Standa...
18	-8,809	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
19	-8,909	Loam	19,00	19,00	0,40	0,80		12/15	Standa...
20	-9,109	Clay	18,00	18,00	0,40	0,80		12/15	Standa...
21	-9,509	Loam	19,00	19,00	0,40	0,80		12/15	Standa...
22	-10,028	Clay	18,00	18,00	0,40	0,80		12/15	Standa...
23	-10,828	Loam	19,00	19,00	0,40	0,80		12/15	Standa...
24	-10,928	Clay	18,00	18,00	0,40	0,80		12/15	Standa...
25	-11,028	Loam	19,00	19,00	0,40	0,80		12/15	Standa...
26	-11,128	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
27	-11,228	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...
28	-24,059	Sand	18,00	20,00	0,40	0,80	0,200	12/15	Standa...

Number layer	Top layer [m R.L.]	Soil Type	Phi [deg]	Addit. PP at top [kN/m2]	Addit. PP at bottom [kN/m2]	OCR value [-]	Use Tension
1	0,790	Sand	25,00	0,00	0,00	1,000	True
2	0,290	Sand	25,00	0,00	0,00	1,000	True
3	0,190	Sand	25,00	0,00	0,00	1,000	True
4	-0,210	Sand	27,00	0,00	0,00	1,000	True
5	-2,510	Sand	25,00	0,00	0,00	1,000	True
6	-2,710	Loam	27,50	0,00	0,00	1,000	True
7	-2,810	Clay	17,50	0,00	0,00	1,000	True
8	-3,010	Peat	15,00	0,00	0,00	1,000	False
9	-3,810	Peat	15,00	0,00	0,00	1,000	False
10	-4,010	Peat	15,00	0,00	0,00	1,000	False
11	-5,010	Clay	17,50	0,00	0,00	1,000	True
12	-5,510	Clay	22,50	0,00	0,00	1,000	True
13	-6,790	Loam	27,50	0,00	0,00	1,000	True
14	-7,009	Clay	22,50	0,00	0,00	1,000	True
15	-7,409	Loam	27,50	0,00	0,00	1,000	True
16	-8,509	Sand	25,00	0,00	0,00	1,000	True
17	-8,709	Loam	27,50	0,00	0,00	1,000	True
18	-8,809	Sand	25,00	0,00	0,00	1,000	True
19	-8,909	Loam	27,50	0,00	0,00	1,000	True
20	-9,109	Clay	22,50	0,00	0,00	1,000	True
21	-9,509	Loam	27,50	0,00	0,00	1,000	True
22	-10,028	Clay	22,50	0,00	0,00	1,000	True
23	-10,828	Loam	27,50	0,00	0,00	1,000	True
24	-10,928	Clay	22,50	0,00	0,00	1,000	True
25	-11,028	Loam	27,50	0,00	0,00	1,000	True
26	-11,128	Sand	25,00	0,00	0,00	1,000	True
27	-11,228	Sand	27,00	0,00	0,00	1,000	True
28	-24,059	Sand	27,00	0,00	0,00	1,000	True

2.6 Pile Types

Note : if alpha;t is not user defined, the next rules apply :
- alpha;t according to table 7.g and table 7.h of NEN 9997-1:2016
- for clay: alpha;t depends on the CPT-value and relative depth
- for peat: alpha;t = 0
- for sand/gravel: alpha;t also depends on the median

Number of pile types : 7

2.6.1 Pile type : funde 380/450

Pile type for shaft friction factor (alpha;t) sand/gravel : Screw pile, cast in place, lost tip

Pile type for shaft friction factor (alpha;t) clay : User defined
Shaft friction factor clay [-] : 0,0000
Materialtype for pile : Concrete
Pile shape : Round pile with lost tip

Pile dimensions :
- Diameter at tip [m] : 0,450
- Diameter shaft [m] : 0,415
- Effective heigth enlarged base [m] : 0,000

2.6.2 Pile type : funde 460/560

Pile type for shaft friction factor (alpha;t) sand/gravel : Screw pile, cast in place, lost tip

Pile type for shaft friction factor (alpha;t) clay : User defined
Shaft friction factor clay [-] : 0,0000
Materialtype for pile : Concrete
Pile shape : Round pile with lost tip

Pile dimensions :
- Diameter at tip [m] : 0,560
- Diameter shaft [m] : 0,510
- Effective heigth enlarged base [m] : 0,000

2.6.3 Pile type : DP 360

Pile type for shaft friction factor (alpha;t) sand/gravel : User defined (vibrating)

Shaft friction factor sand/gravel [-] : 0,0090
Pile type for shaft friction factor (alpha;t) clay : User defined
Shaft friction factor clay [-] : 0,0000
Materialtype for pile : Concrete
Pile shape : Round pile

Pile dimensions :
- Diameter [m] : 0,360

2.6.4 Pile type : DP 410

Pile type for shaft friction factor (alpha;t) sand/gravel : User defined (vibrating)

Shaft friction factor sand/gravel [-] : 0,0090
Pile type for shaft friction factor (alpha;t) clay : User defined
Shaft friction factor clay [-] : 0,0000
Materialtype for pile : Concrete
Pile shape : Round pile

Pile dimensions :
- Diameter [m] : 0,410

2.6.5 Pile type : DP 460

Pile type for shaft friction factor (alpha;t) sand/gravel : User defined (vibrating)

Shaft friction factor sand/gravel [-] : 0,0090
Pile type for shaft friction factor (alpha;t) clay : User defined
Shaft friction factor clay [-] : 0,0000
Materialtype for pile : Concrete
Pile shape : Round pile

Pile dimensions :
- Diameter [m] : 0,460

2.6.6 Pile type : funde 406/560

Pile type for shaft friction factor (alpha;t) sand/gravel : Screw pile, cast in place, lost tip

Pile type for shaft friction factor (alpha;t) clay : User defined
Shaft friction factor clay [-] : 0,0000
Materialtype for pile : Concrete
Pile shape : Round pile with lost tip

Pile dimensions :
- Diameter at tip [m] : 0,560
- Diameter shaft [m] : 0,483
- Effective heigth enlarged base [m] : 0,000

2.6.7 Pile type : Round 510


Pile type for shaft friction factor (alpha;t) sand/gravel :	Screw pile, cast in place, with grout
Pile type for shaft friction factor (alpha;t) clay :	User defined
Shaft friction factor clay [-] :	0,0000
Materialtype for pile :	Concrete
Pile shape :	Round pile
Pile dimensions :	
Diameter [m] :	0,510

2.7 Foundation Plan

Number of piles :	9
Number of collaborating piles* :	1

* : 0 = not defined, 1 = non rigid superstructure, >1 = rigid superstructure

2.7.1 View of Foundation Plan




Pile nr./code	X-coordinate [m]	Y-coordinate [m]	Maximum load [kN]	Minimum load [kN]	Pile head level [m R.L.]	Use alternat. loads	Factor Gamma;var
1: 1	0,00	0,00	0,00	0,00	-2,60	False	n.a.
2: 2	0,00	2,00	0,00	0,00	-2,60	False	n.a.
3: 3	2,00	0,00	0,00	0,00	-2,60	False	n.a.
4: 4	-2,00	-2,00	0,00	0,00	-2,60	False	n.a.
5: 5	2,00	-2,00	0,00	0,00	-2,60	False	n.a.
6: 6	-2,00	2,00	0,00	0,00	-2,60	False	n.a.
7: 7	-2,00	0,00	0,00	0,00	-2,60	False	n.a.
8: 8	2,00	2,00	0,00	0,00	-2,60	False	n.a.
9: 9	0,00	-2,00	0,00	0,00	-2,60	False	n.a.

Note regarding the loads: tension forces are positive, compressive forces are negative
Note 2: See OVERRULED PARAMETERS for gamma;var

2.8 Excavation Data

Excavation level in [m. reference level] :	-2,60
Reduction model :	Safe (NEN)



2.9 Optional Parameters

Unit weight water [kN/m3] :	9,81
Surcharge [kN/m2] :	0,00

2.10 Overruled Parameters

User defined gamma;var [-]	1,00
User defined Factor xi3 [-] :	1,28
User defined Factor xi4 [-] :	1,03
User defined gamma;st [-]	1,00

2.11 Model Options

Suppress compaction
If compaction is used, according to NEN 9997-1:2016 CPT's should be made after installation to verify this assumption
Use the influence of excavations (standard).
Suppress excess pore pressure

2.12 Model Options

Selected pile types :
-fundex 380/450
-fundex 460/560
-DPA 410
-DPA 460
-Round 510

Selected profiles :
- -3
- -5
- -6
- -8
- -9

Trajectory

-begin [m] :	-18,00
-end [m] :	-21,50
-interval [m] :	0,50

3 Tension Piles EC7- : ndication Bearing Capacit

3.1 Errors and arnings

Warning : The factor xi3 (NEN 9997-1:2016) is user defined. Evidence to support this from the NEN deviating value has to be provided.
Warning : The factor xi4 (NEN 9997-1:2016) is user defined. Evidence to support this from the NEN deviating value has to be provided.
Warning : The factor gamma;st (NEN 9997-1:2016) is user defined. Evidence to support this from the NEN deviating value has to be provided.
Warning : The factor gamma;var (NEN 9997-1:2016) is user defined. Evidence to support this from the NEN deviating value has to be provided.
At pile type fundex 380/450 :
Due to the use of a low vibrating pile type, the reduction of CPT-value due to the excavation is done using NEN 9997-1:2016.

At pile type fundex 460/560 :
Due to the use of a low vibrating pile type, the reduction of CPT-value due to the excavation is done using NEN 9997-1:2016.

At pile type Round 510 :
Due to the use of a low vibrating pile type, the reduction of CPT-value due to the excavation is done using NEN 9997-1:2016.

When reviewing the following results, warnings listed above should be considered.

3.2 Remarks

When calculating the max. mobilized soil weight, the topangle is used according to NEN 9997-1:2016.

3.3 Calculation Parameters

3.3.1 Pile Factors

xi3 (user defined) :	1,28
xi4 (user defined) :	1,03
User defined gamma;var [-]	1,000
User defined gamma;st [-]	1,000
Factor gamma;gamma according to NEN 9997-1:2016 table A.2 [-]	
Above excavation level	1,0
Below excavation level	1,1

3.3.2 Pile t pe : funde 380/450

Pile type for shaft friction factor (alpha;t) sand/gravel :	Screw pile, cast in place, lost tip
Pile type for shaft friction factor (alpha;t) clay :	User defined
Shaft friction factor clay [-] :	0,0000
Materialtype for pile :	Concrete
Pile shape :	Round pile with lost tip
Pile dimensions :	
Diameter at tip [m] :	0,450
Diameter shaft [m] :	0,415
Effective heigth enlarged base [m] :	0,000

3.3.3 Pile t pe : funde 460/560

Pile type for shaft friction factor (alpha;t) sand/gravel :	Screw pile, cast in place, lost tip
Pile type for shaft friction factor (alpha;t) clay :	User defined

Shaft friction factor clay [-] :	0,0000
Materialtype for pile :	Concrete
Pile shape :	Round pile with lost tip
Pile dimensions :	
Diameter at tip [m] :	0,560
Diameter shaft [m] :	0,510
Effective heigth enlarged base [m] :	0,000

3.3.4 Pile type : DP 410

Pile type for shaft friction factor (alpha;t) sand/gravel :	User defined (vibrating)
Shaft friction factor sand/gravel [-] :	0,0090
Pile type for shaft friction factor (alpha;t) clay :	User defined
Shaft friction factor clay [-] :	0,0000
Materialtype for pile :	Concrete
Pile shape :	Round pile
Pile dimensions :	
Diameter [m] :	0,410

3.3.5 Pile type : DP 460

Pile type for shaft friction factor (alpha;t) sand/gravel :	User defined (vibrating)
Shaft friction factor sand/gravel [-] :	0,0090
Pile type for shaft friction factor (alpha;t) clay :	User defined
Shaft friction factor clay [-] :	0,0000
Materialtype for pile :	Concrete
Pile shape :	Round pile
Pile dimensions :	
Diameter [m] :	0,460

3.3.6 Pile type : Round 510

Pile type for shaft friction factor (alpha;t) sand/gravel :	Screw pile, cast in place, with grout
Pile type for shaft friction factor (alpha;t) clay :	User defined
Shaft friction factor clay [-] :	0,0000
Materialtype for pile :	Concrete
Pile shape :	Round pile
Pile dimensions :	
Diameter [m] :	0,510

3.4 Results for all CPT's

3.4.1 Results for pile type : funde 380 450

3.4.1.1 Pile group 1

Number of piles belonging to this pile group : 1
Names of piles belonging to this pile group
1

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	365,37	363,18	363,18	Ksi3
-18,50	381,55	386,87	381,55	Ksi4
-19,00	397,73	410,24	397,73	Ksi4
-19,50	413,91	430,38	413,91	Ksi4
-20,00	430,09	446,60	430,09	Ksi4
-20,50	446,27	462,78	446,27	Ksi4
-21,00	462,45	478,96	462,45	Ksi4
-21,50	478,63	495,14	478,63	Ksi4

3.4.1.2 Pile group 2

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
2
9

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	412,80	398,82	398,82	Ksi3
-18,50	449,12	430,35	430,35	Ksi3
-19,00	482,85	462,11	462,11	Ksi3
-19,50	514,79	492,40	492,40	Ksi3
-20,00	545,51	521,52	521,52	Ksi3
-20,50	575,38	549,75	549,75	Ksi3
-21,00	604,65	577,28	577,28	Ksi3
-21,50	633,48	604,26	604,26	Ksi3

3.4.1.3 Pile group 3

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
3
7

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	412,80	398,82	398,82	Ksi3
-18,50	449,12	430,35	430,35	Ksi3
-19,00	482,85	462,11	462,11	Ksi3
-19,50	514,79	492,40	492,40	Ksi3
-20,00	545,51	521,52	521,52	Ksi3
-20,50	575,38	549,75	549,75	Ksi3
-21,00	604,65	577,28	577,28	Ksi3
-21,50	633,48	604,26	604,26	Ksi3

3.4.1.4 Pile group 4

Number of piles belonging to this pile group : 4
Names of piles belonging to this pile group
4
5
6
8

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	484,56	457,66	457,66	Ksi3
-18,50	536,30	499,67	499,67	Ksi3
-19,00	586,24	543,13	543,13	Ksi3
-19,50	634,89	585,55	585,55	Ksi3
-20,00	682,64	627,15	627,15	Ksi3
-20,50	729,75	668,11	668,11	Ksi3
-21,00	776,39	708,56	708,56	Ksi3

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-21,50	822,69	748,61	748,61	Ksi3

3.4.2 Results for pile type : funde 460/560

3.4.2.1 Pile group 1

Number of piles belonging to this pile group : 1
Names of piles belonging to this pile group
1

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	360,04	376,26	360,04	Ksi4
-18,50	375,93	392,15	375,93	Ksi4
-19,00	391,82	408,04	391,82	Ksi4
-19,50	407,71	423,93	407,71	Ksi4
-20,00	423,60	439,82	423,60	Ksi4
-20,50	439,49	455,71	439,49	Ksi4
-21,00	455,38	471,60	455,38	Ksi4
-21,50	471,27	487,49	471,27	Ksi4

3.4.2.2 Pile group 2

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
2
9

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	461,36	450,99	450,99	Ksi3
-18,50	498,74	483,76	483,76	Ksi3
-19,00	533,53	516,61	516,61	Ksi3
-19,50	566,85	547,97	547,97	Ksi3
-20,00	599,32	578,29	578,29	Ksi3
-20,50	631,24	607,89	607,89	Ksi3
-21,00	662,76	636,98	636,98	Ksi3
-21,50	693,96	665,68	665,68	Ksi3

3.4.2.3 Pile group 3

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
3
7

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	461,36	450,99	450,99	Ksi3
-18,50	498,74	483,76	483,76	Ksi3
-19,00	533,53	516,61	516,61	Ksi3
-19,50	566,85	547,97	547,97	Ksi3
-20,00	599,32	578,29	578,29	Ksi3
-20,50	631,24	607,89	607,89	Ksi3
-21,00	662,76	636,98	636,98	Ksi3
-21,50	693,96	665,68	665,68	Ksi3

3.4.2.4 Pile group 4

Number of piles belonging to this pile group : 4
Names of piles belonging to this pile group
4
5

6
8

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	565,76	537,52	537,52	Ksi3
-18,50	624,27	585,02	585,02	Ksi3
-19,00	680,90	634,13	634,13	Ksi3
-19,50	736,43	682,18	682,18	Ksi3
-20,00	791,27	729,46	729,46	Ksi3
-20,50	845,64	776,18	776,18	Ksi3
-21,00	899,64	822,51	822,51	Ksi3
-21,50	953,35	868,53	868,53	Ksi3

3.4.3 Results for pile type : DP 410

3.4.3.1 Pile group 1

Number of piles belonging to this pile group : 1
Names of piles belonging to this pile group
1

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	365,61	361,33	361,33	Ksi3
-18,50	381,80	385,12	381,80	Ksi4
-19,00	398,00	408,58	398,00	Ksi4
-19,50	414,19	429,99	414,19	Ksi4
-20,00	430,38	446,91	430,38	Ksi4
-20,50	446,57	463,10	446,57	Ksi4
-21,00	462,77	479,30	462,77	Ksi4
-21,50	478,96	495,49	478,96	Ksi4

3.4.3.2 Pile group 2

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
2
9

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	409,94	395,76	395,76	Ksi3
-18,50	446,19	427,21	427,21	Ksi3
-19,00	479,88	458,90	458,90	Ksi3
-19,50	511,77	489,12	489,12	Ksi3
-20,00	542,41	518,18	518,18	Ksi3
-20,50	572,19	546,34	546,34	Ksi3
-21,00	601,36	573,80	573,80	Ksi3
-21,50	630,08	600,70	600,70	Ksi3

3.4.3.3 Pile group 3

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
3
7

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	409,94	395,76	395,76	Ksi3
-18,50	446,19	427,21	427,21	Ksi3
-19,00	479,88	458,90	458,90	Ksi3
-19,50	511,77	489,12	489,12	Ksi3
-20,00	542,41	518,18	518,18	Ksi3

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-20,50	572,19	546,34	546,34	Ksi3
-21,00	601,36	573,80	573,80	Ksi3
-21,50	630,08	600,70	600,70	Ksi3

3.4.3.4 Pile group 4

Number of piles belonging to this pile group : 4
Names of piles belonging to this pile group
4
5
6
8

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	480,09	453,26	453,26	Ksi3
-18,50	531,48	494,97	494,97	Ksi3
-19,00	581,06	538,12	538,12	Ksi3
-19,50	629,35	580,24	580,24	Ksi3
-20,00	676,74	621,54	621,54	Ksi3
-20,50	723,48	662,19	662,19	Ksi3
-21,00	769,74	702,34	702,34	Ksi3
-21,50	815,65	742,07	742,07	Ksi3

3.4.4 Results for pile type : DP 460

3.4.4.1 Pile group 1

Number of piles belonging to this pile group : 1
Names of piles belonging to this pile group
1

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	363,03	377,06	363,03	Ksi4
-18,50	379,08	395,46	379,08	Ksi4
-19,00	395,13	411,51	395,13	Ksi4
-19,50	411,18	427,56	411,18	Ksi4
-20,00	427,23	443,61	427,23	Ksi4
-20,50	443,27	459,66	443,27	Ksi4
-21,00	459,32	475,71	459,32	Ksi4
-21,50	475,37	491,76	475,37	Ksi4

3.4.4.2 Pile group 2

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
2
9

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	437,05	424,83	424,83	Ksi3
-18,50	473,86	457,02	457,02	Ksi3
-19,00	508,04	489,34	489,34	Ksi3
-19,50	540,54	520,15	520,15	Ksi3
-20,00	572,00	549,82	549,82	Ksi3
-20,50	602,76	578,66	578,66	Ksi3
-21,00	633,04	606,88	606,88	Ksi3
-21,50	662,98	634,63	634,63	Ksi3

3.4.4.3 Pile group 3

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
3
7

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	437,05	424,83	424,83	Ksi3
-18,50	473,86	457,02	457,02	Ksi3
-19,00	508,04	489,34	489,34	Ksi3
-19,50	540,54	520,15	520,15	Ksi3
-20,00	572,00	549,82	549,82	Ksi3
-20,50	602,76	578,66	578,66	Ksi3
-21,00	633,04	606,88	606,88	Ksi3
-21,50	662,98	634,63	634,63	Ksi3

3.4.4.4 Pile group 4

Number of piles belonging to this pile group : 4
Names of piles belonging to this pile group
4
5
6
8

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	523,81	496,30	496,30	Ksi3
-18,50	578,77	540,97	540,97	Ksi3
-19,00	631,85	587,14	587,14	Ksi3
-19,50	683,71	632,24	632,24	Ksi3
-20,00	734,77	676,52	676,52	Ksi3
-20,50	785,28	720,20	720,20	Ksi3
-21,00	835,39	763,41	763,41	Ksi3
-21,50	885,20	806,27	806,27	Ksi3

3.4.5 Results for pile type : Round 510

3.4.5.1 Pile group 1

Number of piles belonging to this pile group : 1
Names of piles belonging to this pile group
1

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	360,04	376,26	360,04	Ksi4
-18,50	375,93	392,15	375,93	Ksi4
-19,00	391,82	408,04	391,82	Ksi4
-19,50	407,71	423,93	407,71	Ksi4
-20,00	423,60	439,82	423,60	Ksi4
-20,50	439,49	455,71	439,49	Ksi4
-21,00	455,38	471,60	455,38	Ksi4
-21,50	471,27	487,49	471,27	Ksi4

3.4.5.2 Pile group 2

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
2
9

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	461,36	450,99	450,99	Ksi3
-18,50	498,74	483,76	483,76	Ksi3
-19,00	533,53	516,61	516,61	Ksi3
-19,50	566,85	547,97	547,97	Ksi3
-20,00	599,32	578,29	578,29	Ksi3
-20,50	631,24	607,89	607,89	Ksi3
-21,00	662,76	636,98	636,98	Ksi3
-21,50	693,96	665,68	665,68	Ksi3

3.4.5.3 Pile group 3

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
3
7

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	461,36	450,99	450,99	Ksi3
-18,50	498,74	483,76	483,76	Ksi3
-19,00	533,53	516,61	516,61	Ksi3
-19,50	566,85	547,97	547,97	Ksi3
-20,00	599,32	578,29	578,29	Ksi3
-20,50	631,24	607,89	607,89	Ksi3
-21,00	662,76	636,98	636,98	Ksi3
-21,50	693,96	665,68	665,68	Ksi3

3.4.5.4 Pile group 4

Number of piles belonging to this pile group : 4
Names of piles belonging to this pile group
4
5
6
8

Level [m R.L.]	Rt;d min [kN]	Rt;d avg [kN]	Rt;d [kN]	Ksi used [-]
-18,00	565,76	537,52	537,52	Ksi3
-18,50	624,27	585,02	585,02	Ksi3
-19,00	680,90	634,13	634,13	Ksi3
-19,50	736,43	682,18	682,18	Ksi3
-20,00	791,27	729,46	729,46	Ksi3
-20,50	845,64	776,18	776,18	Ksi3
-21,00	899,64	822,51	822,51	Ksi3
-21,50	953,35	868,53	868,53	Ksi3

3.5 D C T VE: Results using si3

3.5.1 Results for pile t pe : funde 380 450

3.5.1.1 Pile group 1

Number of piles belonging to this pile group : 1
Names of piles belonging to this pile group
1

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	359,40	376,77	25,01	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,50	381,05	392,95	25,83	0,00
3	-19,00	405,89	409,13	26,64	0,00
3	-19,50	425,31	425,31	27,45	0,00
3	-20,00	441,49	441,49	28,26	0,00
3	-20,50	457,67	457,67	29,07	0,00
3	-21,00	473,84	473,84	29,89	0,00
3	-21,50	490,02	490,02	30,70	0,00
5	-18,00	357,14	386,38	25,01	0,00
5	-18,50	385,47	402,56	25,83	0,00
5	-19,00	411,16	418,73	26,64	0,00
5	-19,50	434,70	434,91	27,45	0,00
5	-20,00	451,09	451,09	28,26	0,00
5	-20,50	467,27	467,27	29,07	0,00
5	-21,00	483,45	483,45	29,89	0,00
5	-21,50	499,63	499,63	30,70	0,00
6	-18,00	340,15	365,37	25,01	0,00
6	-18,50	368,35	381,55	25,83	0,00
6	-19,00	393,81	397,73	26,64	0,00
6	-19,50	413,91	413,91	27,45	0,00
6	-20,00	430,09	430,09	28,26	0,00
6	-20,50	446,27	446,27	29,07	0,00
6	-21,00	462,45	462,45	29,89	0,00
6	-21,50	478,63	478,63	30,70	0,00
8	-18,00	379,70	401,40	25,01	0,00
8	-18,50	403,79	417,58	25,83	0,00
8	-19,00	428,46	433,76	26,64	0,00
8	-19,50	449,94	449,94	27,45	0,00
8	-20,00	466,12	466,12	28,26	0,00
8	-20,50	482,30	482,30	29,07	0,00
8	-21,00	498,48	498,48	29,89	0,00
8	-21,50	514,65	514,65	30,70	0,00
9	-18,00	379,51	379,51	25,01	0,00
9	-18,50	395,69	395,69	25,83	0,00
9	-19,00	411,87	411,87	26,64	0,00
9	-19,50	428,04	428,04	27,45	0,00
9	-20,00	444,22	444,22	28,26	0,00
9	-20,50	460,40	460,40	29,07	0,00
9	-21,00	476,58	476,58	29,89	0,00
9	-21,50	492,76	492,76	30,70	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.1.2 Pile group 2

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
2
9

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	390,42	982,99	25,01	0,00
3	-18,50	417,68	1064,94	25,83	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-19,00	449,93	1151,66	26,64	0,00
3	-19,50	480,65	1243,34	27,45	0,00
3	-20,00	510,12	1340,16	28,26	0,00
3	-20,50	538,61	1442,31	29,07	0,00
3	-21,00	566,35	1549,96	29,89	0,00
3	-21,50	593,51	1663,29	30,70	0,00
5	-18,00	386,19	1037,98	25,01	0,00
5	-18,50	421,14	1122,95	25,83	0,00
5	-19,00	454,01	1212,81	26,64	0,00
5	-19,50	485,22	1307,73	27,45	0,00
5	-20,00	515,11	1407,90	28,26	0,00
5	-20,50	543,98	1513,49	29,07	0,00
5	-21,00	572,04	1624,71	29,89	0,00
5	-21,50	599,48	1741,72	30,70	0,00
6	-18,00	368,52	942,27	25,01	0,00
6	-18,50	403,44	1021,84	25,83	0,00
6	-19,00	436,17	1106,05	26,64	0,00
6	-19,50	467,17	1195,09	27,45	0,00
6	-20,00	496,83	1289,14	28,26	0,00
6	-20,50	525,45	1388,39	29,07	0,00
6	-21,00	553,29	1493,01	29,89	0,00
6	-21,50	580,51	1603,19	30,70	0,00
8	-18,00	417,74	1148,18	25,01	0,00
8	-18,50	448,16	1238,90	25,83	0,00
8	-19,00	480,31	1334,68	26,64	0,00
8	-19,50	510,93	1435,69	27,45	0,00
8	-20,00	540,34	1542,12	28,26	0,00
8	-20,50	568,82	1654,15	29,07	0,00
8	-21,00	596,56	1771,96	29,89	0,00
8	-21,50	623,73	1895,73	30,70	0,00
9	-18,00	431,22	1021,23	25,01	0,00
9	-18,50	461,31	1104,94	25,83	0,00
9	-19,00	490,14	1193,45	26,64	0,00
9	-19,50	518,03	1286,94	27,45	0,00
9	-20,00	545,22	1385,61	28,26	0,00
9	-20,50	571,88	1489,64	29,07	0,00
9	-21,00	598,14	1599,19	29,89	0,00
9	-21,50	624,09	1714,47	30,70	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.1.3 Pile group 3

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
3
7

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	390,42	982,99	25,01	0,00
3	-18,50	417,68	1064,94	25,83	0,00
3	-19,00	449,93	1151,66	26,64	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-19,50	480,65	1243,34	27,45	0,00
3	-20,00	510,12	1340,16	28,26	0,00
3	-20,50	538,61	1442,31	29,07	0,00
3	-21,00	566,35	1549,96	29,89	0,00
3	-21,50	593,51	1663,29	30,70	0,00
5	-18,00	386,19	1037,98	25,01	0,00
5	-18,50	421,14	1122,95	25,83	0,00
5	-19,00	454,01	1212,81	26,64	0,00
5	-19,50	485,22	1307,73	27,45	0,00
5	-20,00	515,11	1407,90	28,26	0,00
5	-20,50	543,98	1513,49	29,07	0,00
5	-21,00	572,04	1624,71	29,89	0,00
5	-21,50	599,48	1741,72	30,70	0,00
6	-18,00	368,52	942,27	25,01	0,00
6	-18,50	403,44	1021,84	25,83	0,00
6	-19,00	436,17	1106,05	26,64	0,00
6	-19,50	467,17	1195,09	27,45	0,00
6	-20,00	496,83	1289,14	28,26	0,00
6	-20,50	525,45	1388,39	29,07	0,00
6	-21,00	553,29	1493,01	29,89	0,00
6	-21,50	580,51	1603,19	30,70	0,00
8	-18,00	417,74	1148,18	25,01	0,00
8	-18,50	448,16	1238,90	25,83	0,00
8	-19,00	480,31	1334,68	26,64	0,00
8	-19,50	510,93	1435,69	27,45	0,00
8	-20,00	540,34	1542,12	28,26	0,00
8	-20,50	568,82	1654,15	29,07	0,00
8	-21,00	596,56	1771,96	29,89	0,00
8	-21,50	623,73	1895,73	30,70	0,00
9	-18,00	431,22	1021,23	25,01	0,00
9	-18,50	461,31	1104,94	25,83	0,00
9	-19,00	490,14	1193,45	26,64	0,00
9	-19,50	518,03	1286,94	27,45	0,00
9	-20,00	545,22	1385,61	28,26	0,00
9	-20,50	571,88	1489,64	29,07	0,00
9	-21,00	598,14	1599,19	29,89	0,00
9	-21,50	624,09	1714,47	30,70	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.1.4 Pile group 4

Number of piles belonging to this pile group : 4
Names of piles belonging to this pile group
4
5
6
8

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	443,08	2452,30	25,01	0,00
3	-18,50	479,21	2715,32	25,83	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-19,00	522,98	2997,44	26,64	0,00
3	-19,50	565,73	3299,38	27,45	0,00
3	-20,00	607,59	3621,88	28,26	0,00
3	-20,50	648,75	3965,67	29,07	0,00
3	-21,00	689,37	4331,48	29,89	0,00
3	-21,50	729,56	4720,04	30,70	0,00
5	-18,00	435,42	2633,80	25,01	0,00
5	-18,50	481,13	2908,91	25,83	0,00
5	-19,00	525,39	3203,55	26,64	0,00
5	-19,50	568,48	3518,45	27,45	0,00
5	-20,00	610,65	3854,34	28,26	0,00
5	-20,50	652,08	4211,95	29,07	0,00
5	-21,00	692,94	4592,02	29,89	0,00
5	-21,50	733,33	4995,27	30,70	0,00
6	-18,00	416,56	2335,10	25,01	0,00
6	-18,50	462,24	2588,58	25,83	0,00
6	-19,00	506,39	2860,64	26,64	0,00
6	-19,50	549,34	3152,02	27,45	0,00
6	-20,00	591,33	3463,44	28,26	0,00
6	-20,50	632,59	3795,63	29,07	0,00
6	-21,00	673,27	4149,33	29,89	0,00
6	-21,50	713,50	4525,26	30,70	0,00
8	-18,00	481,01	3014,45	25,01	0,00
8	-18,50	521,31	3312,56	25,83	0,00
8	-19,00	565,03	3630,88	26,64	0,00
8	-19,50	607,68	3970,14	27,45	0,00
8	-20,00	649,48	4331,07	28,26	0,00
8	-20,50	690,61	4714,40	29,07	0,00
8	-21,00	731,21	5120,86	29,89	0,00
8	-21,50	771,40	5551,18	30,70	0,00
9	-18,00	512,21	2594,32	25,01	0,00
9	-18,50	554,48	2864,36	25,83	0,00
9	-19,00	595,84	3153,62	26,64	0,00
9	-19,50	636,54	3462,83	27,45	0,00
9	-20,00	676,72	3792,72	28,26	0,00
9	-20,50	716,51	4144,02	29,07	0,00
9	-21,00	756,00	4517,47	29,89	0,00
9	-21,50	795,24	4913,79	30,70	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.2 Results for pile type : funde 460/560

3.5.2.1 Pile group 1

Number of piles belonging to this pile group : 1
Names of piles belonging to this pile group
1

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	371,24	371,24	37,78	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,50	387,13	387,13	39,00	0,00
3	-19,00	403,02	403,02	40,23	0,00
3	-19,50	418,91	418,91	41,46	0,00
3	-20,00	434,80	434,80	42,68	0,00
3	-20,50	450,69	450,69	43,91	0,00
3	-21,00	466,58	466,58	45,14	0,00
3	-21,50	482,47	482,47	46,36	0,00
5	-18,00	380,67	380,67	37,78	0,00
5	-18,50	396,56	396,56	39,00	0,00
5	-19,00	412,45	412,45	40,23	0,00
5	-19,50	428,34	428,34	41,46	0,00
5	-20,00	444,23	444,23	42,68	0,00
5	-20,50	460,13	460,13	43,91	0,00
5	-21,00	476,01	476,01	45,14	0,00
5	-21,50	491,90	491,90	46,36	0,00
6	-18,00	360,04	360,04	37,78	0,00
6	-18,50	375,93	375,93	39,00	0,00
6	-19,00	391,82	391,82	40,23	0,00
6	-19,50	407,71	407,71	41,46	0,00
6	-20,00	423,60	423,60	42,68	0,00
6	-20,50	439,49	439,49	43,91	0,00
6	-21,00	455,38	455,38	45,14	0,00
6	-21,50	471,27	471,27	46,36	0,00
8	-18,00	395,43	395,43	37,78	0,00
8	-18,50	411,32	411,32	39,00	0,00
8	-19,00	427,21	427,21	40,23	0,00
8	-19,50	443,10	443,10	41,46	0,00
8	-20,00	458,99	458,99	42,68	0,00
8	-20,50	474,88	474,88	43,91	0,00
8	-21,00	490,77	490,77	45,14	0,00
8	-21,50	506,66	506,66	46,36	0,00
9	-18,00	373,93	373,93	37,78	0,00
9	-18,50	389,82	389,82	39,00	0,00
9	-19,00	405,71	405,71	40,23	0,00
9	-19,50	421,60	421,60	41,46	0,00
9	-20,00	437,49	437,49	42,68	0,00
9	-20,50	453,38	453,38	43,91	0,00
9	-21,00	469,27	469,27	45,14	0,00
9	-21,50	485,16	485,16	46,36	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.2.2 Pile group 2

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
2
9

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	442,54	987,67	37,78	0,00
3	-18,50	470,77	1070,10	39,00	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-19,00	504,08	1157,34	40,23	0,00
3	-19,50	535,79	1249,57	41,46	0,00
3	-20,00	566,36	1346,96	42,68	0,00
3	-20,50	596,14	1449,71	43,91	0,00
3	-21,00	625,38	1557,99	45,14	0,00
3	-21,50	654,21	1671,99	46,36	0,00
5	-18,00	440,63	1042,98	37,78	0,00
5	-18,50	476,44	1128,45	39,00	0,00
5	-19,00	509,98	1218,84	40,23	0,00
5	-19,50	541,92	1314,32	41,46	0,00
5	-20,00	572,72	1415,09	42,68	0,00
5	-20,50	602,72	1521,31	43,91	0,00
5	-21,00	632,14	1633,17	45,14	0,00
5	-21,50	661,13	1750,86	46,36	0,00
6	-18,00	419,95	946,78	37,78	0,00
6	-18,50	456,10	1026,81	39,00	0,00
6	-19,00	489,73	1111,51	40,23	0,00
6	-19,50	521,60	1201,07	41,46	0,00
6	-20,00	552,28	1295,68	42,68	0,00
6	-20,50	582,14	1395,51	43,91	0,00
6	-21,00	611,43	1500,74	45,14	0,00
6	-21,50	640,29	1611,56	46,36	0,00
8	-18,00	471,20	1153,85	37,78	0,00
8	-18,50	503,17	1245,10	39,00	0,00
8	-19,00	536,63	1341,44	40,23	0,00
8	-19,50	568,41	1443,04	41,46	0,00
8	-20,00	599,04	1550,09	42,68	0,00
8	-20,50	628,87	1662,76	43,91	0,00
8	-21,00	658,13	1781,26	45,14	0,00
8	-21,50	686,98	1905,74	46,36	0,00
9	-18,00	480,64	1026,15	37,78	0,00
9	-18,50	512,32	1110,35	39,00	0,00
9	-19,00	542,66	1199,38	40,23	0,00
9	-19,50	572,14	1293,42	41,46	0,00
9	-20,00	601,06	1392,67	42,68	0,00
9	-20,50	629,58	1497,30	43,91	0,00
9	-21,00	657,80	1607,50	45,14	0,00
9	-21,50	685,81	1723,44	46,36	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.2.3 Pile group 3

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
3
7

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	442,54	987,67	37,78	0,00
3	-18,50	470,77	1070,10	39,00	0,00
3	-19,00	504,08	1157,34	40,23	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-19,50	535,79	1249,57	41,46	0,00
3	-20,00	566,36	1346,96	42,68	0,00
3	-20,50	596,14	1449,71	43,91	0,00
3	-21,00	625,38	1557,99	45,14	0,00
3	-21,50	654,21	1671,99	46,36	0,00
5	-18,00	440,63	1042,98	37,78	0,00
5	-18,50	476,44	1128,45	39,00	0,00
5	-19,00	509,98	1218,84	40,23	0,00
5	-19,50	541,92	1314,32	41,46	0,00
5	-20,00	572,72	1415,09	42,68	0,00
5	-20,50	602,72	1521,31	43,91	0,00
5	-21,00	632,14	1633,17	45,14	0,00
5	-21,50	661,13	1750,86	46,36	0,00
6	-18,00	419,95	946,78	37,78	0,00
6	-18,50	456,10	1026,81	39,00	0,00
6	-19,00	489,73	1111,51	40,23	0,00
6	-19,50	521,60	1201,07	41,46	0,00
6	-20,00	552,28	1295,68	42,68	0,00
6	-20,50	582,14	1395,51	43,91	0,00
6	-21,00	611,43	1500,74	45,14	0,00
6	-21,50	640,29	1611,56	46,36	0,00
8	-18,00	471,20	1153,85	37,78	0,00
8	-18,50	503,17	1245,10	39,00	0,00
8	-19,00	536,63	1341,44	40,23	0,00
8	-19,50	568,41	1443,04	41,46	0,00
8	-20,00	599,04	1550,09	42,68	0,00
8	-20,50	628,87	1662,76	43,91	0,00
8	-21,00	658,13	1781,26	45,14	0,00
8	-21,50	686,98	1905,74	46,36	0,00
9	-18,00	480,64	1026,15	37,78	0,00
9	-18,50	512,32	1110,35	39,00	0,00
9	-19,00	542,66	1199,38	40,23	0,00
9	-19,50	572,14	1293,42	41,46	0,00
9	-20,00	601,06	1392,67	42,68	0,00
9	-20,50	629,58	1497,30	43,91	0,00
9	-21,00	657,80	1607,50	45,14	0,00
9	-21,50	685,81	1723,44	46,36	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.2.4 Pile group 4

Number of piles belonging to this pile group : 4
Names of piles belonging to this pile group
4
5
6
8

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	520,99	2486,08	37,78	0,00
3	-18,50	561,78	2751,91	39,00	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-19,00	611,19	3036,95	40,23	0,00
3	-19,50	659,51	3341,93	41,46	0,00
3	-20,00	707,00	3667,60	42,68	0,00
3	-20,50	753,89	4014,67	43,91	0,00
3	-21,00	800,36	4383,89	45,14	0,00
3	-21,50	846,50	4775,97	46,36	0,00
5	-18,00	513,83	2669,37	37,78	0,00
5	-18,50	565,10	2947,36	39,00	0,00
5	-19,00	614,76	3244,99	40,23	0,00
5	-19,50	663,27	3563,00	41,46	0,00
5	-20,00	710,95	3902,13	42,68	0,00
5	-20,50	758,02	4263,10	43,91	0,00
5	-21,00	804,64	4646,64	45,14	0,00
5	-21,50	850,92	5053,48	46,36	0,00
6	-18,00	491,37	2367,55	37,78	0,00
6	-18,50	542,86	2623,75	39,00	0,00
6	-19,00	592,56	2898,65	40,23	0,00
6	-19,50	641,00	3192,99	41,46	0,00
6	-20,00	688,58	3507,49	42,68	0,00
6	-20,50	735,53	3842,88	43,91	0,00
6	-21,00	782,03	4199,89	45,14	0,00
6	-21,50	828,20	4579,26	46,36	0,00
8	-18,00	564,10	3053,49	37,78	0,00
8	-18,50	609,88	3354,58	39,00	0,00
8	-19,00	659,41	3676,01	40,23	0,00
8	-19,50	707,74	4018,50	41,46	0,00
8	-20,00	755,24	4382,77	42,68	0,00
8	-20,50	802,13	4769,57	43,91	0,00
8	-21,00	848,59	5179,62	45,14	0,00
8	-21,50	894,72	5613,65	46,36	0,00
9	-18,00	597,30	2629,20	37,78	0,00
9	-18,50	645,51	2902,07	39,00	0,00
9	-19,00	692,75	3194,27	40,23	0,00
9	-19,50	739,35	3506,54	41,46	0,00
9	-20,00	785,51	3839,62	42,68	0,00
9	-20,50	831,34	4194,22	43,91	0,00
9	-21,00	876,93	4571,09	45,14	0,00
9	-21,50	922,33	4970,95	46,36	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.3 Results for pile t pe : DP 410

3.5.3.1 Pile group 1

Number of piles belonging to this pile group : 1
Names of piles belonging to this pile group
1

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	357,10	377,02	24,41	0,00

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,50	378,82	393,21	25,21	0,00
3	-19,00	403,78	409,40	26,00	0,00
3	-19,50	425,60	425,60	26,79	0,00
3	-20,00	441,79	441,79	27,59	0,00
3	-20,50	457,98	457,98	28,38	0,00
3	-21,00	474,18	474,18	29,17	0,00
3	-21,50	490,37	490,37	29,96	0,00
5	-18,00	354,68	386,63	24,41	0,00
5	-18,50	383,08	402,83	25,21	0,00
5	-19,00	408,90	419,02	26,00	0,00
5	-19,50	432,57	435,21	26,79	0,00
5	-20,00	451,40	451,40	27,59	0,00
5	-20,50	467,60	467,60	28,38	0,00
5	-21,00	483,79	483,79	29,17	0,00
5	-21,50	499,98	499,98	29,96	0,00
6	-18,00	337,86	365,61	24,41	0,00
6	-18,50	366,12	381,80	25,21	0,00
6	-19,00	391,69	398,00	26,00	0,00
6	-19,50	414,19	414,19	26,79	0,00
6	-20,00	430,38	430,38	27,59	0,00
6	-20,50	446,57	446,57	28,38	0,00
6	-21,00	462,77	462,77	29,17	0,00
6	-21,50	478,96	478,96	29,96	0,00
8	-18,00	377,49	401,67	24,41	0,00
8	-18,50	401,63	417,87	25,21	0,00
8	-19,00	426,39	434,06	26,00	0,00
8	-19,50	449,24	450,25	26,79	0,00
8	-20,00	466,44	466,44	27,59	0,00
8	-20,50	482,63	482,63	28,38	0,00
8	-21,00	498,83	498,83	29,17	0,00
8	-21,50	515,02	515,02	29,96	0,00
9	-18,00	379,53	379,76	24,41	0,00
9	-18,50	395,95	395,95	25,21	0,00
9	-19,00	412,14	412,14	26,00	0,00
9	-19,50	428,34	428,34	26,79	0,00
9	-20,00	444,53	444,53	27,59	0,00
9	-20,50	460,72	460,72	28,38	0,00
9	-21,00	476,92	476,92	29,17	0,00
9	-21,50	493,11	493,11	29,96	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for sand and gravel are adjusted for the coarsness of the actual soil (sand when D50 > 0.6mm; gravel when D50 > 2 mm).
Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.3.2 Pile group 2

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
2
9

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	387,35	982,70	24,41	0,00
3	-18,50	414,54	1064,63	25,21	0,00
3	-19,00	446,73	1151,32	26,00	0,00
3	-19,50	477,39	1242,97	26,79	0,00
3	-20,00	506,79	1339,76	27,59	0,00
3	-20,50	535,22	1441,87	28,38	0,00
3	-21,00	562,89	1549,49	29,17	0,00
3	-21,50	589,98	1662,79	29,96	0,00
5	-18,00	383,02	1037,67	24,41	0,00
5	-18,50	417,89	1122,62	25,21	0,00
5	-19,00	450,70	1212,45	26,00	0,00
5	-19,50	481,85	1307,34	26,79	0,00
5	-20,00	511,69	1407,47	27,59	0,00
5	-20,50	540,51	1513,04	28,38	0,00
5	-21,00	568,51	1624,21	29,17	0,00
5	-21,50	595,87	1741,18	29,96	0,00
6	-18,00	365,53	942,00	24,41	0,00
6	-18,50	400,36	1021,54	25,21	0,00
6	-19,00	433,01	1105,72	26,00	0,00
6	-19,50	463,95	1194,74	26,79	0,00
6	-20,00	493,56	1288,76	27,59	0,00
6	-20,50	522,12	1387,97	28,38	0,00
6	-21,00	549,89	1492,56	29,17	0,00
6	-21,50	577,03	1602,70	29,96	0,00
8	-18,00	414,60	1147,84	24,41	0,00
8	-18,50	444,92	1238,54	25,21	0,00
8	-19,00	476,99	1334,28	26,00	0,00
8	-19,50	507,54	1435,26	26,79	0,00
8	-20,00	536,88	1541,65	27,59	0,00
8	-20,50	565,29	1653,64	28,38	0,00
8	-21,00	592,96	1771,42	29,17	0,00
8	-21,50	620,05	1895,16	29,96	0,00
9	-18,00	428,32	1020,93	24,41	0,00
9	-18,50	458,33	1104,61	25,21	0,00
9	-19,00	487,08	1193,09	26,00	0,00
9	-19,50	514,89	1286,56	26,79	0,00
9	-20,00	541,99	1385,20	27,59	0,00
9	-20,50	568,56	1489,19	28,38	0,00
9	-21,00	594,72	1598,71	29,17	0,00
9	-21,50	620,57	1713,95	29,96	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for sand and gravel are adjusted for the coarsness of the actual soil (sand when D50 > 0.6mm; gravel when D50 > 2 mm).
Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.3.3 Pile group 3

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
3
7

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	387,35	982,70	24,41	0,00
3	-18,50	414,54	1064,63	25,21	0,00
3	-19,00	446,73	1151,32	26,00	0,00
3	-19,50	477,39	1242,97	26,79	0,00
3	-20,00	506,79	1339,76	27,59	0,00
3	-20,50	535,22	1441,87	28,38	0,00
3	-21,00	562,89	1549,49	29,17	0,00
3	-21,50	589,98	1662,79	29,96	0,00
5	-18,00	383,02	1037,67	24,41	0,00
5	-18,50	417,89	1122,62	25,21	0,00
5	-19,00	450,70	1212,45	26,00	0,00
5	-19,50	481,85	1307,34	26,79	0,00
5	-20,00	511,69	1407,47	27,59	0,00
5	-20,50	540,51	1513,04	28,38	0,00
5	-21,00	568,51	1624,21	29,17	0,00
5	-21,50	595,87	1741,18	29,96	0,00
6	-18,00	365,53	942,00	24,41	0,00
6	-18,50	400,36	1021,54	25,21	0,00
6	-19,00	433,01	1105,72	26,00	0,00
6	-19,50	463,95	1194,74	26,79	0,00
6	-20,00	493,56	1288,76	27,59	0,00
6	-20,50	522,12	1387,97	28,38	0,00
6	-21,00	549,89	1492,56	29,17	0,00
6	-21,50	577,03	1602,70	29,96	0,00
8	-18,00	414,60	1147,84	24,41	0,00
8	-18,50	444,92	1238,54	25,21	0,00
8	-19,00	476,99	1334,28	26,00	0,00
8	-19,50	507,54	1435,26	26,79	0,00
8	-20,00	536,88	1541,65	27,59	0,00
8	-20,50	565,29	1653,64	28,38	0,00
8	-21,00	592,96	1771,42	29,17	0,00
8	-21,50	620,05	1895,16	29,96	0,00
9	-18,00	428,32	1020,93	24,41	0,00
9	-18,50	458,33	1104,61	25,21	0,00
9	-19,00	487,08	1193,09	26,00	0,00
9	-19,50	514,89	1286,56	26,79	0,00
9	-20,00	541,99	1385,20	27,59	0,00
9	-20,50	568,56	1489,19	28,38	0,00
9	-21,00	594,72	1598,71	29,17	0,00
9	-21,50	620,57	1713,95	29,96	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for sand and gravel are adjusted for the coarsness of the actual soil (sand when D50 > 0.6mm; gravel when D50 > 2 mm).
Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.3.4 Pile group 4

Number of piles belonging to this pile group : 4
Names of piles belonging to this pile group
4
5
6
8

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	438,78	2450,49	24,41	0,00
3	-18,50	474,65	2713,37	25,21	0,00
3	-19,00	518,12	2995,33	26,00	0,00
3	-19,50	560,56	3297,11	26,79	0,00
3	-20,00	602,12	3619,44	27,59	0,00
3	-20,50	642,98	3963,06	28,38	0,00
3	-21,00	683,30	4328,69	29,17	0,00
3	-21,50	723,18	4717,06	29,96	0,00
5	-18,00	431,10	2631,90	24,41	0,00
5	-18,50	476,50	2906,86	25,21	0,00
5	-19,00	520,45	3201,34	26,00	0,00
5	-19,50	563,25	3516,07	26,79	0,00
5	-20,00	605,12	3851,79	27,59	0,00
5	-20,50	646,26	4209,23	28,38	0,00
5	-21,00	686,82	4589,11	29,17	0,00
5	-21,50	726,91	4992,17	29,96	0,00
6	-18,00	412,45	2333,36	24,41	0,00
6	-18,50	457,80	2586,70	25,21	0,00
6	-19,00	501,64	2858,61	26,00	0,00
6	-19,50	544,29	3149,83	26,79	0,00
6	-20,00	585,98	3461,09	27,59	0,00
6	-20,50	626,94	3793,11	28,38	0,00
6	-21,00	667,32	4146,63	29,17	0,00
6	-21,50	707,25	4522,38	29,96	0,00
8	-18,00	476,43	3012,36	24,41	0,00
8	-18,50	516,43	3310,32	25,21	0,00
8	-19,00	559,84	3628,47	26,00	0,00
8	-19,50	602,18	3967,56	26,79	0,00
8	-20,00	643,67	4328,31	27,59	0,00
8	-20,50	684,50	4711,46	28,38	0,00
8	-21,00	724,80	5117,73	29,17	0,00
8	-21,50	764,67	5547,85	29,96	0,00
9	-18,00	507,55	2592,46	24,41	0,00
9	-18,50	549,49	2862,35	25,21	0,00
9	-19,00	590,54	3151,45	26,00	0,00
9	-19,50	630,93	3460,50	26,79	0,00
9	-20,00	670,80	3790,22	27,59	0,00
9	-20,50	710,27	4141,35	28,38	0,00
9	-21,00	749,44	4514,61	29,17	0,00
9	-21,50	788,36	4910,74	29,96	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for sand and gravel are adjusted for the coarsness of the actual soil (sand when D50 > 0.6mm; gravel when D50 > 2 mm).
Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.4 Results for pile t□ pe : DP□ 460

3.5.4.1 Pile group 1

Number of piles belonging to this pile group : 1
Names of piles belonging to this pile group
1

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	374,33	374,33	30,73	0,00
3	-18,50	390,38	390,38	31,73	0,00
3	-19,00	406,43	406,43	32,73	0,00
3	-19,50	422,48	422,48	33,73	0,00
3	-20,00	438,53	438,53	34,72	0,00
3	-20,50	454,58	454,58	35,72	0,00
3	-21,00	470,63	470,63	36,72	0,00
3	-21,50	486,68	486,68	37,72	0,00
5	-18,00	377,44	383,86	30,73	0,00
5	-18,50	399,91	399,91	31,73	0,00
5	-19,00	415,96	415,96	32,73	0,00
5	-19,50	432,01	432,01	33,73	0,00
5	-20,00	448,06	448,06	34,72	0,00
5	-20,50	464,11	464,11	35,72	0,00
5	-21,00	480,16	480,16	36,72	0,00
5	-21,50	496,21	496,21	37,72	0,00
6	-18,00	359,03	363,03	30,73	0,00
6	-18,50	379,08	379,08	31,73	0,00
6	-19,00	395,13	395,13	32,73	0,00
6	-19,50	411,18	411,18	33,73	0,00
6	-20,00	427,23	427,23	34,72	0,00
6	-20,50	443,27	443,27	35,72	0,00
6	-21,00	459,32	459,32	36,72	0,00
6	-21,50	475,37	475,37	37,72	0,00
8	-18,00	397,45	398,77	30,73	0,00
8	-18,50	414,82	414,82	31,73	0,00
8	-19,00	430,87	430,87	32,73	0,00
8	-19,50	446,92	446,92	33,73	0,00
8	-20,00	462,97	462,97	34,72	0,00
8	-20,50	479,02	479,02	35,72	0,00
8	-21,00	495,07	495,07	36,72	0,00
8	-21,50	511,12	511,12	37,72	0,00
9	-18,00	377,05	377,05	30,73	0,00
9	-18,50	393,10	393,10	31,73	0,00
9	-19,00	409,15	409,15	32,73	0,00
9	-19,50	425,20	425,20	33,73	0,00
9	-20,00	441,25	441,25	34,72	0,00
9	-20,50	457,30	457,30	35,72	0,00
9	-21,00	473,35	473,35	36,72	0,00
9	-21,50	489,40	489,40	37,72	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for sand and gravel are adjusted for the coarsness of the actual soil (sand when D50 > 0.6mm; gravel when D50 > 2 mm).
Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.4.2 Pile group 2

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
2
9

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	416,49	985,37	30,73	0,00
3	-18,50	444,26	1067,56	31,73	0,00
3	-19,00	477,05	1154,53	32,73	0,00
3	-19,50	508,24	1246,48	33,73	0,00
3	-20,00	538,21	1343,58	34,72	0,00
3	-20,50	567,27	1446,02	35,72	0,00
3	-21,00	595,66	1553,97	36,72	0,00
3	-21,50	623,56	1667,63	37,72	0,00
5	-18,00	413,28	1040,52	30,73	0,00
5	-18,50	448,79	1125,74	31,73	0,00
5	-19,00	482,06	1215,85	32,73	0,00
5	-19,50	513,64	1311,05	33,73	0,00
5	-20,00	543,95	1411,50	34,72	0,00
5	-20,50	573,32	1517,40	35,72	0,00
5	-21,00	601,97	1628,93	36,72	0,00
5	-21,50	630,08	1746,27	37,72	0,00
6	-18,00	394,11	944,57	30,73	0,00
6	-18,50	429,73	1024,36	31,73	0,00
6	-19,00	462,95	1108,82	32,73	0,00
6	-19,50	494,39	1198,11	33,73	0,00
6	-20,00	524,52	1292,43	34,72	0,00
6	-20,50	553,69	1391,96	35,72	0,00
6	-21,00	582,16	1496,87	36,72	0,00
6	-21,50	610,10	1607,36	37,72	0,00
8	-18,00	444,42	1151,04	30,73	0,00
8	-18,50	475,63	1242,02	31,73	0,00
8	-19,00	508,45	1338,07	32,73	0,00
8	-19,50	539,64	1439,37	33,73	0,00
8	-20,00	569,62	1546,10	34,72	0,00
8	-20,50	598,71	1658,44	35,72	0,00
8	-21,00	627,13	1776,58	36,72	0,00
8	-21,50	655,05	1900,70	37,72	0,00
9	-18,00	455,83	1023,73	30,73	0,00
9	-18,50	486,68	1107,68	31,73	0,00
9	-19,00	516,21	1196,44	32,73	0,00
9	-19,50	544,82	1290,20	33,73	0,00
9	-20,00	572,80	1389,15	34,72	0,00
9	-20,50	600,30	1493,47	35,72	0,00
9	-21,00	627,47	1603,34	36,72	0,00
9	-21,50	654,38	1718,94	37,72	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for sand and gravel are adjusted for the coarsness of the actual soil (sand when D50 > 0.6mm; gravel when D50 > 2 mm).
Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.4.3 Pile group 3

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
3
7

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	416,49	985,37	30,73	0,00
3	-18,50	444,26	1067,56	31,73	0,00
3	-19,00	477,05	1154,53	32,73	0,00
3	-19,50	508,24	1246,48	33,73	0,00
3	-20,00	538,21	1343,58	34,72	0,00
3	-20,50	567,27	1446,02	35,72	0,00
3	-21,00	595,66	1553,97	36,72	0,00
3	-21,50	623,56	1667,63	37,72	0,00
5	-18,00	413,28	1040,52	30,73	0,00
5	-18,50	448,79	1125,74	31,73	0,00
5	-19,00	482,06	1215,85	32,73	0,00
5	-19,50	513,64	1311,05	33,73	0,00
5	-20,00	543,95	1411,50	34,72	0,00
5	-20,50	573,32	1517,40	35,72	0,00
5	-21,00	601,97	1628,93	36,72	0,00
5	-21,50	630,08	1746,27	37,72	0,00
6	-18,00	394,11	944,57	30,73	0,00
6	-18,50	429,73	1024,36	31,73	0,00
6	-19,00	462,95	1108,82	32,73	0,00
6	-19,50	494,39	1198,11	33,73	0,00
6	-20,00	524,52	1292,43	34,72	0,00
6	-20,50	553,69	1391,96	35,72	0,00
6	-21,00	582,16	1496,87	36,72	0,00
6	-21,50	610,10	1607,36	37,72	0,00
8	-18,00	444,42	1151,04	30,73	0,00
8	-18,50	475,63	1242,02	31,73	0,00
8	-19,00	508,45	1338,07	32,73	0,00
8	-19,50	539,64	1439,37	33,73	0,00
8	-20,00	569,62	1546,10	34,72	0,00
8	-20,50	598,71	1658,44	35,72	0,00
8	-21,00	627,13	1776,58	36,72	0,00
8	-21,50	655,05	1900,70	37,72	0,00
9	-18,00	455,83	1023,73	30,73	0,00
9	-18,50	486,68	1107,68	31,73	0,00
9	-19,00	516,21	1196,44	32,73	0,00
9	-19,50	544,82	1290,20	33,73	0,00
9	-20,00	572,80	1389,15	34,72	0,00
9	-20,50	600,30	1493,47	35,72	0,00
9	-21,00	627,47	1603,34	36,72	0,00
9	-21,50	654,38	1718,94	37,72	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for sand and gravel are adjusted for the coarsness of the actual soil (sand when D50 > 0.6mm; gravel when D50 > 2 mm).
Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.4.4 Pile group 4

Number of piles belonging to this pile group : 4
Names of piles belonging to this pile group
4
5
6
8

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	480,85	2468,43	30,73	0,00
3	-18,50	519,22	2732,78	31,73	0,00
3	-19,00	565,70	3016,28	32,73	0,00
3	-19,50	611,10	3319,68	33,73	0,00
3	-20,00	655,61	3643,68	34,72	0,00
3	-20,50	699,47	3989,03	35,72	0,00
3	-21,00	742,83	4356,45	36,72	0,00
3	-21,50	785,81	4746,69	37,72	0,00
5	-18,00	473,37	2650,78	30,73	0,00
5	-18,50	521,82	2927,25	31,73	0,00
5	-19,00	568,70	3223,31	32,73	0,00
5	-19,50	614,38	3539,70	33,73	0,00
5	-20,00	659,16	3877,12	34,72	0,00
5	-20,50	703,25	4236,33	35,72	0,00
5	-21,00	746,81	4618,05	36,72	0,00
5	-21,50	789,96	5023,01	37,72	0,00
6	-18,00	452,75	2350,59	30,73	0,00
6	-18,50	501,27	2605,36	31,73	0,00
6	-19,00	548,10	2878,78	32,73	0,00
6	-19,50	593,67	3171,56	33,73	0,00
6	-20,00	638,31	3484,44	34,72	0,00
6	-20,50	682,25	3818,16	35,72	0,00
6	-21,00	725,66	4173,43	36,72	0,00
6	-21,50	768,67	4550,99	37,72	0,00
8	-18,00	521,22	3033,07	30,73	0,00
8	-18,50	564,16	3332,60	31,73	0,00
8	-19,00	610,67	3652,40	32,73	0,00
8	-19,50	656,04	3993,19	33,73	0,00
8	-20,00	700,54	4355,71	34,72	0,00
8	-20,50	744,39	4740,69	35,72	0,00
8	-21,00	787,75	5148,85	36,72	0,00
8	-21,50	830,73	5580,93	37,72	0,00
9	-18,00	553,29	2610,97	30,73	0,00
9	-18,50	598,37	2882,35	31,73	0,00
9	-19,00	642,52	3173,01	32,73	0,00
9	-19,50	686,00	3483,67	33,73	0,00
9	-20,00	729,00	3815,08	34,72	0,00
9	-20,50	771,65	4167,95	35,72	0,00
9	-21,00	814,02	4543,02	36,72	0,00
9	-21,50	856,18	4941,02	37,72	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for sand and gravel are adjusted for the coarsness of the actual soil (sand when D50 > 0.6mm; gravel when D50 > 2 mm).
Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.5 Results for pile t: pe : Round 510

3.5.5.1 Pile group 1

Number of piles belonging to this pile group : 1
Names of piles belonging to this pile group
1

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18.00	371,24	371,24	37,78	0,00
3	-18,50	387,13	387,13	39,00	0,00
3	-19.00	403,02	403,02	40,23	0,00
3	-19.50	418,91	418,91	41,46	0,00
3	-20.00	434,80	434,80	42,68	0,00
3	-20.50	450,69	450,69	43,91	0,00
3	-21.00	466,58	466,58	45,14	0,00
3	-21.50	482,47	482,47	46,36	0,00
5	-18,00	380,67	380,67	37,78	0,00
5	-18.50	396,56	396,56	39,00	0,00
5	-19,00	412,45	412,45	40,23	0,00
5	-19.50	428,34	428,34	41,46	0,00
5	-20,00	444,23	444,23	42,68	0,00
5	-20,50	460,13	460,13	43,91	0,00
5	-21,00	476,01	476,01	45,14	0,00
5	-21,50	491,90	491,90	46,36	0,00
6	-18,00	360,04	360,04	37,78	0,00
6	-18,50	375,93	375,93	39,00	0,00
6	-19,00	391,82	391,82	40,23	0,00
6	-19,50	407,71	407,71	41,46	0,00
6	-20,00	423,60	423,60	42,68	0,00
6	-20,50	439,49	439,49	43,91	0,00
6	-21,00	455,38	455,38	45,14	0,00
6	-21,50	471,27	471,27	46,36	0,00
8	-18,00	395,43	395,43	37,78	0,00
8	-18,50	411,32	411,32	39,00	0,00
8	-19,00	427,21	427,21	40,23	0,00
8	-19,50	443,10	443,10	41,46	0,00
8	-20,00	458,99	458,99	42,68	0,00
8	-20,50	474,88	474,88	43,91	0,00
8	-21,00	490,77	490,77	45,14	0,00
8	-21,50	506,66	506,66	46,36	0,00
9	-18,00	373,93	373,93	37,78	0,00
9	-18,50	389,82	389,82	39,00	0,00
9	-19,00	405,71	405,71	40,23	0,00
9	-19,50	421,60	421,60	41,46	0,00
9	-20,00	437,49	437,49	42,68	0,00
9	-20,50	453,38	453,38	43,91	0,00
9	-21,00	469,27	469,27	45,14	0,00
9	-21,50	485,16	485,16	46,36	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.5.2 Pile group 2

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
2
9

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	442,54	987,67	37,78	0,00
3	-18,50	470,77	1070,10	39,00	0,00
3	-19,00	504,08	1157,34	40,23	0,00
3	-19,50	535,79	1249,57	41,46	0,00
3	-20,00	566,36	1346,96	42,68	0,00
3	-20,50	596,14	1449,71	43,91	0,00
3	-21,00	625,38	1557,99	45,14	0,00
3	-21,50	654,21	1671,99	46,36	0,00
5	-18,00	440,63	1042,98	37,78	0,00
5	-18,50	476,44	1128,45	39,00	0,00
5	-19,00	509,98	1218,84	40,23	0,00
5	-19,50	541,92	1314,32	41,46	0,00
5	-20,00	572,72	1415,09	42,68	0,00
5	-20,50	602,72	1521,31	43,91	0,00
5	-21,00	632,14	1633,17	45,14	0,00
5	-21,50	661,13	1750,86	46,36	0,00
6	-18,00	419,95	946,78	37,78	0,00
6	-18,50	456,10	1026,81	39,00	0,00
6	-19,00	489,73	1111,51	40,23	0,00
6	-19,50	521,60	1201,07	41,46	0,00
6	-20,00	552,28	1295,68	42,68	0,00
6	-20,50	582,14	1395,51	43,91	0,00
6	-21,00	611,43	1500,74	45,14	0,00
6	-21,50	640,29	1611,56	46,36	0,00
8	-18,00	471,20	1153,85	37,78	0,00
8	-18,50	503,17	1245,10	39,00	0,00
8	-19,00	536,63	1341,44	40,23	0,00
8	-19,50	568,41	1443,04	41,46	0,00
8	-20,00	599,04	1550,09	42,68	0,00
8	-20,50	628,87	1662,76	43,91	0,00
8	-21,00	658,13	1781,26	45,14	0,00
8	-21,50	686,98	1905,74	46,36	0,00
9	-18,00	480,64	1026,15	37,78	0,00
9	-18,50	512,32	1110,35	39,00	0,00
9	-19,00	542,66	1199,38	40,23	0,00
9	-19,50	572,14	1293,42	41,46	0,00
9	-20,00	601,06	1392,67	42,68	0,00
9	-20,50	629,58	1497,30	43,91	0,00
9	-21,00	657,80	1607,50	45,14	0,00
9	-21,50	685,81	1723,44	46,36	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.5.3 Pile group 3

Number of piles belonging to this pile group : 2
Names of piles belonging to this pile group
3
7

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	442,54	987,67	37,78	0,00
3	-18,50	470,77	1070,10	39,00	0,00
3	-19,00	504,08	1157,34	40,23	0,00
3	-19,50	535,79	1249,57	41,46	0,00
3	-20,00	566,36	1346,96	42,68	0,00
3	-20,50	596,14	1449,71	43,91	0,00
3	-21,00	625,38	1557,99	45,14	0,00
3	-21,50	654,21	1671,99	46,36	0,00
5	-18,00	440,63	1042,98	37,78	0,00
5	-18,50	476,44	1128,45	39,00	0,00
5	-19,00	509,98	1218,84	40,23	0,00
5	-19,50	541,92	1314,32	41,46	0,00
5	-20,00	572,72	1415,09	42,68	0,00
5	-20,50	602,72	1521,31	43,91	0,00
5	-21,00	632,14	1633,17	45,14	0,00
5	-21,50	661,13	1750,86	46,36	0,00
6	-18,00	419,95	946,78	37,78	0,00
6	-18,50	456,10	1026,81	39,00	0,00
6	-19,00	489,73	1111,51	40,23	0,00
6	-19,50	521,60	1201,07	41,46	0,00
6	-20,00	552,28	1295,68	42,68	0,00
6	-20,50	582,14	1395,51	43,91	0,00
6	-21,00	611,43	1500,74	45,14	0,00
6	-21,50	640,29	1611,56	46,36	0,00
8	-18,00	471,20	1153,85	37,78	0,00
8	-18,50	503,17	1245,10	39,00	0,00
8	-19,00	536,63	1341,44	40,23	0,00
8	-19,50	568,41	1443,04	41,46	0,00
8	-20,00	599,04	1550,09	42,68	0,00
8	-20,50	628,87	1662,76	43,91	0,00
8	-21,00	658,13	1781,26	45,14	0,00
8	-21,50	686,98	1905,74	46,36	0,00
9	-18,00	480,64	1026,15	37,78	0,00
9	-18,50	512,32	1110,35	39,00	0,00
9	-19,00	542,66	1199,38	40,23	0,00
9	-19,50	572,14	1293,42	41,46	0,00
9	-20,00	601,06	1392,67	42,68	0,00
9	-20,50	629,58	1497,30	43,91	0,00
9	-21,00	657,80	1607,50	45,14	0,00
9	-21,50	685,81	1723,44	46,36	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

3.5.5.4 Pile group 4

Number of piles belonging to this pile group : 4
Names of piles belonging to this pile group
4
5
6
8

CPT name	Level [m R.L.]	Rt;d Indicative [kN]	Max. mobilized soil weight [kN]	Pile weight [kN]	Tension derived from clay [%]
3	-18,00	520,99	2486,08	37,78	0,00
3	-18,50	561,78	2751,91	39,00	0,00
3	-19,00	611,19	3036,95	40,23	0,00
3	-19,50	659,51	3341,93	41,46	0,00
3	-20,00	707,00	3667,60	42,68	0,00
3	-20,50	753,89	4014,67	43,91	0,00
3	-21,00	800,36	4383,89	45,14	0,00
3	-21,50	846,50	4775,97	46,36	0,00
5	-18,00	513,83	2669,37	37,78	0,00
5	-18,50	565,10	2947,36	39,00	0,00
5	-19,00	614,76	3244,99	40,23	0,00
5	-19,50	663,27	3563,00	41,46	0,00
5	-20,00	710,95	3902,13	42,68	0,00
5	-20,50	758,02	4263,10	43,91	0,00
5	-21,00	804,64	4646,64	45,14	0,00
5	-21,50	850,92	5053,48	46,36	0,00
6	-18,00	491,37	2367,55	37,78	0,00
6	-18,50	542,86	2623,75	39,00	0,00
6	-19,00	592,56	2898,65	40,23	0,00
6	-19,50	641,00	3192,99	41,46	0,00
6	-20,00	688,58	3507,49	42,68	0,00
6	-20,50	735,53	3842,88	43,91	0,00
6	-21,00	782,03	4199,89	45,14	0,00
6	-21,50	828,20	4579,26	46,36	0,00
8	-18,00	564,10	3053,49	37,78	0,00
8	-18,50	609,88	3354,58	39,00	0,00
8	-19,00	659,41	3676,01	40,23	0,00
8	-19,50	707,74	4018,50	41,46	0,00
8	-20,00	755,24	4382,77	42,68	0,00
8	-20,50	802,13	4769,57	43,91	0,00
8	-21,00	848,59	5179,62	45,14	0,00
8	-21,50	894,72	5613,65	46,36	0,00
9	-18,00	597,30	2629,20	37,78	0,00
9	-18,50	645,51	2902,07	39,00	0,00
9	-19,00	692,75	3194,27	40,23	0,00
9	-19,50	739,35	3506,54	41,46	0,00
9	-20,00	785,51	3839,62	42,68	0,00
9	-20,50	831,34	4194,22	43,91	0,00
9	-21,00	876,93	4571,09	45,14	0,00
9	-21,50	922,33	4970,95	46,36	0,00

CPT name	Alpha t aver. overall	Alpha t aver. sand/gravel	Alpha t aver. clay/peat/loam
3	0,0088	0,0090	0,0000
5	0,0089	0,0090	0,0000
6	0,0089	0,0090	0,0000
8	0,0089	0,0090	0,0000
9	0,0090	0,0090	0,0000

Please note that User defined values for Alpha t for clay are adjusted when the profile does not entiarly consists of peat/clay. Also note that Alpha t for peat is 0.

End of Report