© This drawing is subject to copyright of Kay Elliott Architects Ltd.
For Construction purposes, contractors must work to figured dimensions only. All dimensions and sizes to be checked by the Contractor on site and discrepancies verified before work proceeds.

ISO9001:2015 & ISO14001:2015 Registered

RIBA Chartered Practice

0m 5m 10m

Scale 1:100

LEGEND

- EXIT TO PROTECTED CORRIDOR OR FINAL EXIT FROM ATTRACTION. MAXIMUM 30m TRAVEL DISTANCE.
- EXIT — FIRE EXIT DOOR WITH APPROPRIATE IRONMONGERY TO LATER SPECIFICATION FOR AL LNEW DOORS.
- 30 MINUTE FIRE RESISTING CORRIDOR WITH ALL WALLS, DOORS & CEILINGS APPROPRIATELY RATED, TO LATER SPECIFICATION.
- HOSE REEL — HOSE REELS. 3 TO BE RELOCATED AS NOTED. TO REACH 30m.

NOTE:

FIRE STRATEGY TO BE CHECKED AND APPROVED BY VELDWEG.

FIRE ALARAM PANEL LOCATION TO BE AGREED.

- Luchttoevoer
- Luchtafvoer
- Overstroom
- 1770 Luchtvolumestroom in m³/h

opleveringspunt van de verhuurer
Luchttoevoer en Luchtafvoer
TP 1.VD-1 max. beschikbaar

opleveringspunt van de verhuurer
Luchttoevoer en Luchtafvoer
TP 1.VD-2 max. beschikbaar

opleveringspunt van de verhuurer
Luchttoevoer en Luchtafvoer
TP BG max. beschikbaar

OP DE INSTALLTIES zijn de volgende normen o.a. van toepassing op het ontwerp en de uitvoering.

- NEN-EN 12831 transmissieberekeningen (tevens gelden ook ISSO 53 en 57);
- NEN 2916 energieprestatie van utiliteitsgebouwen;
- NEN-ISO 7730 thermische behaaglijkheid;
- ISSO 50 verwarmingsinstallatie;
- ISSO 17 berekening en ontwerp luchtkanalen;
- ISSO 18 berekening en ontwerp leidingen;
- ISSO 31 meten en inregelen klimaatinstallaties;
- ISSO 55 tapwaterinstallaties in woon- en utiliteitsgebouwen;
- ISSO 55.1 handleiding legionella preventie;
- ISSO 55.2 handleiding zorgplicht legionella preventie;
- NEN 1006 algemene voorschriften voor leidingwaterinstallaties;
- NEN 1610 buitenriolering inclusief Nederlandse aanvulling NEN 3218-1;
- NEN 3215 gebouwriolering en buitenriolering binnen perceelgrenzen;
- NTR 3216 riolering voor bouwwerken;
- NEN-EN 378 eisen koelinstallaties en warmtepompen;
- NEN 1010 eisen elektrische installaties voor laagspanning;
- alle overige niet nader genoemde geldende NEN en ISSO normen;
- kwaliteitseisen voor de uitvoering van luchtkanalen LUKA.

1ste VERDIEPING
1 : 100

BEGANE GROND
1 : 100

PRELIMINARY

rev.	date	name	description

HUTH engineering GmbH
Südstraße 6
D-58332 Schwelm
Fon +49 170 2447959

client
Madame Tussauds Amsterdam

project
Madame Tussauds Amsterdam
Kalverpassage, Amsterdam, NL

scale	project no.	name	create date
1:100	*2404*	*rhu*	*29.01.2025*

content / area /craft
INSTALLATIES - VENTILATIE

begane grond + 1ste verdieping

phase	drawing no. / revision	revision date
Aanvraag	*A-V-FP01*	*29.01.2025*

file name: *2404 mtam anfrag - ventilatie concept preliminary 29.01.2025.dwg*